

City of Albuquerque

P.O. BOX 1293 ALBUQUERQUE, NEW MEXICO 87103

HYDROLOGY SECTION 123 Central NW, Albuquerque, NM 87102 (505) 766-7644

August 26, 1986

Steve Clark
Weiss/Hines Engineering, Inc.
1100 Alvarado, NE Suite B
Albuquerque, New Mexico 87110

RE: DRAINAGE & GRADING PLAN SUBMITTAL OF VISTA MONTAND NORTH SUBDIVISION - RECEIVED AUGUST 15, 1986 FOR PRELIMINARY PLAT APPROVAL (E-11/D15A)

Dear Steve:

The above referenced submittal, dated August 15, 1986, is approved for Preliminary Plat.

Before Final Plat sign-off by the City Engineer, the following items are required:

- 1. An executed Subdivision Improvements Agreement.
- The downstream Drainage Easement across Tract 25D for the 30" S.D. must be granted to the City of Albuquerque. Bellamah Development Company currently has an easement from the owners of Tract 25D, but this needs to be assigned to the City as a public drainage easement. This is presently in the process of being done.

If you have any questions, call me at 766-7644.

Cordially,

Roger A. Green, P.E. C.E./Hydrology Section

cc: Andre Houle, DRC


RAG/bsj


Walter Nickerson, P.E., City Engineer

PUBLIC WORKS DEPARTMENT

ENGINEERING GROUP


Telephone (505) 768-2500






VICINITY MAP

E-11





1" = 20'

TYPICAL LOT GRADING PLAN

swales to drain backyards towards the fronts of the lots and into streets. LEGAL: Lots 6 and 7 of Block 1, Lots 1, 2, and 7-10 of Block 2, and Lots 19-30 of Block 3, Vista Montano Subdivision.

boundary and will be extended through the development.

The intent of this plan is to show:

SURVEYOR: Elder Company Surveying, 530 Jefferson N.E., ALbuquerque, NM. July, 1986.

The proposed improvements are comprised of a 20-unit residential single-dwelling development including paved streets, roll curbs, sidewalks, houses and associated

The Present site is undeveloped vacant land surrounded by residential subdivisions. Existing surrounding public streets and utilities have been brought to the subdivision

a) Grading relationships between the existing ground elevations and proposed finished elevations in order to facilitate positive drainage to designated

b) The extent of proposed site improvements, including buildings, walks and

c) The flow rate/volume of rainfall runoff across or around these improvements and

d) The relationship of onsite improvements with existing neighboring property to insure an orderly transition between proposed and surrounding grades.

GENERAL NOTES: The site will be graded so that all flows will drain past the eastern property line in Desert Sands Place NW, thence to the storm sewer inlet located in the cul-de-sac at the southern end of Woodhollow Place NW. Individual lots will have shallow

methods of handling these flows to meet City requirements for drainage

 $\underline{\text{T.B.M.:}}$ Top of curb (north) on Desert Sand Place at east property line. Elevation = 5,112.05'.

B.M.: NE corner of Section 26, T11N, R2E, NMPM Brass Cap monument in place in concrete.

SOILS: SCS Soils Map #20 (Bernalillo County, NM). Soil is type 'MWA', Hydrologic Soil Group 'B'.

FLOOD HAZARD: FEMA Map #14. Due to the construction of the Mariposa Detention FAcility, the site has been removed from the flood plain.

OFF-SITE DRAINAGE: Concrete block walls block flows from the north and west. Approximately 0.7 acres of the residential development to the south (Vista Cielo Ave.) drain into the site in Vista Sierra and Vista Montano Streets. No flows enter the site from the east.

EROSION CONTROL: Contractor shall be responsible for containing sediment generated during construction by use of a temporary earth berm or silt fence constructed across the site's eastern outlet.

RATIONAL METHOD- Q = CIA (ON-SITE)

- Area of site: 197,014 sq.ft. = 4.5 Ac.

Run-off Coefficient:

Existing site: Undeveloped Area = $197,014 \text{ ft}^2$

 $\frac{\text{Developed Site:}}{\text{Roof Area} = 49,500 ft'}$ Landscaped Area = 107,229 ft² Paved Area = 40,285 ft²

 $C_p = \frac{40,285(0.95)}{197,014} = \frac{0.19}{197}$

Composite C = 0.40Composite C = 0.56

Rainfall Intensity:

 $I = P_6 (6.84) T^{-0.51} = 4.65$ " per hour where $P_6 = 2.2$ "(DPM 22.2 D-1) $T_6 = 10$ minutes

Existing Condition:

 $Q_{100} = (0.40)(4.65)(4.5)$ = 8.4 cfs $V_{100} = (8.4)(50T_c)(60 \text{ sec/min})/2$ $V_{100} = (11.7)(50)(60)/2$ = 12,555 cu. ft.

 $Q_{100} = (0.56)(4.65)(4.5)$ = 11.7 cfs

Developed Condition:

of Rupoff seconds.

T= TOTAL DURATION

Area: Vista Sierra Street, Vista Montano Street, ½ of Vista Cielo Avenue, and fronts of adjoining lots.

Existing off-site: Landscaped Area = 17,884 ft² Paved Area = 11,616 ft² $C_1 = \frac{17,884(0.25)}{29,590} = 0.15$

RATIONAL METHOD- Q = CIA (OFF-SITE)

 $C_p = \frac{11,616(0.90)}{29,500} = \frac{0.35}{}$ Composite C = 0.50

 $Q_{100} = (0.50)(4.65)(0.68)$ = 1.6 cfs $V_{100} = (1.6)(50T_c)(60 \text{ sec/min})/2$ = 2,400 cu.cft.

Total Flows (Developed): . 17,550 cu.ft. 11.7 cfs On-site 2,400 cu.ft. 19,950 cu.ft. $\frac{1.6 \text{ cfs}}{13.3 \text{ cfs}}$ Off-site

SUMMARY:

 $Q_{100} = (13.3) - (8.4) = 4.9 \text{ cfs (increase)}$ $v_{100} = (19,950) - (12,555) = 7,395 \text{ cu.ft. (increase)}$

