

AS BUILT INFORMATION

CONTRACTOR

DATE

INSPECTOR'S ACCEPTANCE BY

DATE

FIELD VERIFICATION BY

DATE

DRAWINGS BY

DATE

RECORDED BY

DATE

NO.

GRADING KEVED NOTES

1. INSTALL 30 PIPE, HOPE N-12WT OR APPROVED EQUAL. SIZES PER PLAN.

2. INSTALL SINGLE COA TYPE 'D' STORM DRAIN INLET (OR APPROVED EQUAL) PER COA STD DWG 2206.

3. INSTALL DOUBLE COA TYPE 'D' STORM DRAIN INLET (OR APPROVED EQUAL) PER COA STD DWG 2206.

4. REMOVE EXISTING STORM DRAIN STRUCTURE AND INSTALL 6" DIA TYPE 'E' MANHOLE WITH GRATED COVER PER COA STD DWG 2102. MODIFY WITH WATER QUALITY SNOOT PER DETAIL A1, SHEET 9. CONTRACTOR TO VERIFY EXISTING INVERT AND CONTACT ENGINEER WITH ANY DISCREPANCIES.

5. INSTALL SINGLE 24" SIDEWALK CULVERT PER COA STD DWG 2236.

6. WATER QUALITY SWALE PER DETAIL A2, SHEET 9.

7. INSTALL RIP RAP/BASALT SWALE (DIMENSIONS PER PLAN) PER DETAIL A3, SHEET 9.

8. INSTALL DRAINAGE DIVERSION BERM PER DETAIL A4, SHEET 9.

9. MATCH EXISTING.

ENGINEER'S SEAL

NO.

DATE

SURVEY INFORMATION

FIELD NOTES

LEGEND

PROPERTY LINE

PROJECT LIMITS OF GRADING

EXISTING INDEX CONTOUR

EXISTING INTERMEDIATE CONTOUR

EXISTING GROUND ELEVATION

PROPOSED GROUND ELEVATION

FL=FLOW LINE, TC=TOP OF CURB

TS=TOP OF SIDEWALK,

TC=TOP OF GRATE,

FG=FINISH GROUND

DIRECTION OF FLOW

GRADE BREAK/WATER BLOCK

PROPOSED INDEX CONTOUR

PROPOSED INTERMEDIATE CONTOUR

PROPOSED CURB & GUTTER

PROPOSED STORM DRAIN LINE

PROPOSED STORM DRAIN MANHOLE

PROPOSED STORM DRAIN INLETS

PROPOSED BERM

Scale: 1" = 30'

NORTH

15

0

30

60

BOHANNAN & HUSTON

www.bhinc.com

800.877.5332

CONSENSUS PLANNING, INC.

Planning / Landscape Architecture

302 Eighth Street NW

Albuquerque, NM 87102

842-5465

(505) 764-8801

e-mail: op@consensusplanning.com

RECORD DRAWINGS

PROJECT #

PHASE 1

DATE

12/2013

DATE

11/2013

DATE

11/2013

DESIGNED BY

BHW

DRAWN BY

BHW

CHECKED BY

JLM

NO.

DATE

REMARKS

BY

REVISIONS

DESIGN

VISTA DEL NORTE PARK

FINAL FOR CONSTRUCTION

X

City Project No.	Zone Map No.	Sheet	8	of	18
City Engineer Approval		Last Design Update			
Design Review Committee		City Engineer Approval			
TITLE:		VISTA DEL NORTE PARK GRADING PLAN			
CITY OF ALBUQUERQUE PARKS AND RECREATION DEPARTMENT STRATEGIC PLANNING AND DESIGN DIVISION		DESIGNED BY: BHW DRAWN BY: BHW CHECKED BY: JLM DATE: 11/2013 DATE: 11/2013 DATE: 12/2013			