



GENERAL SHEET NOTES

- DO NOT SCALE DRAWINGS.
- ALL DOOR/WINDOW/DECORATIVE INTERIOR TRIMMING TO MATCH EXT'G
- ALL RESTROOM DOORS SHALL BE EQUIPPED WITH SELF CLOSING MECHANISMS

SHEET KEYNOTES

- POSTED SIGN - VIOLATORS SUBJECT TO A FINE AND
OR TOWING
POSTED SIGN - SEE NOTE 2 & 3. SEE DETAIL
E6/AS101
NO PARKING (ALL CAPS)
BIKE RACK-SEE NOTE 9 & 10. SEE DETAIL C6/AS101
CURRENT WASTE ENCLOSURE TO REMAIN

NOTES

NOTE 1: EXISTING LANDSCAPE AND SIGNAGE TO REMAIN. ALL NEW LANDSCAPING AND SIGNAGE WILL NOT INTERFERE WITH CLEAR SIGHT REQUIREMENTS. THEREFORE, SIGNS, WALLS, TREES, AND SHRUBBERY BETWEEN 3 AND 8 FEET TALL (AS MEASURED FROM THE GUTTER PAN) WILL NOT BE ACCEPTABLE IN THE CLEAR SIGHT TRIANGLE.

NOTE 2: SIGNAGE FOR ADA MUST BE IN ALL CAPS - "NO PARKING" EACH OF WHICH SHALL BE AT LEAST ONE FOOT HIGH AND AT LEAST TWO INCHES WIDE, PLACED AT THE REAR OF THE PARKING SPACE SO AS TO BE CLOSE TO WHERE AN ADJACENT VEHICLES REAR TIRE WOULD BE PLACED.

NOTE 3: SIGNAGE FOR ADA PARKING MUST BE
IN ALL CAPS – "VIOLATORS ARE SUBJECT TO A
FINE AND/OR TOWING"

NOTE 4: OWNER PROVIDED. BIKE RACK SHALL BE MINIMUM 30" TALL AND 18" WIDE. RACK SHALL BE SUPPORTED 2 OR MORE PLACES. COMB/TOASTER RACKS NOT ALLOWED. RACK DESIGNED TO SUPPORT BIKE IN UPRIGHT POSITION. RACK MUST ALLOW VARYING BIKE FRAMES/STYLES. USER NOT REQUIRED TO LIFT BIKE ONTO RACK. EACH BIKE PARKING SPACE ACCESSIBLE W/OUT MOVING ANOTHER BIKE.

NOTE 5: BIKE RACK STURDY/ANCHORED TO CONCRETE PAD W/1'-0" CLEAR ZONE.

NOTE 6: ADA SUPPORT FOR CUSTOMER SERVICE SHALL BE PROVIDED BY STAFF AS NEEDED INDEPENDENTLY FOR ANY CUSTOMER NEEDING ASSISTANCE.

Pen n y Design, LLC
302 SANDIARDEN
ALBUQUERQUE, NEW MEXICO 87107
505 . 280 . 5439

THRIVE DISPENSARY
5926 2ND STREET
Albuquerque, New Mexico 87107

[illegible]

AS101