

# CITY OF ALBUQUERQUE



August 22, 2012

Philip W. Clark, P.E.  
**Clark Consulting Engineers**  
19 Ryan Road  
Edgewood, NM 87015

[CCEalbq@aol.com](mailto:CCEalbq@aol.com)

**Re: Earthday Recycling, 112 Headingly Ave. NW,  
Request for Permanent C.O. – Not Accepted  
Engineer's Stamp dated: 01-05-12, (G15/D105)  
Certification dated: 08-16-12**

Dear Mr. Clark,

Based upon the information provided in the Certification received 08-21-12, the above referenced Certification is not accepted for release of Permanent Certificate of Occupancy by Hydrology.

PO Box 1293

Albuquerque

NM 87103

[www.cabq.gov](http://www.cabq.gov)

1. The Engineer's certifying language will need to be per the DPM, see attached sample.
2. All pond volumes require certification. Please provide the north and south pond volume.
3. After a recent site visit, it appears some asphaltic material was placed in the south pond. The fill will affect the volume and may cause flows to leave the site to the east and west. The approved plan calls for 690 cf of storage. Please clarify the grades in this area.
4. Additional certified spot elevations are required for permanent certificate of occupancy acceptance by hydrology.
5. The as-built plan should reflect as constructed conditions.
  - a. The landscape area adjacent to the entrance drive was not built.
  - b. Plan should note all walls that are not constructed.

To improve certification quality, Hydrology is requiring on onsite meeting after the comments have been addressed. Please contact Tim Sims at 924-3982 to schedule the meeting.

If you have any questions, you can contact me at 924-3986.

Sincerely,

Curtis Cherne, P.E.  
Principal Engineer—Hydrology, Planning Dept.  
Development and Building Services  
C: e-mail

DRAINAGE CERT W/ SURVEY WORK BY OTHERS  
12/28/01

DRAINAGE CERTIFICATION

I, \_\_\_\_\_, NMPE \_\_\_\_\_, OF THE FIRM \_\_\_\_\_,  
HEREBY CERTIFY THAT THIS PROJECT HAS BEEN GRADED AND WILL DRAIN IN  
SUBSTANTIAL COMPLIANCE WITH AND IN ACCORDANCE WITH THE DESIGN INTENT OF  
THE APPROVED PLAN DATED \_\_\_\_\_. THE RECORD INFORMATION EDITED ONTO THE  
ORIGINAL DESIGN DOCUMENT HAS BEEN OBTAINED BY  
NMPS \_\_\_\_\_, OF THE FIRM \_\_\_\_\_. I FURTHER CERTIFY THAT I HAVE  
PERSONALLY VISITED THE PROJECT SITE ON \_\_\_\_\_ AND HAVE DETERMINED BY  
VISUAL INSPECTION THAT THE SURVEY DATA PROVIDED IS REPRESENTATIVE OF  
ACTUAL SITE CONDITIONS AND IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE  
AND BELIEF. THIS CERTIFICATION IS SUBMITTED IN SUPPORT OF A REQUEST FOR  
\_\_\_\_\_.

(DESCRIBE ANY EXCEPTIONS AND/OR QUALIFICATIONS HERE IN A SEPARATE  
PARAGRAPH)

(DESCRIBE ANY DEFICIENCIES AND/OR REQUIRED CORRECTIONS HERE IN A SEPARATE  
PARAGRAPH)

THE RECORD INFORMATION PRESENTED HEREON IS NOT NECESSARILY COMPLETE AND  
INTENDED ONLY TO VERIFY SUBSTANTIAL COMPLIANCE OF THE GRADING AND  
DRAINAGE ASPECTS OF THIS PROJECT. THOSE RELYING ON THIS RECORD DOCUMENT  
ARE ADVISED TO OBTAIN INDEPENDENT VERIFICATION OF ITS ACCURACY BEFORE USING  
IT FOR ANY OTHER PURPOSE.

(SEAL)

XXXXXXXXXXXXXXXXXX, NMPE XXXX

\_\_\_\_\_  
DATE

APPROVED BY THE EXECUTIVE COMMITTEE ON 4/9/02