
DRAINAGE INFORMATION SHEET

4-Plex PROJECT TITLE:Warran Shaffer Apartments No. 276	NE ATLAS/DRNG. FILE #: G-16/DGB-			
PROJECT TITLE:Warren Shaffer Apartments No 270NE ATLAS/DRNG. FILE #: G-16/D66				
LEGAL DESCRIPTION: Lot 10, Block 2, Indian Acres Subdivision CITY ADDRESS: 3400 Wellesley Drive, NE				
ENGINEERING FIRM: Lovelady & Associates				
ADDRESS: 7408 Morrow Road, N.E.87110	PHONE: 883-7973			
OWNER: Warren Shaffer:	CONTACT: Warren Shaffer			
ADDRESS: 5736 Osuna Drive NE	PHONE: 888-2928			
ARCHITECT: Jerry Torr & Associates	CONTACT: Jerry Torr			
ADDRESS: 5736 Osuna Road NE	PHONE: 884-7713			
SURVEYOR: N/A	CONTACT:			
ADDRESS:	PHONE:			
CONTRACTOR: N/A	CONTACT:			
ADDRESS:	PHONE:			
X COPY OF CONFERENCE RECAP FEB 1 9 1985	RB NOROJ. NO			
TYPE OF SUBMITTAL: HYDROLOGY SECTIVED	K TYPE OF APPROVAL SOUGHT:			
	SKETCH PLAT APPROVAL			
	PRELIMINARY PLAT APPROVAL			
,	SITE DEVELOPMENT PLAN APPROVAL FINAL PLAT APPROVAL			
	BUILDING PERMIT APPROVAL			
	FOUNDATION PERMIT APPROVAL			
	CERTIFICATE OF OCCUPANCY APPROVAL			
MONTOYA/BERNIE J. MONTOYA LETTER OF FEB. 12, 1985	ROUGH GRADING PERMIT APPROVAL			
	GRADING/PAVING PERMIT APPROVAL			
Magazina di producti di produc	OTHER (SPECIFY)			
DATE SUBMITTED: February 18, 1985				
BY: Frank D. Lovelady, P.E.				



" Minus Gravel Erosion Protection "Thick

ADDITIONAL CALCULATIONS:

SWALE - EACH SWALE IS TO CARRY ONE-HALF OF ALL DRAINAGE EAST OF THE PARKING LOT.

 $Q_{100} = 0.58$ cfs The ratio of area east of parking lot to total area is approximately 79/134 = 0.59

 $Q_{swale} = 0.58 \times 0.59 \times 0.5 = 0.17 \text{ cfs}$

Try swale 6" deep with 6:1 side slopes. Per Mannings Eqution (HP41cv Program "V-DITCH") D = 0.20 feet flow depth Z = 6:1 side slopes N = 0.035S = 0.0092 ft/ft

Q = 0.21 cfs. > 0.17 cfs. (Capacity is adequate)


V = 0.87 fps (Velocity is non-erodable)

CONSTRUCTION NOTES:

- 1. TWO (2) WORKING DAYS PRIOR TO ANY EXCAVATION, CONTRACTOR MUST CONTACT LINE LOCATING SERVICE AT 765-1234 FOR LOCATION OF EXISTING UTILITIES.
- 2. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL EXCAVATE AND VERIFY THE HORIZONTAL AND VERTICAL LOCATION OF ALL POTENTIAL OBSTRUCTIONS; SHOULD A CONFLICT EXIST, THE CONTRACTOR SHALL NOTIFY THE ENGINEER SO THAT THE CONFLICT CAN BE RE-SOLVED WITH A MINIMUM AMOUNT OF DELAY.
- ALL WORK ON THIS PROJECT SHALL BE PERFORMED IN ACCORDANCE WITH APPLICABLE FEDERAL, STATE, AND LOCAL LAWS, RULES, AND REGULATIONS CONCERNING CONSTRUCTION SAFETY AND HEALTH.
- 4. ALL CONSTRUCTION WITHIN CITY RIGHT-OF-WAY SHALL BE PERFORMED IN ACCORDANCE WITH APPLICABLE CITY OF ALBUQUERQUE STANDARDS AND PROCEDURES.

EROSION AND SEDIMENTATION CONTROL:

THE CONTRACTOR IS RESPONSIBLE FOR EROSION AND SEDIMENTATION CONTROL DURING CONSTRUCTION. THE CONTRACTOR MUST PREVENT ALL SOIL-BEARING WATER GENERATED ON THE SITE FROM ENTERING THE AD-JACENT STREET. IN THE EVENT THAT SEDIMENT FROM THE SITE REACHES THE STREET, THE CONTRACTOR SHALL COMPLETELY AND THOROUGHLY REMOVE SAME WITHOUT DELAY.



LEGAL DESCRIPTION:

A CERTAIN TRACT OR PARCEL OF LAND SITUATED WITHIN THE CITY LIMITS OF THE CITY OF ALBUQUERQUE, BERNALILLO COUNTY, NEW MEXICO: BEING AND COMPRISING LOT 10, BLOCK 2, INDIAN ACRES SUBDIVISION, A SUBDIVISION OF THE CITY OF ALBUQUERQUE, NEW MEXICO.

LEGEND: DESCRIPTION FLOW DIRECTION CONTOUR SPOT ELEVATION PROPERTY LINE ROOF DRAIN TC - TOP CURB TA = TOP ASPHALTFL = FLOW LINE

BENCH MARK:

STATION IS LOCATED 3.4 MI. NE OF DOWNTOWN ALBUQUERQUE AT THE INTERSECTION OF AZTEC ROAD AND LAFAYETTE DRIVE, IN THE SW QUAD-RANT OF THE INTERSECTION.

STATION IS 31.8 FT. SOUTH OF CENTERLINE ON AZTEC ROAD AND 30.6 FEET WEST OF CENTERLINE ON LAFAYETTE DRIVE.

STATION MARK IS A STANDARD USC&GS BRASS CAP SET IN TOP OF CON-CRETE POST FLUSH WITH THE GROUND AND STAMPED "P-225, 1951" ELEV-ATION 5099.957

TEMPORARY BENCH MARK (TBM) IS THE WEST TOP BONNET BOLT OF THE FIRE HYDRANT LOCATED NEAR THE NNW CURB RETURN OF WELLESLEY DRIVE, NE AND AZTEC DRIVE NE: ELEVATION 5109.68.

Drainage Calculations

I. REFERENCES:

- A. City of Albuquerque Development Process Manual (DPM) Volume 2, Design Criteria, Chapter 22, Drainage, Flood Control and Erosion Control.
- B. Soil Survey of Bernalillo County and Parts of Sandoval and Valencia Counties, New Mexico, United States Department of Agriculture, Soil Conservation Service.

II. GENERAL INFORMATION:

- A. Soil Type (Ref.B., Page 21)Soil type is EmB, Embudo gravelly fine sandy loam, 0 to 5 percent slopes. The Hydrologic Soil Group is "B".
- B. Imperviousness:

Tune of Curtose	Existing Area Sq.Ft. Acres	Proposed Area Sq.Ft. Acres
Type of Surface		
Building roof	N/A	2.400
Concrete Surfaces	11	384
Asphalt Surfaces	11	2,732
Landscaping	**	1,188
Undeveloped surface	7,891	1,187
Site total	7,891 0.1812	7,891 0.1812
Percent impervious	0%	70%

- C. "C" Factor (See Ref. A., Plate 22.2 C-1) Undeveloped "C" Factor = 0.34
 Developed "C" Factor = 0.66
- D. Rainfall, 100-year, 6-hour, R₆; (See Ref.A., Plate $22.2 D-1) R_6 = 2.2 inches.$
- E. Time of Consentration, T; Use the minimum time of concentration of 10 minutes.
- F. Rainfall Intensity, I; (See Ref. A, Plate 22.2 D-2) $I = R_{6} \times 6.84 \times T_{c}^{-0.51} = 2.2 \times 6.84 \times (10)^{-0.51} = 4.85 \text{ inches per hour.}$

III. PEAK DISCHARGE:


- A. Existing Conditions. $Q_{100} = 0.34 \times 4.65 \times 0.1812 = 0.28 \text{ cfs}$ $Q_{10} = 0.657 \times 0.28 = 0.19 \text{ cfs}$ B. Developed Conditions.
- $Q_{100} = 0.66 \times 4.65 \times 0.1812 = 0.58 \text{ cfs}$ $Q_{10} = 0.657 \times 0.58 = 0.38 \text{ cfs}$

IV. ANALYSIS OF DOWNSTREAM CONDITIONS:

- A. Determine the peak discharge of the total drainage basin of which this site is a part and check the capacity of the existing channel which runs north from Aztec Road beginning at a point approximately 150 feet west of Lafayette Drive and ends in a ponding area near the intersection of Commanche Road and the North Diversion Channel:
- B. Area = 54.89 acres. Overland flow time, T-1, (See Plate 22.2 B-1) curve for paved areas, slope is 1%: Velocity = 1.35 fps; L = 450
 - $T-1 = \frac{450}{(1.35 \times 60)} = 5.6 \text{ min.};$ Street flow time (Plate 22.2 B-2) street length = 1,800'; Slope = (5134 - 5090)/1800 = 0.0244 or 2.44 %. Velocity = 4.2 fps. $T-2 = 1800/(4.2 \times 60) = 7.1$ $T_{C} = T-1 + T-2 = 12.7$ minutes.
 - $I = 2.2 \times 6.84 (12.7)^{-0.51} = 4.12$ inches per hour. Peak discharge by Rational Equation: Q = CIA
 - Assume developed "C" = 0.80 $Q = 0.8 \times 4.12 \times 54.89 = 180.9 \text{ cfs.}$
- C. Channel capacity. Average channel cross section is unlined, 12-foot bottom width $1\frac{1}{2}$:1 side slopes, depth of 8 ft.; slope = 2/230 = 0.0087'/'; Assume flow depth of 2.5 feet A = 39.4 P = 21; R = 39.4/ 21 = 1.87
- $Q = 39.4(1.486/0.035)(1.87)^{2/3}(0.0087)^{1/2} = 236$ 236 cfs>180.9 cfs; therefore the channel has adequate capacity with only 2 foot depth, or 6 feet of freeboard.

v. conclusions:

- 1. Adequate downstream capacity exists and, therefore, unrestricted discharge from the site is acceptable.
- 2. The site does not lie within any flood hazard areas.
- 3. The site ,in both its existing and proposed conditions, is not subject to offsite flows crossing the side or rear lot lines. Minimal flows that may enter the property from the east are accepted.



GRADING & DRAINAGE PLAN FOR

SHAFFER APARTMENTS NO.2 (4-PLEX) (3400 Wellesley Drive, N. E.) Albuquerque, New Mexico

