CITY OF ALBUQUERQUE



Richard J. Berry, Mayor

July 26, 2017

Scott Steffen, PE Bohannan Huston, Inc. 7500 Jefferson St NE Albuquerque, NM 87109

RE: Sawmill Village Phase 2

Grading Plan

Stamp Date: 7/24/17

Hydrology File: H13D025A C

Dear Mr. Steffen:

PO Box 1293

Based upon the information provided in your submittal received 7/24/17, the Grading Plan **is not** approved for Building Permit. The following comments need to be addressed for approval of the above referenced project:

Albuquerque

1. Please provide the required 0.87' water block per COA Paving Detail No. 2426.

New Mexico 87103

2. Please provide the three point chart for each driveway radius per COA Paving Detail No. 2426.

www.cabq.gov

3. Please provide a section through the proposed building and existing adjacent pond. Please label the elevations of the top of pond, the bottom of pond and the 100 year WSE.

I have attached the COA Paving Detail No. 2426 and the proposed section for your use.

If you have any questions, please contact me at 924-3995 or rbrissette@cabq.gov.


Sincerely,

Reneé C. Brissette, P.E.

Senior Engineer, Hydrology

Reneé C. Brissetto


Planning Department



SECTION A.A. Job of 7042 5960,00 BOTHWOLF BUND

ELLA KEMOIKEMENIS MITH RESPECT I

- VERTICAL LOCATIONS OF ALL POTENTI UTILITIES. SHOULD A CONFLICT EXIST OBSERVER OR ENGINEER SO THAT THI AMOUNT OF DELAY. PRIOR TO CONSTRUCTION, THE CO
- 4. TWO (2) WORKING DAYS PRIOR TO LINE LOCATING SERVICE FOR LOCATION
- CREWS. UTILITY CREWS TO PERFORM THEIR REQ COORDINATION OF ALL NECESSARY UTIL WILL BE ALLOWED FOR DELAYS OR INC APPURTENANCES ENCOUNTERED DURING BE COORDINATED WITH THAT UTILITY. ALL ELECTRICAL, TELEPHONE, CABI THE CONTRACTOR MAY BE RE
- BY THE CONSTRUCTION OBSERVER. ACTIVITY SHALL BE REPAIRED OR REPLA THE CONSTRUCTION AREA. ANY DAMA(THE CONTRACTOR IS RESPONSIBLE
- SHALL BE REPAIRED OR REPLACED AT T 7. CONSTRUCTION ACTIVITY SHALL BE ANY DAMAGE TO ADJACENT PROPERTIES
- 8. OVERNIGHT PARKING OF CONSTRUCTI DESIGNATED TRAFFIC LANES. THE CONTI MATERIAL WITHIN THE PUBLIC RIGHT-OF-
- PERMITS, EPA STORM WATER PERMITS, ET TO COMMENCING CONSTRUCTION (I.E., BAI THE CONTRACTOR SHALL OBTAIN ALL
- ALL PROPERTY CORNERS DESTROYED





City of Albuquerque


Planning Department

Development & Building Services Division

DRAINAGE AND TRANSPORTATION INFORMATION SHEET (REV 09/2015)

Project Title:	Building Permit #: City Drainage #:
DRB#: EPC#:	
Legal Description:	
City Address:	
Engineering Firm:	Contact:
Address:	
Phone#: Fax#:	E-mail:
Owner:	Contact:
Address:	
Phone#: Fax#:	
Architect:	Contact:
Address:	
Phone#: Fax#:	E-mail:
Other Contact:	Contact:
Address:	
Phone#: Fax#:	E-mail:
DEPARTMENT: HYDROLOGY/ DRAINAGE TRAFFIC/ TRANSPORTATION MS4/ EROSION & SEDIMENT CONTROL	CHECK TYPE OF APPROVAL/ACCEPTANCE SOUGHT: BUILDING PERMIT APPROVAL CERTIFICATE OF OCCUPANCY
	32.11.16.112 61 6666111161
TYPE OF SUBMITTAL: ENGINEER/ ARCHITECT CERTIFICATION	PRELIMINARY PLAT APPROVAL
ENGINEER/ ARCHITECT CERTIFICATION	SITE PLAN FOR SUB'D APPROVAL
CONCEPTUAL G & D PLAN	SITE PLAN FOR BLDG. PERMIT APPROVAL
GRADING PLAN	FINAL PLAT APPROVAL SIA/ RELEASE OF FINANCIAL GUARANTEE
DRAINAGE MASTER PLAN	FOUNDATION PERMIT APPROVAL
DRAINAGE REPORT	GRADING PERMIT APPROVAL
CLOMR/LOMR	SO-19 APPROVAL
	PAVING PERMIT APPROVAL
TRAFFIC CIRCULATION LAYOUT (TCL)	GRADING/ PAD CERTIFICATION
TRAFFIC IMPACT STUDY (TIS)	WORK ORDER APPROVAL
EROSION & SEDIMENT CONTROL PLAN (ESC)	CLOMR/LOMR
OTHER (SPECIFY)	PRE-DESIGN MEETING
	OTHER (SPECIFY)
IS THIS A RESUBMITTAL?: Yes No	
DATE SUBMITTED:By:	
•	

COA STAFF: ELECTRONIC SUBMITTAL RECEIVED: ____



July 24, 2017 - 7:22am

GRADING NOTES

- 1. EXCEPT AS PROVIDED HEREIN, GRADING SHALL BE PERFORMED AT THE ELEVATIONS AND IN ACCORDANCE WITH THE DETAILS SHOWN ON THIS PLAN.
- 2. THE COST FOR REQUIRED CONSTRUCTION DUST AND EROSION CONTROL MEASURES SHALL BE INCIDENTAL TO THE PROJECT COST.
- 3. ALL WORK RELATIVE TO FOUNDATION CONSTRUCTION, SITE PREPARATION, AND PAVEMENT INSTALLATION, AS SHOWN ON THIS PLAN, SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE "GEOTECHNICAL INVESTIGATION," AS PROVIDED BY THE ARCHITECT OR OWNER. ALL OTHER WORK SHALL, UNLESS OTHERWISE STATED OR PROVIDED FOR HEREON, BE CONSTRUCTED IN ACCORDANCE WITH THE PROJECT, (FIRST PRIORITY) SPECIFICATIONS, AND/OR THE CITY OF ALBUQUERQUE (COA) STANDARD SPECIFICATIONS FOR PUBLIC WORKS (SECOND PRIORITY).
- 4. EARTH SLOPES SHALL NOT EXCEED 3 HORIZONTAL TO 1 VERTICAL UNLESS SHOWN
- 5. IT IS THE INTENT OF THESE PLANS THAT THIS CONTRACTOR SHALL NOT PERFORM ANY WORK OUTSIDE OF THE PROPERTY BOUNDARIES EXCEPT AS REQUIRED BY THIS PLAN.
- 6. THE CONTRACTOR IS TO ENSURE THAT NO SOIL ERODES FROM THE SITE ONTO ADJACENT PROPERTY OR PUBLIC RIGHT-OF-WAY. THIS SHOULD BE ACHIEVED BY CONSTRUCTING TEMPORARY BERMS OR SILT FENCE AT THE PROPERTY LINES AND WETTING THE SOIL TO PROTECT IT FROM WIND EROSION.
- 7. A DISPOSAL SITE FOR ANY & ALL EXCESS EXCAVATION MATERIAL, AND UNSUITABLE MATERIAL AND/OR A BORROW SITE CONTAINING ACCEPTABLE FILL MATERIAL SHALL BE OBTAINED BY THE CONTRACTOR IN COMPLIANCE WITH APPLICABLE ENVIRONMENTAL REGULATIONS AND APPROVED BY THE OBSERVER. ALL COSTS INCURRED IN OBTAINING A DISPOSAL OR BORROW SITE AND HAUL TO OR FROM SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT AND NO SEPARATE MEASUREMENT OR PAYMENT SHALL BE MADE.
- 8. PAVING AND ROADWAY GRADES SHALL BE +/- 0.1' FROM PLAN ELEVATIONS. PAD ELEVATION SHALL BE +/- 0.05' FROM BUILDING PLAN ELEVATION.
- 9. ALL PROPOSED CONTOURS REFLECT TOP OF PAVEMENT ELEVATIONS IN THE PARKING AREA AND MUST BE ADJUSTED FOR MEDIANS AND ISLANDS.

EXISTING GROUND SPOT ELEVATION

TW=TOP OF WALL, BW=BOTTOM OF WALL

KEYED NOTES

B) HDPE STORM DRAIN, SIZE PER PLAN.

(E) EXISTING STORM DRAIN INLET

TO BE VACATED.

(C) TYPE 'D' INLET PER COA STD DWG 2206

(A) DAYLIGHT PRIVATE STORM DRAIN TO POND WITH

NON-WOVEN GEOTEXTILE FABRIC, CLASS I

D TYPE 'E' STORM DRAIN MANHOLE PER COA STD DWG

E LIMITS OF PORTION OF PUBLIC DRAINAGE EASEMENT

10'X10' RIP RAP BLANKET, D50=6", 1' THICK OVER

PROPOSED SPOT ELEVATION TC=TOP OF CURB, FL=FLOW LINE

EX=EXISTING, TG=TOP OF GRADE

FGH=FINISH GROUND HIGH SIDE

FGL=FINISH GROUND LOW SIDE


PROPOSED DIRECTION OF FLOW

PROPOSED INTER CONTOURS

PROPOSED MANHOLE

WATER BLOCK

10. VERIFY ALL ELEVATIONS SHOWN ON PLAN FROM BASIS OF ELEVATION CONTROL STATION PRIOR TO BEGINNING CONSTRUCTION.



ZONE ATLAS PAGE J-13-Z

GENERAL NOTES

- 1. ALL WORK DETAILED ON THESE PLANS AND PERFORMED UNDER THIS CONTRACT SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS AND THE PROJECT GEOTECHNICAL REPORT. WHERE APPLICABLE, CITY OF ALBUQUERQUE PUBLIC WORKS STANDARDS SHALL APPLY.
- 2. THE CONTRACTOR SHALL ABIDE BY ALL LOCAL, STATE, AND FEDERAL LAWS, RULES AND REGULATIONS WHICH APPLY TO THE CONSTRUCTION OF THESE IMPROVEMENTS, INCLUDING EPA REQUIREMENTS WITH RESPECT TO STORM WATER DISCHARGE.
- 3. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL FIELD VERIFY THE HORIZONTAL AND VERTICAL LOCATIONS OF ALL POTENTIAL OBSTRUCTIONS INCLUDING ALL UNDERGROUND UTILITIES. SHOULD A CONFLICT EXIST, THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION OBSERVER OR ENGINEER SO THAT THE CONFLICT CAN BE RESOLVED WITH A MINIMUM AMOUNT OF DELAY.
- 4. TWO (2) WORKING DAYS PRIOR TO ANY EXCAVATION, THE CONTRACTOR SHALL CONTACT LINE LOCATING SERVICE FOR LOCATION OF EXISTING UTILITIES.
- 5. ALL ELECTRICAL, TELEPHONE, CABLE TV, GAS AND OTHER UTILITY LINES, CABLES, AND APPURTENANCES ENCOUNTERED DURING CONSTRUCTION THAT REQUIRE RELOCATION, SHALL BE COORDINATED WITH THAT UTILITY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION OF ALL NECESSARY UTILITY ADJUSTMENTS. NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR DELAYS OR INCONVENIENCES CAUSED BY UTILITY COMPANY WORK CREWS. THE CONTRACTOR MAY BE REQUIRED TO RESCHEDULE HIS ACTIVITIES TO ALLOW UTILITY CREWS TO PERFORM THEIR REQUIRED WORK.
- 6. THE CONTRACTOR IS RESPONSIBLE FOR PROTECTING ALL EXISTING UTILITY LINES WITHIN THE CONSTRUCTION AREA. ANY DAMAGE TO EXISTING FACILITIES CAUSED BY CONSTRUCTION ACTIVITY SHALL BE REPAIRED OR REPLACED AT THE CONTRACTOR'S EXPENSE AND APPROVED BY THE CONSTRUCTION OBSERVER.
- 7. CONSTRUCTION ACTIVITY SHALL BE LIMITED TO THE PROPERTY AND/OR PROJECT LIMITS. ANY DAMAGE TO ADJACENT PROPERTIES RESULTING FROM THE CONSTRUCTION PROCESS SHALL BE REPAIRED OR REPLACED AT THE CONTRACTOR'S EXPENSE.
- 8. OVERNIGHT PARKING OF CONSTRUCTION EQUIPMENT SHALL NOT OBSTRUCT DRIVEWAYS OR DESIGNATED TRAFFIC LANES. THE CONTRACTOR SHALL NOT STORE ANY EQUIPMENT OR MATERIAL WITHIN THE PUBLIC RIGHT-OF-WAY.
- 9. THE CONTRACTOR SHALL OBTAIN ALL THE NECESSARY PERMITS FOR THE PROJECT PRIOR TO COMMENCING CONSTRUCTION (I.E., BARRICADING, TOPSOIL DISTURBANCE, EXCAVATION PERMITS, EPA STORM WATER PERMITS, ETC.).
- 10. ALL PROPERTY CORNERS DESTROYED DURING CONSTRUCTION SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE. ALL PROPERTY CORNERS MUST BE RESET BY A REGISTERED LAND SURVEYOR.
- 11. THE CONTRACTOR SHALL PREPARE A CONSTRUCTION TRAFFIC CONTROL AND SIGNING PLAN AND OBTAIN APPROVAL OF SUCH PLAN FROM THE CITY OF ALBUQUERQUE, TRAFFIC ENGINEERING DEPARTMENT, PRIOR TO BEGINNING ANY CONSTRUCTION WORK ON OR ADJACENT TO EXISTING STREETS.
- 12. ALL BARRICADES AND CONSTRUCTION SIGNING SHALL CONFORM TO APPLICABLE SECTIONS OF THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" (MUTCD), US DEPARTMENT OF TRANSPORTATION, LATEST EDITION.
- 13. THE CONTRACTOR SHALL MAINTAIN ALL CONSTRUCTION BARRICADES AND SIGNING AT ALL TIMES. THE CONTRACTOR SHALL VERIFY THE PROPER LOCATION OF ALL BARRICADING AT THE END AND BEGINNING OF EACH DAY.
- 14. THE CONTRACTOR SHALL TAKE ALL STEPS NECESSARY TO CONFORM WITH EPA REQUIREMENTS, INCLUDING COMPLIANCE WITH NPDES PHASE 2 REQUIREMENTS.



VILL I AVE N UQUEF

DATE: 7/24/17

REVISIONS

CAD DWG FILE:

DRAWN BY: CHECKED BY:


SHEET TITLE

COPYRIGHT:

GRADING PLAN

Bohannan A Huston

SHEET 1 OF 1



1	MAN S-IVII
	RIO GRANDE BLVD CORRIDOR SI
K	
	1 S.M. 11 2 Pol 173
	OLD TOWN 6 18 COM
	9-72-572 9-5848 FREEWAY 584.3 834.1 6 C. S.
30	280C1626
	9-75133 B28 114161 A B SR 9
	MUSEUM 5 LTD REV
	MUSEUM OF NATURAL NATURAL
	HISTORY SU-1
	11 10 1 10 1 10 1 10 1 10 1 10 1 10 1
	ALBUQUERGUE S MUSEUM PROPRIES SP. 92 - 80
	200 100 100 100 100 100 100 100 100 100
	SU-2 PARK
	2 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
	MA HI STOOLS (SA P. SOUTH SAN AND SAN
	SLOTH & CHARON PROPERTY CONTRACTOR CONTRACTO
	5) (6) (2)25-3
	SHOOL (2) 1 27 27 27 27 27 27 27 27 27 27 27 27 27
	MARDENS OF RECORD TO THE PROPERTY OF THE PROPE
	* R3 (3 2 5 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7
	VICINITY MAP

ZONE ATLAS PAGE J-13-Z

NLET TABLE

Capacity¹

3.6

9.4

9.4

9.4

33.9

Capacity Based on Manning's Eq. w: N=0.013

Slope

1.00%

0.80%

0.80%

0.80%

10.40%

inel	het Tare ²	het Type ² Basin <u>Actua</u>		Arrai	િવસ્ત્રઓપ્ ^{રે}
‡	mer spe		Flowicki	Head fto	[:ts]
l+′	·.83L004T-FED		: 2	1:	3-
ľ-ž	1-83LCC4 TVPE 0	.43	• 5	13	37
P=3	1.83L004.7/98.0			: <u>:</u>	25

NUETS RUACED INSUMPICIONE TOMANO CAPACITES SASEDICALESSER CE CRECARDIA MERREQUATOAS.

STORM DRAIN PIPE TABLE

18

18

18

SAWMILL VILLAGE PHASE 2

Proposed Developed Conditions Basin Data Table

				Trist≥b'e is	based on t	re DPM Sec	tion 22.2. Zone:	2				
8asin	Area	Area	Land Treatment Percentages		Q(100yr) Q(100yr)	V(100yr)	V _{1100ys-85m}	V _{1100y:-241r} .	FIRST FLUSH			
ID	(SQ.FT)	(AC.)	A	В	£	D	(cfs/ac.)	(CFS)	(inches)	(CF)	(CF)	(CF)
жыте	L Basins							-			-	
A1	31243	0.72	0%	10%	C∺	90%	4.5	3.2	25	5171	6168	797
A2	25757	0.59	0%	0%	C∺	100%	4.7	2.8	2.1	4550	5409	730
A3	17199	0.39	0%	5%	C %	95%	4.6	1.8	2.1	2942	3497	453
A4	4471	0.10	0%	54%	C∺	46%	3.4	5.3	1.4	522	59:	59
Αã	16846	0.39	0%	0%	36%	14%	3.4	1.3	13	1787	1858	69
A 6	5021	0.12	0%	5%	C∺	95%	4.6	5.5	2.1	859	1018	135
TOTAL	100537	2.31	_		_	_	_	10.0	_	15831	18481	2252

ACTUAL

FLOW

32

7.8

9.1

9.1

9.1

GRADING AND DRAINAGE NARRATIVE

INLET/SD/BASIN

N2, SD2, A2

N3. SD2

SD3

SD5

SD1

SD2

SD4

SD5

Site Location and Background Information

The purpose of this submittal is to present a grading and drainage plan for the proposed Sawmill Village Phase 2 development located at the northwest corner of Bellamah Avenue and 18th Street. The site legal description is Tract 2—D—1, Arbolera De Vida Subdivision. The proposed development will include two buildings and associated parking and plaza areas. Building A1 is a mixed use building with retail and active use spaces on the ground floor and residential apartments on the second and third floors. Building A2 is a proposed two story Charter School.

The Sawmill Unit 2 Master Drainage Plan, "Drainage Report for Arbolera de Vida Unit 2 (aka Sawmill)" by Bohannan Huston Inc., dated October 16, 2003, and amended on February 24, 2005, allows for free discharge from the proposed development to Sawmill Pond 2 (City Hydrology file: H13-D25). The Sawmill Village Drainage Plan by Bohannan Huston, Inc., dated May 13, 2008, incorporated Sawmill Village Phase 1 into the Sawmill Master Drainage Plan (City Hydrology file: H13-D25A). The Sawmill Village Drainage Plan modified Pond 2 to accept runoff from Phase 1 to be in compliance with the guidelines and recommendations set forth in the Master Drainage Plan. This grading and drainage plan is submitted in support of Hydrology approval for site development plan approval.

Methodology Section 22.2 of the City of Albuquerque Development Process Manual was used to analyze the site hydrology. The site is in rainfall zone 2 as defined by figure A-1 of the DPM section 22. The onsite storm drain was sized based on Manning's Equation. The onsite storm drain inlets were sized based on the inlets being in a sump condition.

Existing Conditions

The site is currently undeveloped land that has been previously disturbed, with an existing slope across the site of less than 1% from southeast to northwest. Sawmill Pond 2 encroaches on the northern portion of the site, which is encumbered by a drainage easement for the pond. Except for flows entering the pond, there are no offsite flows entering the site that will impact the proposed development. The site is slightly higher than Bellamah Avenue to the south, Sawmill Village Phase 2 to the east, the railroad bed to the west and Pond 2 to the north.

Proposed Conditions

The site is divided into 6 onsite drainage basins based on the proposed grading plan and roof drainage. Basins A1, A3 and A4 drain via the parking lot to a proposed private storm drain system that conveys flows to Pond 2. Basin A2 encompasses the roof for Building 2. The roof drains from Building 2 will connect directly to the storm drain system. Basin A5, which includes the sidewalk on the north side of Building 2 and that portion of Pond 2 that encroaches into the site, drains via surface flow into Pond 2.

Basin A6 encompasses the plaza area on the east side of Buildings A1 and A2, which drains to the existing Sawmill Village Phase 1 parking area to the east of the site. An existing storm drain will collect the flow from Basin A6 and convey it to Pond 2. Basins 8 and 13 of the Sawmill Village Drainage Plan allow for flows from the site to drain east into this existing storm drain, which was constructed with Phase 1.

Pond 2 is sized for a 100yr 24hr volume per the Sawmill Master Drainage Plan. Per the latest drainage certification for Sawmill Village (dated October 04, 2011), the existing volume was determined to be 6.45 acre-ft. The required pond volume for the fully developed Arbolera de Vida subdivision is 5.79 acre-ft (252,167CF), which is lower than the ponding volume provided, 6.45 acre—ft (281,084CF). Pond 2 is a retention pond to elevation 4956.4 at which it can discharge 4 cfs to the existing Bellamah storm drain.


The Pond 2 volume at an elevation 4958.8 is 6.95 acre—ft, which is 20% greater than the required pond volume for the fully developed Arbolera de Vida subdivision. In the event that the pond is full the proposed private storm drain system that discharges to the pond would surge. The lowest grate elevations in the private storm drain system are within the Sawmill Village Phase 2 parking lot. The water surface elevation would rise, inundating the Sawmill Village Phase 2 parking area, eventually spilling to Bellamah Avenue. The elevation at which water would spill into Bellamah Avenue is 4961.0, which is 0.9 feet lower than the adjacent finished floor elevation. This allows for the pond to safely discharge flows without flooding adjacent structures in the event that the 100-year, 24-hour storm event is exceeded.

This project is required to meet the first flush requirements of the City Drainage Ordinance. The first flush requirement is calculated as 0.34 inches (0.44 inches less 0.1 inch initial abstraction) times the the percentage of impervious surface within the development (land treatment D). The first flush requirement for Sawmill Village Phase 2 is approximately 2250 cubic feet. The first flush requirement will be met by existing retention volume in Pond 2, which was created by lowering the pond bottom from the Sawmill Village Phase 1 Grading Plan pond bottom elevation (4950.66). The volume available for the first flush is 21,600 cubic feet, which is greater than what is required for the project.

In accordance with FEMA community map panel #35001C0331H, the site is located within a Zone "X" flood plain. This means the site is either subject to the 500-year flood, located within an area of 1.0% chance of annual flood with average depths less than 1 foot, or is located in an area protected by levees from the 1.0% annual chance flood.

This drainage submittal has been prepared in accordance with City of Albuquerque requirements. This plan clearly demonstrates the proposed grading and drainage concepts. The implementation of these concepts would result in the safe passage of the 100 year storm event. With this submittal we request hydrology department approval of this Grading and Drainage Plan for DRB site plan for subdivision approval. A more detailed Grading Plan will be submitted in support of Building Permit approval. The proposed drainage scheme presented in this plan is not anticipated to change as a result of the more detailed grading plan.

Bohannan A Huston



 \mathcal{O} SAWMILL VILLAGE P
BELLAMAH AVE NW AND 1
ALBUQUERQUE, NN

DATE: 7/24/17						
REVISIONS						
	-					
•						
CAD DWG FILE:						

DRAWN BY: CHECKED BY: COPYRIGHT:

SHEET TITLE

DRAINAGE MANAGEMENT PLAN

SHEET 1 OF 1

	·	Proposed	Ultimat	e Develo	pment Co	onditions	Basin Dat	a Table		
		This table	is based	on the DP	M Section	22.2, Zone:	2			
Basin	Area	Area	Land	Treatme	nt Percei	ntages	Q(100)	Q(100)	V(100)	V(100)6HR
ID	(SQ. FT)	(AC.)	Α	В	C	D	(cfs/ac.)	(CFS)	(inches)	(CF)
Tract B-2-A	226055	7.46	0.0%	5.0%	5.0%	90.0%	4.50	33.58	2.00	37742
								<u> </u>		<u> </u>
BASIN 1	32962	0.76	0.0%	10.0%	0.0%	90.0%	4.46	3.37	1.99	5455
BASIN 2	34871	0.80	0.0%	10.0%	0.0%	90.0%	4.46	3.57	1.99	5771
BASIN 3	8640	0.20	0.0%	5.0%	0.0%	95.0%	4.58	0.91	2.05	1478
BASIN 4	13870	0.32	0.0%	5.0%	0.0%	95.0%	4.58	1.46	2.05	2373
BASIN 5	4709	0.11	0.0%	10.0%	0.0%	90.0%	4.46	0.48	1.99	779
BASIN 6	11415	0.26	0.0%	5.0%	0.0%	95.0%	4.58	1.20	2.05	1953

BASIN 9

BASIN 10

BASIN 11

BASIN 12

BASIN 13

BASIN 16

BASIN 17

BASIN 18

BASIN 19

BASIN 20

BASIN 21

BASIN 1

BASIN

EXISTING BUILDING

Proposed Ultimate Development Conditions Basin Data Table							STORM DRAIN PIPE TABLE							
***************************************		************	M Section	***********	***************************************					Contributing	Size			ACTUAL
Area	Land	Treatme	ent Percei	ntages	Q(100)	Q(100)	V(100)	V(100)6HR	PIPE#	Basins and Storm Drains	in.	Slope	Capacity	FLOW
(AC.)	Α	В	C	D	(cfs/ac.)	(CFS)	(inches)	(CF)					cfs	cfs
7.46	0.0%	5.0%	5.0%	90.0%	4.50	33.58	2.00	37742	NORTH		1		CIS	CIS
											40	0.500/	7.40	0.57
0.76	0.0%	10.0%	0.0%	90.0%	4.46	3.37	1.99	5455	SD1	BSN 2	18	0.50%	7.43	3.57
0.80	0.0%	10.0%	0.0%	90.0%	4.46	3.57	1.99	5771	SD2	BSN 5	8	0.50%	0.85	0.48
0.20	0.0%	5.0%	0.0%	95.0%	4.58	0.91	2.05	1478	SD3	BSN 2,5	18	1.00%	10.50	4.05
0.32	0.0%	5.0%	0.0%	95.0%	4.58	1.46	2.05	2373	SD4	BSN 1,2,5	18	1.00%	10.50	7.42
0.11	0.0%	10.0%	0.0%	90.0%	4.46	0.48	1.99	779	CENTRAL					
0.11	0.0%	5.0%	0.0%	95.0%	4.58	1.20	2.05	1953	SD5	SD6,15 + BSN19	30	1.00%	41.02	25.65
0.28	0.0%	10.0%	0.0%	90.0%	4.46	2.13	1.99	3443	SD6	SD7,21 + BSN3	30	0.50%	29.00	20.92
				· · · · · · · · · · · · · · · · · · ·	 		1.99	2721	SD7	SD8, BSN9	24	0.50%	16.00	14.20
0.38	0.0%	10.0%	0.0%	90.0%	4.46	1.68		463	SD8	SD9,20 + BSN10	24	0.50%	16.00	13.92
0.06	0.0%	5.0%	0.0%	95.0%	4.58	0.28	2.05		SD9	BSN 11,12,14	24	0.50%	16.00	9.36
0.58	0.0%	5.0%	0.0%	95.0%	4.58	2.64	2.05	4299	SD10	BSN 12	18	0.50%	7.43	4.37
0.71	0.0%	5.0%	0.0%	95.0%	4.58	3.23	2.05	5260	SD11	BSN 14	12	0.50%	2.52	1.75
0.98	0.0%	10.0%	0.0%	90.0%	4.46	4.37	1.99	7073	SD12	SD13 + BSN4	18	1.00%	10.50	4.79
0.49	0.0%	5.0%	0.0%	95.0%	4.58	2.25	2.05	3661	SD13	BSN 6,7	12	1.00%	3.56	3.33
0.52	0.0%	55.0%	0.0%	45.0%	3.37	1.75	1.38	2612	SD14	BSN 7	12	0.50%	2.52	2.13
0.16	0.0%	15.0%	0.0%	85.0%	4.34	0.68	1.92	1090	SD15	BSN 8,13	18	1.00%	10.50	3.93
0.68	0.0%	5.0%	0.0%	95.0%	4.58	3.13	2.05	5102	SD16	BSN 13	12	1.00%	3.56	2.25
0.30	0.0%	65.0%	0.0%	35.0%	3.13	0.92	1.25	1338	SD20	BSN 21	12	1.00%	3.56	1.92
1.43	0.0%	10.0%	0.0%	90.0%	4.46	6.36	1.99	10290	SD21	SD12 + BSN20	18	1.00%	10.50	5.81
0.17	0.0%	5.0%	0.0%	95.0%	4.58	0.80	2.05	1304				1		
0.22	0.0%	0.0%	0.0%	100.0%	4.70	1.02	2.12	1671	WEST					
0.19	0.0%	15.0%	0.0%	85.0%	4.34	0.84	1.92	1354	SD17	BSN 15,16	12	2.00%	5.04	3.81
					ý.	1 .			SD18	BSN 15	8	1.00%	1.21	0.68
9.79	0.0%	12.2%	0.0%	87.8%	4.40	43.10	1.96	69490	SD19	BSN 16	12	1.00%	3.56	3.13


BASIN 2

BASHY

BASIN

BASIN 6

		-
	S-MI S-HILL AND 100450 S-MI S-HILLY / T	****
	WILLIAM AND REW! 43 0 7	Y
	C-2 A2 MCCORD 55 199884	•
	100090 77 3002A1C C AAI	•
	CARLON CO. SELLAMAN CO.	L₹
	RIOTERANDE BLVD CORRIDOR	m
		1
	1 S.M. W	S.
	SHERATON STEWART OLD TOWN	Ê
	SHERATON STEWART SAWMILL WELLS PARK RIA	1
1 4		L
	FREEWAY FREEWAY	Č
	10	S
	de la contraction de la contra	IA)
	LANGE STORY OF THE	11
	5 C-2 1/cut	7
		15
	Museum of Marural Marural	M
	HISTORY / SU-1	7
	ALBUQUERQUE E	Ĭ,
	MUSEUM TO SEE THE SEE	ij
	SU-1 FESTER ST 82 80 ST 82 8	Ŀ
		2
	H-1 H-1 SU-2 PARK SILERO	×
	STATE STATE OF A STATE	2
	and	Ś
	VICINITY MAP	
•		
	ZONE ATLAS PAGE J-13-Z	



architecture

engineering

Albuquerque, NM 87109

505 761-9700 fax 761-4222


dps @dpsdesign.org

GRADING AND DRAINAGE NARRATIVE

Site Location and Background Information

The purpose of this submittal is to present a drainage and grading plan for the proposed Sawmill Village development to the North of Bellamah and 18th street. The design site proposes mixed use development. There will be some residential townhomes, and some commercial sites. The site is in rainfall zone 2 as defined by figure A-1 of the DPM section 22. The existing legal description of the site is Tract 2-D, Arbolera De Vida and Lot B-2-A, Duke City Lumber Company Addition. Please see the vicinity map on this sheet for a graphic depiction of the site location. This conceptual grading and drainage plan is submitted in support of site plan approval.

The Sawmill Master Drainage Plan Area, prepared by Bohannan Huston Inc., addresses drainage off the western site and the surrounding area to the west and north (city hydrology file: H13-D25). This submittal integrates the eastern Lot B-2-A into the Sawmill Master Drainage Plan and modifies the pond construction to be in compliance with the guidance and recommendations set forth in that report.



PROJECT

Existing Conditions

This entire site (Tracts 2—D & B—2—A) is approximately 10 acres and is an old industrial sawmill. The natural slope of the site is very flat. The slope across the site is less than 1% from the northeast to the southwest. There is an existing pond north of Tract 2-D that is part of the Sawmill Master Drainage Plan. It currently discharges into the storm drain in Bellamah at a maximum flow of 4 C.F.S. The site is approximately level with Bellamah and the surrounding properties.

Under proposed conditions the site will slope slightly to the pond north of Tract 2—D and utilize storm drain systems to convey runoff to the pond w/ functional surface slopes. The site will be mostly impervious treatment D and the rest landscaped treatment B and C. The Sawmill Master Drainage Plan sizes the existing pond as a retention system to be conservative. The pond is a retention pond to elevation 4954 at which it can discharge 4 C.F.S. in a detention condition. The existing pond is sized to accept runoff from the Tract 2-D (the portion of the site west of 18th St.). The pond expansion is sized to accept additional runoff from Lot B-2-A. With this project, we propose to expand the volume of the existing pond by approximately 59,000 CF. This expansion can be accomplished without lowering the pond bottom. Accordingly, the depth of retained water below the invert of the outlet pipe will not be increased with this project. The proposed pond expansion volume exceeds the 100yr, 6hr storm volume generated by tract B-2-A.

Flood plain

In accordance with FEMA community map panel #35001C0331 E, the site is not located within a flood

There are no significant upstream offsite flows which will impact this site.

Conclusions

This drainage submittal has been prepared in accordance with City of Albuquerque requirements. This plan clearly demonstrates the proposed, general surface grading and drainage. The implementation of this design will result in the safe passage of the 100 year storm event. With this submittal we request hydrology department approval of this Grading and Drainage Plan for building permit.

INLET TABLE

Inlet	Inlet	Top of	Actual	Avail	Capacity
#	Туре	Grate	Flow	Head ft	
IN1	2'x2' Nyloplast Road & Highway Grate	57.07	3.37	0.5	6.00
IN2	2'x2' Nyloplast Road & Highway Grate	58.00	3.57	0.5	6.00
IN3	2'x2' Nyloplast Road & Highway Grate	58.38	0.91	0.5	6.00
IN4	2'x2' Nyloplast Road & Highway Grate	58.38	1.46	0.5	6.00
IN5	2'x2' Nyloplast Road & Highway Grate	58.76	0.48	0.5	6.00
IN6	2'x2' Nyloplast Road & Highway Grate	59.15	1.20	0.5	6.00
IN7	2'x2' Nyloplast Road & Highway Grate	59.16	2.13	0.5	6.00
IN8	2'x2' Nyloplast Road & Highway Grate	57.97	1.68	0.5	6.00
IN9	2'x2' Nyloplast Road & Highway Grate	59.39	0.28	0.5	6.00
IN10	2'x2' Nyloplast Road & Highway Grate	58.64	2.64	0.5	6.00
IN11	2'x2' Nyloplast Road & Highway Grate	58.45	3.23	0.5	6.00
IN12	2'x2' Nyloplast Road & Highway Grate	58.81	4.37	0.5	6.00
IN13	2'x2' Nyloplast Road & Highway Grate	57.97	2.25	0.5	6.00
IN14	24" Standard Nyloplast Grate	58.80	1.75	0.5	3.60
IN15	2'x2' Nyloplast Road & Highway Grate	57.90	0.68	0.5	6.00
IN16	2'x2' Nyloplast Road & Highway Grate	57.75	3.13	0.5	6.00
IN19	2'x2' Nyloplast Road & Highway Grate	57.30	0.80	0.5	6.00
IN20	2'x2' Nyloplast Road & Highway Grate	57.15	1.02	0.5	6.00
IN21	18" Pedestrian Nyloplast Grate	57.00	0.84	0.5	2.20
11 42 1	10 1 edestriari ryjupiast Grate	07.00	0.04	0.0	<u></u>

The actual head available varies with each inlet, but in no case is the available head less than 0.5'.

nue a Bellamah awmill

REVI	SIONS).
\triangle		
Λ		
$\overline{\triangle}$		
$\overline{\wedge}$	*	

RAWN BY	CP
EVIEWED BY	BJS
ATE	May 13, 2008
PO IECT NO	06124

DRAINAGE MANAGEMENT

SHEET NO.

PLAN

DRAWING NAME

P:\070249\cdp\general\070249DMP01.dwg Thu, 22-May-2008 - 9:49:am, Plotted by: JSMITH

LEGEND

PROPOSED DIRECTION OF FLOW

PROPOSED INTER CONTOURS

PROPOSED STORM DRAIN INLET

BASIN 16

BELLAMAH AVENÜËN,M.

60' R.O.N.

BUILDING

F.F.=60.00

BASIN 17

WATER BLOCK

-5305 PROPOSED INDEX CONTOURS

1"=40'

BASIN 18

F.F.=59.00 BUILDING

F.F.=59.50

BASIN 8

BASIN 13

PONDBOT: 4949.50

EXPANSION: 59,137 CF

VOL:

4955.70

238,560 CF

CITY OF ALBUQUERQUE



May 14, 2008

Bruce J. Stidworthy, P.E.
Bohannan Huston, Inc.
7500 Jefferson St NE – Courtyard I
Albuquerque, NM 87109

Re: Sawmill Village Grading and Drainage Plan Engineer's Stamp dated 5-13-08 (H13/D025A)

Dear Mr. Stidworthy,

Based upon the information provided in your submittal received 5-13-08, the above referenced plan is approved for Building Permit conditional on compliance with the SWPPP. Please attach a copy of this approved plan to the construction sets prior to sign-off by Hydrology.

PO Box 1293

This project requires a National Pollutant Discharge Elimination System (NPDES) permit. You are required to send a copy of your SWPPP on a CD to the following address:

Albuquerque

Kathy Verhage, Department of Municipal Development, Storm Drainage Division, P.O. Box 1293, One Civic Plaza, Rm. 301, Albuquerque, NM 87103

NM 87103

Prior to Certificate of Occupancy release, Engineer Certification per the DPM checklist will be required.

www.cabq.gov

If you have any questions, you can contact me at 924-3695.

Sincerely,

Curti a Chem. Curtis A. Cheme, P.E.

Senior Engineer, Planning Dept.

Development and Building Services

SCHLORE

permit A ou are required to soud a copy of pour SAVPSE on a Classical belowing

C: file

Wathy Verhage, DMD