


© 2022 CEI ENGINEERING ASSOCIATES, INC.



CEI ENGINEERING ASSOCIATES, INC.
3108 SW REGENCY PKWY
BENTONVILLE, AR 72712
PHONE: (479) 273-9472
FAX: (479) 273-0844

RESTAURANT DEPOT



PROFESSIONAL OF RECORD	JDG
PROJECT MANAGER	JEH
DESIGNER	HMK/MDT
CEI PROJECT NUMBER	32348
DATE	8/15/2022
REVISION	REV-0

EROSION CONTROL PLAN

SHEET NUMBER

PLAN REVIEW REV'S (REV #2)

C5.0

GENERAL EROSION NOTES

- A. ALL CONTRACTORS AND SUBCONTRACTORS INVOLVED WITH STORM WATER POLLUTION PREVENTION SHALL OBTAIN A COPY OF THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) AND THE STATE OF NEW MEXICO NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM GENERAL PERMIT (NPDES PERMIT) AND BECOME FAMILIAR WITH THEIR
- B. A COPY OF THE SWPPP AND EROSION CONTROL PLANS, INCLUDING APPLICABLE DETAIL SHEETS, MUST REMAIN ONSITE THROUGHOUT CONSTRUCTION AND MADE AVAILABLE TO THE PUBLIC UNTIL THE SITE IS TERMINATED AND/OR PERMANENTLY STABILIZED PER THE NPDES PERMIT.
- C. THE CONTRACTOR MUST UPDATE THE SWPPP AND EROSION CONTROL PLANS TO REFLECT THE PROGRESS OF CONSTRUCTION AND GENERAL CHANGES TO THE PROJECT SITE. CHANGES MAY INCLUDE BMP INSTALLATION. MODIFICATION, OR REMOVAL, CONSTRUCTION ACTIVITIES, CLEARING, GRUBBING, OR GRADING, AND TEMPORARY OR
- D. THE CONTRACTOR MUST ADHERE TO ANY HOURS OF WORK, NOISE LEVEL, OR OTHER CONSTRUCTION RELATED RESTRICTIONS IN ACCORDANCE WITH LOCAL OR STATE REGULATIONS.
- E. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THAT ANY OFFSITE BORROW, SPOIL, OR STORAGE AREAS TO BE UTILIZED, BUT NOT PROVIDED WITHIN THE PROJECT'S LIMITS OF DISTURBANCE, ARE TO BE PROPERLY LICENSED AND
- F. THE NPDES PERMIT DOES ALLOW CERTAIN NON-STORMWATER DISCHARGES AT THE CONSTRUCTION SITE, SEE NPDES PERMIT, SECTION A.1 FOR A COMPLETE LIST OF PERMITTED DISCHARGES. THESE DISCHARGES MUST BE TREATED BY AN ONSITE BMP PRIOR TO LEAVING THE SITE AND MUST NOT CAUSE EROSION OR DAMAGE TO DOWNSTREAM PROPERTIES AND INFRASTRUCTURE. ALL OTHER DISCHARGES ARE STRICTLY PROHIBITED UNLESS AN APPLICABLE PERMIT HAS BEEN OBTAINED PRIOR TO THE DISCHARGE BY THE CONTRACTOR.
- G. THE TEMPORARY PARKING AND STORAGE AREA SHALL ALSO BE USED AS THE EQUIPMENT MAINTENANCE AREA, EQUIPMENT CLEANING AREA, EMPLOYEE BREAK AREA, AND AREA FOR LOCATING PORTABLE FACILITIES, OFFICE TRAILERS AND TOILET FACILITIES. THE EXACT LOCATIONS SHALL BE COORDINATED WITH THE OWNER'S CONSTRUCTION MANAGER AND DEPICTED ON THE ONSITE EROSION CONTROL PLAN.
- H. ALL WASH WATER (CONCRETE TRUCKS, VEHICLE CLEANING, EQUIPMENT CLEANING, ETC.) SHALL BE DISPOSED OF IN A MANNER THAT PREVENTS CONTACT BETWEEN THESE MATERIALS AND STORM WATER THAT IS DISCHARGED FROM THE
- I. MAINTAIN ON THE SITE OR HAVE READILY AVAILABLE SUFFICIENT OIL AND GREASE ABSORBING MATERIALS AND FLOTATION BOOMS TO CONTAIN AND CLEAN UP FUEL OR CHEMICAL SPILLS AND LEAKS.
- J. ADEQUATE HOUSEKEEPING MEASURES SHALL BE IMPLEMENTED SO THAT LOOSE TRASH, MATERIALS, TOOLS, AND EQUIPMENT ARE COLLECTED AND PROPERLY STORED AT THE CONSTRUCTION SITE.
- K. DUST ON THE SITE SHALL BE CONTROLLED BY SPRAYING WATER ON DRY AREAS OF THE SITE. THE USE OF MOTOR OILS AND OTHER PETROLEUM BASED OR TOXIC LIQUIDS FOR DUST SUPPRESSION OPERATIONS IS PROHIBITED.
- L. NO RUBBISH, TRASH, GARBAGE OR OTHER SUCH MATERIALS SHALL BE DISCHARGED INTO DRAINAGE DITCHES, DRAINAGE STRUCTURES, OR WATERS OF THE STATE.
- M. ALL STORM WATER POLLUTION PREVENTION MEASURES PRESENTED ON THIS PLAN, AND IN THE STORM WATER POLLUTION PREVENTION PLAN, SHALL BE INITIATED AS SOON AS PRACTICABLE.
- N. DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITY WILL STOP FOR AT LEAST 14 DAYS, SHALL BE TEMPORARILY STABILIZED IMMEDIATELY
- O. DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITY HAS PERMANENTLY STOPPED SHALL BE PERMANENTLY STABILIZED. THESE AREAS SHALL BE STABILIZED IMMEDIATELY, BUT NO LATER THAN 14 DAYS AFTER THE
- LAST CONSTRUCTION ACTIVITY OCCURRING IN THESE AREAS. REFER TO THE LANDSCAPING PLAN. P. IF THE ACTION OF VEHICLES TRAVELING OVER THE GRAVEL CONSTRUCTION ENTRANCES IS NOT SUFFICIENT TO REMOVE THE MAJORITY OF DIRT OR MUD, THEN THE TIRES MUST BE WASHED BEFORE THE VEHICLES ENTER A PUBLIC ROAD. IF WASHING IS USED, PROVISIONS MUST BE MADE TO INTERCEPT THE WASH WATER AND TRAP THE SEDIMENT BEFORE IT
- Q. ALL MATERIALS SPILLED, DROPPED, WASHED OR TRACKED FROM VEHICLES ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED IMMEDIATELY.

IS CARRIED OFF THE SITE. THE EXACT LOCATIONS SHALL BE COORDINATED WITH THE OWNER'S CONSTRUCTION

- R. CONTRACTORS OR SUBCONTRACTORS WILL BE RESPONSIBLE FOR REMOVING SEDIMENT IN THE DETENTION POND AFTER THE STABILIZATION OF THE SITE AND ANY SEDIMENT THAT MAY HAVE COLLECTED IN THE STORM SEWER
- S. IF SOIL STOCKPILING IS EMPLOYED ON THE SITE, SILT FENCES SHALL BE USED TO HELP CONTAIN THE SEDIMENT.
- T. SLOPES SHALL BE LEFT IN A ROUGHENED CONDITION DURING THE GRADING PHASE TO REDUCE RUNOFF VELOCITIES
- U. SEDIMENT BASINS AND TRAPS ARE ATTRACTIVE TO CHILDREN AND CAN BE VERY DANGEROUS. IN ALL CASES, LOCAL AND/OR STATE ORDINANCES AND REGULATIONS REGARDING HEALTH AND SAFETY MUST BE ADHERED TO.
- V. ALL EXISTING AND PROPOSED STORM SEWER PIPES, DRAINAGE STRUCTURES, AND DRAINAGE DITCHES WITHIN THE PROJECT AREA SHALL BE CLEANED OF ANY TRASH AND ACCUMULATED SEDIMENT PRIOR TO FINAL STABILIZATION.
- W. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE DISPOSED OF WITHIN 30 DAYS AFTER FINAL STABILIZATION. FINAL STABILIZATION HAS OCCURRED WHEN ALL SOIL DISTURBING ACTIVITIES ARE COMPLETED AND A UNIFORM PERENNIAL VEGETATIVE COVER WITH A DENSITY OF N/A COVER FOR UNPAVED AREAS AND AREAS NOT
- X. DUE TO THE GRADE CHANGES DURING THE DEVELOPMENT OF THE PROJECT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ADJUSTING THE EROSION CONTROL MEASURES (SILT FENCES, WATTLES, ETC.) TO HELP PREVENT EROSION AND STORM WATER POLLUTION.
- Y. ALL OFF-SITE CONSTRUCTION SHALL BE STABILIZED AT THE END OF EACH WORKING DAY, THIS INCLUDES BACKFILLING OF TRENCHES FOR STORM DRAINS & UTILITY CONSTRUCTION AND PLACEMENT OF GRAVEL OR BITUMINOUS PAVING FOR ROAD CONSTRUCTION.
- Z. IN AN EMERGENCY SITUATION, THE CONTRACTOR IS RESPONSIBLE FOR MODIFYING OR ADDING BMPS NECESSARY TO STOP POLLUTANT OR SEDIMENT DISCHARGES FROM THE CONSTRUCTION SITE AND PROTECT THE WATER QUALITY OF THE RECEIVING WATERBODY.
- AA. IF AN EXCAVATION NEEDS TO BE DEWATERED DUE TO A RECENT RAINFALL EVENT, THE CONTRACTOR CAN DEWATER THE EXCAVATION VIA A PUMPED FILTER BAG. THE PUMPED FILTER BAG MUST DISCHARGE ONTO A STABILIZED SURFACE AND UPSTREAM OF AN EROSION CONTROL BMP LIKE A SEDIMENT BASIN/TRAP, SILT FENCE, OR OTHER PERIMETER BMP. IT IS STRICTLY PROHIBITED TO DISCHARGE THE PUMPED FILTER BAG INTO A STORM DRAIN OR OTHER CONVEYANCE STRUCTURE WITHOUT THE RUNOFF BEING TREATED VIA AN EROSION CONTROL BMP FIRST.

SEQUENCE OF CONSTRUCTION

- NOTE: DOWNSLOPE PROTECTIVE MEASURES MUST ALWAYS BE IN PLACE BEFORE SOIL IS DISTURBED. CONSTRUCTION STEPS CAN BE IMPLEMENTED CONCURRENTLY ONLY IF ASSOCIATED DOWNSLOPE PROTECTIVE MEASURES HAVE BEEN INSTALLED FOR
- CONSTRUCT THE SILT FENCES ON THE SITE.
- INSTALL INLET PROTECTION DEVICES ON EXISTING INLETS. INSTALL STABILIZED CONSTRUCTION ENTRANCES.
- CLEAR AND GRUB THE SITE. GRADE POND AND INSTALL OUTFALL STRUCTURE WITH SEDIMENT PROTECTION. BEGIN GRADING THE SITE

COVERED BY PERMANENT STRUCTURES HAS BEEN EMPLOYED.

- START CONSTRUCTION OF BUILDING PAD AND STRUCTURES. TEMPORARILY SEED DENUDED AREAS.
- INSTALL UTILITIES, UNDERDRAINS, STORM SEWERS, CURBS AND GUTTERS.
- INSTALL INLET PROTECTION DEVICES. INSTALL RIP RAP AROUND OUTLET STRUCTURES.
- PREPARE SITE FOR PAVING.
- 14. COMPLETE GRADING AND INSTALL PERMANENT SEEDING AND PLANTING. L5. REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES (ONLY IF SITE IS STABILIZED).

NOTE

1. ALBUQUERQUE EROSION & SEDIMENT CONTROL (ESC) STANDARD NOTES TO TAKE PRECEDENT.

GENERAL EROSION NOTES CONT'D

MAINTENANCE ALL MEASURES STATED ON THIS EROSION AND SEDIMENT CONTROL PLAN, AND IN THE STORM WATER POLLUTION PREVENTION PLAN, SHALL BE MAINTAINED IN FULLY FUNCTIONAL CONDITION UNTIL FINAL STABILIZATION OF THE SITE. ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE CHECKED BY A QUALIFIED PERSON AT LEAST ONCE EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A RAINFALL EVENT GREATER THAN 1-INCHES, AND SHOULD BE CLEANED AND REPAIRED IN ACCORDANCE WITH THE FOLLOWING:


- 1. INLET PROTECTION DEVICES AND BARRIERS SHALL BE REPAIRED OR REPLACED IF THEY SHOW SIGNS OF UNDERMINING, OR SHALL BE REPLACED IF THEY SHOW SIGNS OF DETERIORATION.
- 2. ALL SEEDED AREAS SHALL BE CHECKED REGULARLY TO SEE THAT A GOOD STAND IS MAINTAINED. AREAS SHOULD BE FERTILIZED AND RESEEDED AS NEEDED.
- 3. SILT FENCES AND WATTLES SHALL BE REPAIRED TO THEIR ORIGINAL CONDITIONS IF DAMAGED. SEDIMENT SHALL BE REMOVED FROM THE SILT FENCES AND WATTLES WHEN IT REACHES ONE-THIRD TO ONE-HALF THE HEIGHT OF THE BMP.
- 4. THE CONSTRUCTION ENTRANCES SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE CONSTRUCTION ENTRANCES AS CONDITIONS DEMAND.
- 5. THE TEMPORARY PARKING AND STORAGE AREA SHALL BE KEPT IN GOOD CONDITION (SUITABLE FOR PARKING AND STORAGE). THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE TEMPORARY PARKING AS CONDITIONS DEMAND.
- 6. IF THE STONES IN THE GRAVEL INLET SEDIMENT FILTERS OR ROCK CHECK DAMS BECOME CLOGGED WITH SEDIMENT, THE STONES MUST BE PULLED AWAY, CLEANED AND REPLACED.
- 7. THE EMBANKMENT OF THE SEDIMENTATION BASIN SHALL BE CHECKED REGULARLY TO ENSURE THAT IT IS STRUCTURALLY SOUND AND HAS NOT BEEN DAMAGED BY EROSION OR CONSTRUCTION EQUIPMENT.
- 8. THE TEMPORARY SEDIMENT TRAP AND SEDIMENTATION BASIN STRUCTURES SHALL BE CHECKED REGULARLY TO ENSURE THAT THEY ARE STRUCTURALLY SOUND AND HAVE NOT BEEN DAMAGED BY EROSION OR CONSTRUCTION EQUIPMENT.
- 9. DIVERSION DIKES AND/OR DITCHES SHALL BE CHECKED REGULARLY FOR EROSION AND SCOUR. ANY ERODED AREAS FOUND MUST BE IMMEDIATELY REPAIRED.
- 10. CONCRETE WASHOUT AREAS SHALL BE CHECKED REGULARLY FOR LEAKS AND CAPACITY. ALL LEAKS MUST BE REPAIRED IMMEDIATELY. WHEN THE WASHOUT VOLUME HAS BEEN REDUCED BY 85%, THE BMP MUST BE REMOVED AND REPLACED.

ALBUQUERQUE EROSION & SEDIMENT CONTROL (ESC) STANDARD NOTES

- 1. ALL EROSION AND SEDIMENT CONTROL (ESC) WORK ON THESE PLANS, EXCEPT AS OTHERWISE STATED OR PROVIDED HEREON SHALL BE PERMITTED, CONSTRUCTED, INSPECTED, AND MAINTAINED IN ACCORDANCE WITH:
- a. THE CITY ORDINANCE § 14-5-2-11, THE ESC ORDINANCE,
- b. THE EPA'S 2017 CONSTRUCTION GENERAL PERMIT (CGP), AND
- c. THE CITY OF ALBUQUERQUE CONSTRUCTION BMP MANUAL.
- 2. ALL BMP'S MUST BE INSTALLED PRIOR TO BEGINNING ANY EARTH MOVING ACTIVITIES EXCEPT AS SPECIFIED HEREON IN THE PHASING PLAN. CONSTRUCTION OF EARTHEN BMP'S SUCH AS SEDIMENT TRAPS, SEDIMENT BASINS, AND DIVERSION BERMS SHALL BE COMPLETED AND INSPECTED PRIOR TO ANY OTHER CONSTRUCTION OR EARTHWORK. SELF-INSPECTION IS REQUIRED AFTER INSTALLATION OF THE BMPS AND PRIOR TO BEGINNING CONSTRUCTION.
- 3. SELF-INSPECTIONS AT A MINIMUM A ROUTINE COMPLIANCE SELF-INSPECTION IS REQUIRED TO REVIEW THE PROJECT FOR COMPLIANCE WITH THE CONSTRUCTION GENERAL PERMIT ONCE EVERY 14 DAYS AND AFTER ANY PRECIPITATION EVENT OF 1/4 INCH OR GREATER UNTIL THE SITE CONSTRUCTION HAS BEEN COMPLETED AND THE SITE DETERMINED AS STABILIZED BY THE CITY. REPORTS OF THESE INSPECTIONS SHALL BE KEPT BY THE PERSON OR ENTITY AUTHORIZED TO DIRECT THE CONSTRUCTION ACTIVITIES ON THE SITE AND MADE AVAILABLE UPON REQUEST.
- 4. CORRECTIVE ACTION REPORTS MUST BE KEPT BY THE PERSON OR ENTITY AUTHORIZED TO DIRECT THE CONSTRUCTION ACTIVITIES ON THE SITE AND MADE AVAILABLE UPON REQUEST.
- 5. STABILIZATION REPORTS MUST BE KEPT BY THE PERSON OR ENTITY AUTHORIZED TO DIRECT THE CONSTRUCTION ACTIVITIES ON THE SITE AND MADE AVAILABLE UPON REQUEST. REPORTS SHOULD INCLUDE RECORDS OF WEED REMOVAL PER CITY ORDINANCE (§ 9-8-1), STERILIZATION, SOIL TEST RESULTS AND RECOMMENDATION, MATERIALS AND MANUFACTURER'S SPECIFICATIONS FOR APPLICATION RATES, ESTIMATED FUNCTIONAL LONGEVITY, METHODS OF APPLICATION, INSPECTION AND MAINTENANCE. THE REDUCED SELF-INSPECTION SCHEDULE IN CGP 4.4.1 APPLIES TO STABILIZED AREA AND ANY DAMAGED OR WORN STABILIZATION MUST BE IDENTIFIED IN THE REPORTS ALONG WITH WEED PROBLEMS, CORRECTIVE ACTIONS FOR STABILIZATION SHALL BE DOCUMENTED IN A STABILIZATION REPORT INCLUDING ACTUAL RATES AND DATES OF STABILIZATION, AND THE MATERIALS AND MANUFACTURER'S SPECIFICATIONS USED.
- 6. BMPS SHALL BE INSPECTED AND MAINTAINED UNTIL ALL DISTURBED AREAS ARE STABILIZED IN ACCORDANCE WITH THE FINAL STABILIZATION CRITERIA (CGP 2.2.14.B). GENERALLY, ALL DISTURBED AREAS, OTHER THAN STRUCTURES AND IMPERVIOUS SURFACES, MUST HAVE UNIFORM PERENNIAL VEGETATION THAT PROVIDES 70 PERCENT OR MORE OF THE COVER PROVIDED BY NATIVE VEGETATION OR SEED THE DISTURBED AREA AND PROVIDE NON-VEGETATIVE MUI CH THAT PROVIDES COVER FOR AT LEAST THREE YEARS WITHOUT ACTIVE MAINTENANCE. FINAL STABILIZATION MUST BE APPROVED BY THE CITY OF ALBUQUERQUE PRIOR TO REMOVAL OF BMPS AND DISCONTINUATION OF INSPECTIONS.

ALBUQUERQUE STANDARD EROSION & SEDIMENT CONTROL (ESC) CONSTRUCTION NOTES

- 1. WHEN DOING WORK IN THE CITY RIGHT-OF-WAY (E.G. SIDEWALK, DRIVE PADS, UTILITIES, ETC.) PREVENT DIRT FROM GETTING INTO THE STREET. IF DIRT IS PRESENT IN THE STREET, THE STREET SHOULD BE SWEPT DAILY OR PRIOR TO A RAIN EVENT OR CONTRACTOR INDUCED WATER EVENT (E.G. CURB CUT OR WATER TEST).
- WHEN INSTALLING UTILITIES BEHIND THE CURB, THE EXCAVATED DIRT SHOULD NOT BE PLACED IN THE STREET.
- 3. WHEN CUTTING THE STREET FOR UTILITIES INCLUDE A NOTE THAT THE DIRT SHALL BE PLACED ON THE UPHILL SIDE OF THE STREET CUT AND THE AREA SWEPT AFTER THE WORK IS COMPLETE. A WATTLE OR MULCH SOCK MAY BE PLACED AT THE TOE OF THE EXCAVATED DIRT PILE IF SITE CONSTRAINTS DO NOT ALLOW PLACING THE EXCAVATED DIRT ON THE UPHILL SIDE OF THE STREET CUT.



OR STRING-TIED WITH THE BINDINGS ORIENTED AROUND THE SIDES RATHER

THAN OVER AND UNDER THE BALES.


INLET, WITH ENDS OF ADJACENT


ENTRENCHED AND BACKFILLED. A


THE FILTER BARRIER.

LEAST TWO STAKES OR REBAR

TRENCH SHALL BE EXCAVATED AROUNI THE INLET THE WIDTH OF A BALE TO A MINIMUM DEPTH OF 4 INCHES AFTER THE BALES ARE STAKED, THE EXCAVATED SOIL SHALL BE BACKFILLED AND COMPACTED AGAINS










1. WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES. 2. FILTER CLOTH TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH TIES SPACED EVERY

SHALL BE REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE

- 24" AT TOP AND MID SECTION. 3. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVERLAPPED
- 4. MAINTENANCE SHALL BE PERFORMED AS NOTED IN THE EROSION CONTROL PLAN. COLLECTED MATERIAL







SWP-CI "Big Red"

Curb Inlet Protector

By ASP Enterprises and Storm Water Products



Specifications:

- . Infill Material: shredded recycled rubber tires
- 2. Weight: approx. 10 lbs per linear foot
- . Diameter: approx. 8"

Geotextile fabric made of durable high flow fabric with the following prop-

Property	Test Method	Units		Typical Value
Weight	ASTM D5261	oz/sq. yd		9.3
Grab Tensile Strength	ASTM D4632	1b	warp	250
			fill	290
Tear Strength	ASTM D4533	Ib	warp	60
(Trapezoid)			fill	50
Burst	ASTM D3786	psi		440

(Efforts were made to determine flow rate-the fabric exceeded all capacities of the testing equipment)




ASP Enterprises and Storm Water Products assumes no liability for the accuracy or completeness of this information or for the ultimate use by the purchaser. ASP and SWP disclaims any and all express, implied, or statutory standards, warranties or guarantees, including without limitation any implied warranty as to merchantability or fitness for a particular purpose or arising from a course of dealing or usage of trade as to any equipment, materials or information furnished herewith. This document should not be construed as engineering advice.

SWP-CI "Big Red"

Curb Inlet Protector

By ASP Enterprises and Storm Water Products Temporary and Reusable Solutions for Sediment Control



- Environmentally Friendly
- · Drops out sediment by dissipating the water energy

"Big Red" Filter Advantages:

- Easy to Install
- · Versatile for a variety of curb inlets · Reusable and Extremely easy to clean

Made from 90% Inert Recycled Materials

The SWP-CI "Big Red" Filter is a REUSABLE inlet protector that keeps out sediment throughout the entire construction project. There are no pockets to fill, no velcro bags, no assembly etc. Simply place in front of the inlet, make sure it lays in the contour, and you are DONE!


Simple installation also translates into simple removal, cleanup and re

-use at the next project or phase. Maintenance is simple as well by lifting the unit from the inlet, shaking the mud off of it, removing the sediment on the concrete, and placing the unit back. If it is severely filled with sediment, wash it out

in a vegetated area and it is as good as new.

All of these features and benefits combine to make the SWP-CI "Big Red" curb inlet protector the perfect choice for all curb inlet applications. It comes in 54" long for single curb inlets and 104" lengths for double curb inlets.

· Made of Recycled Materials



Fully Reusable


Made of Durable High-Strength Geotextile



CEI ENGINEERING ASSOCIATES. INC. 3108 SW REGENCY PKWY BENTONVILLE, AR 72712 PHONE: (479) 273-9472 FAX: (479) 273-0844

A.S.P. ENTERPRISES. INC.

Your GeoSource Distributor




PROFESSIONAL OF RECORD	IDG
PROJECT MANAGER	JEH
DESIGNER	HMK/MDT
CEI PROJECT NUMBER	32348
DATE	8/15/2022
REVISION	REV-0

EROSION CONTROL NOTES

CITY OF ALBUQUERQUE

Planning Department Alan Varela, Director



September 12, 2022

Jeffrey D. Geurian, P.E. CEI Engineering Associates, INC 3030 LBJ Freeway, #100 Dallas, TX 75234

RE: Restaurant Depot 1901 Menaul Blvd NE Grading & Drainage Plans and Drainage Report

> Engineer's Stamp Date: 08/11/22 Hydrology File: H15D039

Dear Mr. Geurian:

PO Box 1293

Based upon the information provided in your submittal received 08/15/2022, the Grading & Drainage Plans and Drainage Report is approved for Building Permit and Grading Permit. Please attach a copy of this approved plan in the construction sets for Building Permit processing along with a copy of this letter.

Albuquerque

PRIOR TO CERTIFICATE OF OCCUPANCY:

NM 87103

1. Engineer's Certification, per the DPM Part 6-14 (F): *Engineer's Certification Checklist For Non-Subdivision* is required.

www.cabq.gov

2. Please provide the Drainage Covenant with Exhibit A for the stormwater quality pond per Article 6-15(C) of the DPM prior to Permanent Release of Occupancy. Please submit the original copies along with the \$25.00 recording fee check made payable to Bernalillo County to Carrie Compton (cacompton@cabq.gov) on the 4th floor of Plaza de Sol.

As a reminder, if the project total area of disturbance (including the staging area and any work within the adjacent Right-of-Way) is 1 acre or more, then an Erosion and Sediment Control (ESC) Plan and Owner's certified Notice of Intent (NOI) is required to be submitted to the Stormwater Quality Engineer (Doug Hughes, PE, jhughes@cabq.gov, 924-3420) 14 days prior to any earth disturbance.

CITY OF ALBUQUERQUE

Planning Department Alan Varela, Director



Mayor Timothy M. Keller

If you have any questions, please contact me at 924-3995 or rbrissette@cabq.gov.

Sincerely, Renée C. Brissette


Renée C. Brissette, P.E. CFM Senior Engineer, Hydrology Planning Department

PO Box 1293

Albuquerque

NM 87103

www.cabq.gov





UTILITY POLE

02- 2"

3150

CTV

IRAF

175

 $\square SL$

SIM

GUY WIRE ANCHOR

ELECTRICAL METER

ELECTRICAL VAULT

ELECTRICAL MANHOLE

ELECTRICAL PULLBOX

ELECTRICAL TRANSFORMER

CABLE TELEVISION PEDESTAL

CABLE TELEVISION PULLBOX

CABLE TELEVISION VAULT

TRAFFIC SIGNAL FLASHER

TRAFFIC SIGNAL CABINET

TRAFFIC SIGNAL PULLBOX

STREET LIGHT PULLBOX

STREET LIGHT VAULT

NATURAL GAS VALVE

NATURAL GAS VAULT

NATURAL GAS MANHOLE

TELEPHONE PULLBOX

TELEPHONE MANHOLE

TELEPHONE PEDESTAL

FIBER OPTIC MANHOLE

FIBER OPTIC PEDESTAL FIBER OPTIC PULLBOX

SANITARY SEWER MANHOLE

SANITARY SEWER CLEAN OUT

GREASE TRAP/INTERCEPTOR MANHOLE

CURB INLET

GRATE INLET

REVISIONS DESCRIPTION

JUNCTION BOX

FLARED END SECTION

SANITARY SEWER VAULT

TELEPHONE VAULT

NATURAL GAS METER ASSEMBLY

PEDESTRIAN SIGNAL

TRAFFIC VAULT

STREET LIGHT

AREA LIGHT

GROUND LIGHT

ELECTRICAL BOX


• A A A TRAFFIC SIGNAL LIGHT

PVC RISER, NUMBER & SIZE AS SHOWN

CEI ENGINEERING ASSOCIATES, INC. 3108 SW REGENCY PKWY

BENTONVILLE, AR 72712 PHONE: (479) 273-9472 FAX: (479) 273-0844


ш AURAN Δ



1901 ALBU

PROJECT MANAGER	JEH
DESIGNER	HMK/MDT
CEI PROJECT NUMBER	32348
DATE	8/11/2022
REVISION	REV-0

GRADING PLAN





Call before you dig.

UTILITY POLE

GUY WIRE ANCHOR

III before you dig.	Land and Life
	CEI ENGINEERING ASSOCIATES, INC. 3108 SW REGENCY PKWY BENTONVILLE. AR 72712

PHONE: (479) 273-9472

FAX: (479) 273-0844



CENTERLINE

SUBJECT PROPERTY

PROPOSED GR	ADING LEGEND		
	PROPERTY LINE/RIGHT OF WAY LINE	•	CURB INLET
	STORM LINE		COMBINATION INLET
	PROPERTY LINE/RIGHT OF WAY LINE		FLARED END SECTION
XXX	 CONTOUR ELEVATIONS 	50505059	LIMITS OF ENGINEERED MEDIA
	— GRADE BREAK	2000000	PER DETAIL 73A - BIORETENTION AREA ZONE
x XX.XX	SPOT ELEVATIONS: TC = TOP OF CURB G = GUTTER		WITHIN DRY POND

FFE = FINISH FLOOR ELEVATION

FG = FINISH GRADE

GENERAL GRADING NOTES

- A. PRIOR TO INSTALLATION OF STORM OR SANITARY SEWER, THE CONTRACTOR SHALL EXCAVATE, VERIFY, AND CALCULATE ALL CROSSINGS AND INFORM THE OWNER AND THE ENGINEER OF ANY CONFLICTS PRIOR TO CONSTRUCTION. THE ENGINEER WILL BE HELD HARMLESS IN THE EVENT THE ENGINEER IS NOT NOTIFIED OF DESIGN
- CONTRACTOR HAS THE OPTION TO BID THE FOLLOWING MATERIAL FOR THE STORM SEWER SYSTEM EXCEPT WHERE OTHERWISE NOTED: RCP OR HDPE AS INDICATED ON THIS PLAN WHERE THE WORD PIPE IS USED. ALL PIPES SHALL HAVE A MAXIMUM ROUGHNESS COEFFICIENT ("N") OF 0.013 AND SHALL MEET OR EXCEED THE PIPE MANUFACTURERS REQUIREMENTS FOR MINIMUM AND MAXIMUM COVER. CONTRACTOR SHALL REFER TO THE SITEWORK SPECIFICATION SECTION FOR STORM SEWER SYSTEMS FOR ACCEPTABLE TYPE AND MATERIAL.
- ALL SLOPES AND AREAS DISTURBED BY CONSTRUCTION SHALL BE GRADED SMOOTH AND 4" OF TOPSOIL APPLIED. IF ADEQUATE TOPSOIL IS NOT AVAILABLE ON SITE, THE CONTRACTOR SHALL PROVIDE TOPSOIL, APPROVED BY THE OWNER, AS NEEDED. THE AREA SHALL THEN BE SEEDED, FERTILIZED, MULCHED, WATERED AND MAINTAINED UNTIL HARDY GRASS GROWTH IS ESTABLISHED IN ALL AREAS (SEE LANDSCAPE PLAN FOR SEED MIX AND PROPER APPLICATION RATE). ANY AREAS DISTURBED FOR ANY REASON PRIOR TO FINAL ACCEPTANCE OF THE PROJECT SHALL BE CORRECTED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
- D. THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES, AND WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES.
- UNLESS OTHERWISE SHOWN, CALLED OUT OR SPECIFIED HEREON OR WITHIN THE SPECIFICATIONS: ALL STORM DRAIN PIPE BEDDING SHALL BE INSTALLED PER DETAIL 28A. ALL STORM DRAIN PIPES ARE MEASURED FROM CENTER OF STRUCTURES AND ENDS OF FLARED END SECTIONS.


N	O. DATE	REVISIONS DESCRIPTION
Z_1	04/08/2022	FOR BIDDING
I_2	04/12/2022	FOR PERMIT
Z	06/27/2022	PLAN REVIEW REV'S (REV #2)



PROFESSIONAL OF RECORD	JDG
PROJECT MANAGER	JEH
DESIGNER	HMK/MDT
CEI PROJECT NUMBER	32348
DATE	8/11/2022
REVISION	REV-0

8/11/22

DRAINAGE PLAN



© 2022 CEI ENGINEERING ASSOCIATES, INC.




CEI ENGINEERING ASSOCIATES, INC. 3108 SW REGENCY PKWY BENTONVILLE, AR 72712 PHONE: (479) 273-9472 FAX: (479) 273-0844

DEP(AURANT \simeq



PROFESSIONAL OF RECORD	JDG
PROJECT MANAGER	JEH
DESIGNER	HMK/MDT
CEI PROJECT NUMBER	32348
DATE	8/10/2022
REVISION	REV-0


DETAIL SHEET 2





SEE ARCHITECTURAL PLANS FOR EXACT LOCATIONS AND DIMENSIONS OF ORCHES, RAMPS, VESTIBULE, SLOPED PAVING, TRUCK DOCKS, BUILDING

CLOSELY COORDINATE GRADING AT FROST SLABS AND SURROUNDING



SCALE IN FEET

CENTERLINE



UTILITY POLE



CEI ENGINEERING ASSOCIATES, INC. 3108 SW REGENCY PKWY BENTONVILLE, AR 72712 PHONE: (479) 273-9472

FAX: (479) 273-0844

SUBJECT PROPERTY **GUY WIRE ANCHOR** 02- 2" RIGHT-OF-WAY LINE PVC RISER, NUMBER & SIZE AS SHOWN ADJOINING PROPERTY ELECTRICAL METER **315**() ELECTRICAL VAULT EASEMENT LINE _____ BUILDING SETBACK LINE ELECTRICAL MANHOLE CONCRETE HATCH ELECTRICAL PULLBOX CONCRETE SIDEWALK ELECTRICAL BOX CHAIN LINK FENCE ELECTRICAL TRANSFORMER SCREEN WALL CABLE TELEVISION PEDESTAL CABLE TELEVISION PULLBOX $\Box CTV$ RETAINING WALL OVERHEAD ELECTRICAL CTV CABLE TELEVISION VAULT • TRAFFIC SIGNAL LIGHT UNDERGROUND ELECTRICAL TRAFFIC SIGNAL FLASHER GAS LINE FIBER OPTIC LINE PEDESTRIAN SIGNAL CABLE TV LINE IRAF TRAFFIC VAULT WATER LINE TRAFFIC SIGNAL CABINET STORM DRAIN LINE **17**5 TRAFFIC SIGNAL PULLBOX SANITARY SEWER LINE $\square SL$ STREET LIGHT PULLBOX WATER METER STREET LIGHT $\square W$ WATER BOX SIVI STREET LIGHT VAULT WATER MANHOLE AREA LIGHT WATER AIR RELEASE VALVE **GROUND LIGHT** IRRIGATION CONTROL BOX NATURAL GAS VALVE FIRE HYDRANT NATURAL GAS METER ASSEMBLY WATER VALVE 67.18 NATURAL GAS VAULT WATER BLOW-OFF NATURAL GAS MANHOLE FDC ON BLDG. TELEPHONE PULLBOX REMOTE FDC TELEPHONE VAULT STORM DRAIN MANHOLE TELEPHONE MANHOLE STORM DRAIN DROP INLET TELEPHONE PEDESTAL CATCH BASIN FIBER OPTIC MANHOLE FIBER OPTIC VAULT **BOLLARD POST** FIBER OPTIC PEDESTAL FIBER OPTIC PULLBOX GATE SANITARY SEWER MANHOLE SANITARY SEWER CLEAN OUT UTILITY VAULT - UNKNOWN SANITARY SEWER VAULT UTILITY PULLBOX - UNKNOWN GREASE TRAP/INTERCEPTOR MANHOLE VAPOR AND MONITORING WELLS UTILITY MANHOLE - UNKNOWN (ABANDONED IN PLACE) ELECTRIC PEDESTAL

PROPOSED LEG	GEND		
	PROPERTY LINE/RIGHT OF WAY LINE	•	GRATE INLET
	CONCRETE CURB AND GUTTER. SEE DETAIL 01A/01B. FIRE ACCESS		CURB INLET
	SAWCUT	ф	FIRE HYDRANT
0	FENCE	₩	FDC
•	BUILDING CONTROL POINT	H	VALVE
(#)	PROPOSED PARKING SPACES		LIGHT POLE (PER MEP.)
	LIMITE OF SIDEWALKS AND CONSPETE APPONG	•	BOLLARD
	LIMITS OF SIDEWALKS AND CONCRETE APRONS	_	BOLLARD GUARD

→ SIGN

CANOPY COLUMNS

☐ SITE DETAILS

- 01A TYPE A CONCRETE CURB AND GUTTER
- 01C TYPE C CONCRETE RAISED CURB AND GUTTER 03D CONCRETE SIDEWALK
- 04A GUIDE RAIL 06D RETAINING WALL
- 07J CHAIN LINK FENCE ON RETAINING WALL 09B NINETY DEGREE PARKING SPACE STRIPING
- 09F 90 DEGREE ACCESSIBLE PARKING SPACE STRIPING
- 09N 90 DEGREE PARKING 09S ACCESSIBLE / VAN ACCESSIBLE PARKING SIGN
- 09U ACCESSIBLE PARKING SYMBOL 10C FIRE LANE MARKING
- 13D TYPICAL 39' LIGHTING POLE BASE 47C COMMON TRENCH DETAIL ELECTRIC TELEPHONE FIRE ALARM CABLE

SITE NOTES

- 12D 4 INCH WIDE PAINTED YELLOW STRIPES. 2.0 FOOT O.C. @ 45 DEGREES (SEE SIZE INDICATED AT SYMBOL). 21B TAPER CURB FROM 12" TO 6" OVER 12'
- 70B HOOP-STYLE PARKING STOP

DATE	REVISIONS DESCRIPTION
04/08/2022	FOR BIDDING
04/12/2022	FOR PERMIT
06/27/2022	PLAN REVIEW REV'S (REV #2)

PROFESSIONAL OF RECORD	JDG
PROJECT MANAGER	JEH
DESIGNER	HMK/MDT
CEI PROJECT NUMBER	32348
DATE	9/6/2022
REVISION	REV-0


1901 ALBU


SITE PLAN

SHEET NUMBER

SHEET TITLE

STAURANT





SUBJECT PROPERTY

EASEMENT LINE

RIGHT-OF-WAY LINE

ADJOINING PROPERTY

Know what's below.
Call before you dig.

UTILITY POLE

GUY WIRE ANCHOR

ELECTRICAL METER

ELECTRICAL VAULT

PVC RISER, NUMBER & SIZE AS SHOWN

Solutions for Land and Life

CEI ENGINEERING ASSOCIATES, INC. 3108 SW REGENCY PKWY BENTONVILLE, AR 72712 PHONE: (479) 273-9472 FAX: (479) 273-0844

	BUILDING SETBACK LINE	E	ELECTRICAL MANHOLE
	CONCRETE HATCH	$\Box E$	ELECTRICAL PULLBOX
	CONCRETE SIDEWALK		ELECTRICAL BOX
	CHAIN LINK FENCE	ET	ELECTRICAL TRANSFORMER
	SCREEN WALL	∠ CTV	CABLE TELEVISION PEDESTAL
	RETAINING WALL	□ <i>CTV</i>	CABLE TELEVISION PULLBOX
OHE OHE	OVERHEAD ELECTRICAL	CIV	CABLE TELEVISION VAULT
UGE UGE UGE	UNDERGROUND ELECTRICAL	o	TRAFFIC SIGNAL LIGHT
	GAS LINE	0	TRAFFIC SIGNAL FLASHER
FIBOP FIBOP	FIBER OPTIC LINE	⇔	PEDESTRIAN SIGNAL
UGT € UGT €	CABLE TV LINE	II:VAT	TRAFFIC VAULT
	WATER LINE	\boxtimes	TRAFFIC SIGNAL CABINET
	STORM DRAIN LINE	□ <i>TS</i>	TRAFFIC SIGNAL PULLBOX
	SANITARY SEWER LINE	□SL	STREET LIGHT PULLBOX
□WM	WATER METER		STREET LIGHT
\square W	WATER BOX	SIVI	STREET LIGHT VAULT
()	WATER MANHOLE	☆	AREA LIGHT
	WATER AIR RELEASE VALVE	€	GROUND LIGHT
\mathbb{R}	IRRIGATION CONTROL BOX	\mathbf{E}^{G}	NATURAL GAS VALVE
X	FIRE HYDRANT	\circ^G	NATURAL GAS METER ASSEMBLY
⋈wv	WATER VALVE	6/72	NATURAL GAS VAULT
BOV	WATER BLOW-OFF	©	NATURAL GAS MANHOLE
FICA	FDC ON BLDG.	□ <i>T</i>	TELEPHONE PULLBOX
196 ,	REMOTE FDC	III	TELEPHONE VAULT
6 D	STORM DRAIN MANHOLE	\bigcirc	TELEPHONE MANHOLE
	STORM DRAIN DROP INLET	□ <i>T</i>	TELEPHONE PEDESTAL
	CATCH BASIN	E	FIBER OPTIC MANHOLE
-	SIGN		FIBER OPTIC VAULT
•	BOLLARD POST	⊿ F	FIBER OPTIC PEDESTAL
	GATE	⊠F	FIBER OPTIC PULLBOX
p	FLAG POLE	S	SANITARY SEWER MANHOLE
图条在	TREES	•	SANITARY SEWER CLEAN OUT
UNK	UTILITY VAULT - UNKNOWN		SANITARY SEWER VAULT
$\square U$	UTILITY PULLBOX - UNKNOWN	(7)	GREASE TRAP/INTERCEPTOR MANHOLE
()	UTILITY MANHOLE - UNKNOWN		VAPOR AND MONITORING WELLS
THE EPED	ELECTRIC PEDESTAL		(ABANDONED IN PLACE)

0)=H=

PROPOSED LEGEND

PROPERTY LINE/RIGHT OF WAY LINE CONCRETE CURB AND GUTTER. SEE DETAIL 01A/01B. LIMITS OF SIDEWALKS AND CONCRETE APRONS

☐ PAVING DETAILS


03D CONCRETE SIDEWALK 08A STANDARD DUTY ASPHALT PAVING 08B HEAVY DUTY ASPHALT PAVING 08C HEAVY DUTY CONCRETE PAVING (REINFORCED) 08N ASPHALT OVERLAY

PROFESSIONAL O	F RECORD	JDG
PROJECT MANAG	ER	JEH
DESIGNER		HMK/MDT
CEI PROJECT NUN	/IBER	32348
DATE		9/6/2022
REVISION		REV-0

PAVING PLAN

SHEET NUMBER

RESTAURANT





CEI ENGINEERING ASSOCIATES, INC. 3108 SW REGENCY PKWY BENTONVILLE, AR 72712 PHONE: (479) 273-9472 FAX: (479) 273-0844

UTILITY POLE

02- 2"

CTV

 $\square SL$

SIVI

67.15

GUY WIRE ANCHOR

ELECTRICAL METER ELECTRICAL VAULT

ELECTRICAL MANHOLE

ELECTRICAL PULLBOX

ELECTRICAL TRANSFORMER CABLE TELEVISION PEDESTAL

CABLE TELEVISION PULLBOX

CABLE TELEVISION VAULT

TRAFFIC SIGNAL FLASHER

TRAFFIC SIGNAL CABINET

TRAFFIC SIGNAL PULLBOX

STREET LIGHT PULLBOX

STREET LIGHT VAULT

NATURAL GAS VALVE

NATURAL GAS VAULT

NATURAL GAS MANHOLE

TELEPHONE PULLBOX

TELEPHONE MANHOLE

TELEPHONE PEDESTAL

FIBER OPTIC MANHOLE

FIBER OPTIC PEDESTAL FIBER OPTIC PULLBOX

SANITARY SEWER MANHOLE SANITARY SEWER CLEAN OUT

GREASE TRAP/INTERCEPTOR MANHOLE

PROVIDED

PROVIDED

PROVIDED

PROVIDED

14 TREES

PROVIDED

36 DECIDUOUS

TREES PROVIDED

18 TREES

TREES PROVIDED

4 TREES PROVIDED

23,730 SF

171,000 SF TOTAL SITE - 44,503

SF BUILDING = 126,497 SF x 15%

= 18,974 SF REQUIRED

REQUIRED

REQUIRED

132 PARKING SPACES / 10 =

14 TREES REQUIRED

44 TOTAL TREES PROVIDED x 75% = 33

DECIDUOUS TREES REQUIRED

MENAUL BLVD: 530 LF / 30 =

18 TREES REQUIRED

I-25 RAMP: 245 LF / 30 =

9 TREES REQUIRED

UNIVERSITY BLVD: 103 LF / 30 =

4 TREES REQUIRED

SANITARY SEWER VAULT

TELEPHONE VAULT

NATURAL GAS METER ASSEMBLY

PEDESTRIAN SIGNAL

TRAFFIC VAULT

STREET LIGHT

AREA LIGHT

GROUND LIGHT

ELECTRICAL BOX

• TRAFFIC SIGNAL LIGHT

PVC RISER, NUMBER & SIZE AS SHOWN


STAURAN

 \propto

FOR BIDDING NOT FOR CONSTRUCTION

PROFESSIONAL OF RECORD	JDG
PROJECT MANAGER	JEH
DESIGNER	НМК
CEI PROJECT NUMBER	32348
DATE	8/22/2022
REVISION	REV-0

LANDSCAPE PLAN



© 2022 CEI ENGINEERING ASSOCIATES, INC.

Solutions for Land and Life

CEI ENGINEERING ASSOCIATES, INC. 3108 SW REGENCY PKWY BENTONVILLE, AR 72712 PHONE: (479) 273-9472 FAX: (479) 273-0844

NOT FOR

PROFESSIONAL OF RECORD	JDG
PROJECT MANAGER	JEH
DESIGNER	НМК
CEI PROJECT NUMBER	32348
DATE	8/22/2022
REVISION	REV-0

LANDSCAPE PLAN

SHEET NUMBER

■ EPED

↑ 06/27/2022 PLAN REVIEW REV'S (REV #2)

ELECTRIC PEDESTAL

REVISIONS DESCRIPTION

GENERAL NOTES

LANDSCAPE ARCHITECT OR OWNER.

- 1. CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ALL PROPOSED LANDSCAPING IS INSTALLED IN ACCORDANCE WITH PLANS, DETAILS, SPECIFICATIONS (IF APPLICABLE) AND ALL LOCAL CODES AND REQUIREMENTS.
- 2. CONTRACTOR TO INSPECT SITE AND VERIFY CONDITIONS AND DIMENSIONING PRIOR TO PROCEEDING WITH WORK DESCRIBED HERE IN. NOTIFY LANDSCAPE ARCHITECT OF ANY DISCREPANCIES PRIOR TO BEGINNING ANY
- 3. QUANTITIES PROVIDED IN THE PLANT LIST ARE FOR GENERAL USE ONLY. CONTRACTOR IS RESPONSIBLE FOR VERIFICATION OF ALL PLANT AND LANDSCAPE MATERIAL QUANTITIES. SYMBOL COUNT ON PLAN TAKES PRECEDENCE OVER TABLE QUANTITIES.
- 4. IMMEDIATELY AFTER AWARD OF CONTRACT, NOTIFY THE OWNER'S REPRESENTATIVE AND/OR THE LANDSCAPE ARCHITECT OF UNAVAILABILITY OF SPECIFIED PLANT MATERIAL FROM COMMERCIAL NURSERIES. THE OWNER'S REPRESENTATIVE AND/OR LANDSCAPE ARCHITECT WILL PROVIDE ALTERNATE PLANT MATERIAL SELECTIONS IF UNAVAILABILITY OCCURS. SUCH CHANGES SHALL NOT ALTER THE ORIGINAL BID PRICE UNLESS A CREDIT IS DUE TO THE
- 5. ALL PLANT MATERIALS TO CONFORM TO THE AMERICAN STANDARD FOR NURSERY STOCK ANSI Z60.1.
- 6. CONTAINER GROWN STOCK SHOULD HAVE GROWN IN A CONTAINER LONG ENOUGH FOR THE ROOT SYSTEM TO HAVE DEVELOPED SUFFICIENTLY TO HOLD ITS SOIL TOGETHER.
- 7. ANY PLANT SUBSTITUTIONS, RELOCATION, OR REQUIRED CHANGE SHALL REQUIRE THE WRITTEN APPROVAL OF THE
- 8. THE OWNER'S REPRESENTATIVE AND/OR LANDSCAPE ARCHITECT RESERVE THE RIGHT TO REFUSE ANY MATERIAL THEY DEEM UNACCEPTABLE.
- 9. COORDINATE WITH PROJECT REPRESENTATIVE FOR DISTURBED SITE TREATMENTS OUTSIDE LANDSCAPE
- IMPROVEMENTS. SEE CIVIL PLANS FOR SOIL STABILIZATION FOR EROSION CONTROL.10. CONTRACTOR SHALL ENSURE THAT THERE IS POSITIVE DRAINAGE AND NO PONDING OF IRRIGATION WATER AT ROOT
- 11. ALL SLOPES AND AREAS DISTURBED BY CONSTRUCTION SHALL BE GRADED SMOOTH AND FOUR INCHES OF TOPSOIL APPLIED. IF ADEQUATE TOPSOIL IS NOT AVAILABLE ON SITE, THE CONTRACTOR SHALL PROVIDE TOPSOIL, APPROVED BY THE OWNER, AS NEEDED. THE AREA SHALL THEN BE SEEDED/SODDED, FERTILIZED, MULCHED, WATERED AND MAINTAINED UNTIL HARDY GRASS GROWTH IS ESTABLISHED IN ALL AREAS. ANY RELOCATED TREES SHALL BE MAINTAINED UNTIL SUCH POINT AS TREE IS RE-ESTABLISHED. ANY AREAS DISTURBED FOR ANY REASON PRIOR TO FINAL ACCEPTANCE OF THE PROJECT SHALL BE CORRECTED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
- 12. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL UNDERGROUND UTILITIES AND SHALL AVOID DAMAGE TO ALL UTILITIES DURING THE COURSE OF THE WORK. LOCATIONS OF EXISTING BURIED UTILITY LINES SHOWN ON THE PLANS ARE BASED UPON BEST AVAILABLE INFORMATION AND ARE TO BE CONSIDERED APPROXIMATE. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR 1) TO VERIFY THE LOCATIONS OF UTILITY LINES AND ADJACENT TO THE WORK AREA 2) TO PROTECT OF ALL UTILITY LINES DURING THE CONSTRUCTION PERIOD 3) TO REPAIR ANY AND ALL DAMAGE TO UTILITIES, STRUCTURES, SITE APPURTENANCES, ETC. WHICH OCCURS AS A RESULT OF THE CONSTRUCTION AT NO COST TO THE OWNER.
- 13. WEED MAT IS REQUIRED IN LANDSCAPED ISLANDS AS SPECIFIED.
- 14. ALL PLANT MATERIAL QUANTITIES SHOWN ARE APPROXIMATE. CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLETE COVERAGE OF ALL PLANTING BEDS AT SPACING SHOWN.
- 15. IF A SWPPP PLAN IS PROVIDED THIS PLAN IS TO BE IMPLEMENTED COOPERATIVELY WITH SWPPP PLAN, AS NEEDED, TO MAXIMIZE THE EFFECTIVENESS OF THE SWPPP PLAN FOR THIS SITE.
- 16. THE CONTRACTOR IS ENCOURAGED TO COMPLETE TEMPORARY OR PERMANENT SEEDING OR SODDING IN STAGES FOR SOIL STABILIZATION AS AREAS ARE COMPLETED AFTER GRADING.
- 17. SEEDING ON SLOPES: HYDROSEED WITH GRASS SEED AS INDICATED ON PLANS. SEE LEGEND FOR SPECIFIC GRASS SEED TYPE. SEEDING SHALL BE ACCOMPLISHED IMMEDIATELY AFTER BED PREPARATION. HYDROSEED MIXTURE SHALL CONTAIN CELLULOSE MULCH APPLIED AT A RATE OF 2,000 LBS./ACRE, WITH A MAXIMUM OF 50 LBS./100 GAL. OF WATER. IF SEEDING IS DELAYED AFTER MIXING 1/2 2 HOURS ADD AN ADDITIONAL 50% OF SEED MIX, IF DELAY IS LONGER THAN 2 HOURS, BEGIN WITH NEW MIXTURE. ALL SLOPES 2:1 OR GREATER SHALL BE COVERED WITH EROSION CONTROL BLANKET AS SHOWN IN THE EROSION CONTROL BLANKET DETAIL. SEE SPECIFICATIONS FOR SEED ESTABLISHMENT REQUIREMENTS.
- 18. ALL PLANT MATERIAL IN TREE HOLDING AREAS SHALL BE MANUALLY WATERED/IRRIGATED TO KEEP MOIST UNTIL PLANTED.
- 19. LANDSCAPE CONTRACTOR SHALL ENSURE ALL TREES AND SHRUBS ARE ADEQUATELY WATERED AND MAINTAINED FOR A PERIOD OF AT LEAST 2 YEARS OR UNTIL FULLY ESTABLISHED. ONCE TREES AND SHRUBS ARE FULLY ESTABLISHED LANDSCAPE MAINTENANCE CONTRACTOR SHALL MANUALLY WATER PLANTS AS NEEDED TO MAINTAIN PLANTS DURING DRY PERIODS.

MULCH TOP DRESSING: SEE LANDSCAPE

REQUIRED DEPTH

STEEL STAKE DRIVEN FROM MULCH SIDE OF -

EDGING WITH TOP OF STAKE BELOW TOP OF HEADER

PLANTING NOTES

- 1. LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR PREPARING ALL PLANTED AREAS. ALL DELETERIOUS MATERIALS SUCH AS ROCK, TRASH, CONSTRUCTION DEBRIS, AGGREGATE BASE MATERIAL, ASPHALT, ETC. SHALL BE REMOVED PRIOR TO ANY FILL OPERATIONS. FILL ALL PLANTING AREAS WITH CLEAN EARTHEN FILL. SOIL SHALL BE FREE OF HEAVY, STIFF CLAY AND ANY DELETERIOUS MATERIAL OVER ONE INCH IN SIZE. THE TOP SIX INCHES OF FILL MATERIAL STRIPPED FROM SITE MAY BE UTILIZED FOR PLANTER OR TOPSOIL FILL IF PRIOR APPROVAL HAS BEEN OBTAINED FROM THE OWNER'S REPRESENTATIVE AND/OR LANDSCAPE ARCHITECT.
- 2. FINISH GRADE OF LANDSCAPE AREAS (TOP OF TURF AND MULCH) MUST BE GRADED TO 1 1/2" BELOW ADJACENT PAVEMENT SURFACES.
- 3. LOCATE SHRUBS A DISTANCE OF HALF OF THEIR AVERAGE MATURE SPREAD AWAY FROM WALKS, STRUCTURES, CONCRETE PADS, ETC. LOCATE GROUND COVER PLANTINGS A MINIMUM OF 2' FROM WALKS, STRUCTURES, CONCRETE PADS, ETC.
- 4. ALL LAWN AREAS NOT OTHERWISE BORDERED BY WALKS, OR OTHER STRUCTURES, SHALL HAVE MANUFACTURED EDGING AS REQUIRED.
- 5. TREES PLANTED ADJACENT TO PUBLIC ROADS AND PEDESTRIAN SIDEWALKS SHALL BE PRUNED SUFFICIENTLY TO AVOID VISUAL BLOCKS TO INTERSECTING VEHICULAR ACCESS OR INTERFERENCE WITH PEDESTRIAN WALKWAYS. TREES WITH A 4" OR LARGER CALIPER SHALL BE PRUNED UP TO 6'-0" ABOVE PAVEMENTS.
- 6. ALL TREES WITHIN 4' OF PAVED SURFACES (SUCH AS CURBS, WALLS, BUILDINGS AND SIDEWALKS) SHALL BE PROVIDED WITH A DEEP ROOT BARRIER CONTROL DEVICE OR EQUAL. INSTALL PER MFR'S SPECIFICATIONS.
- 7. TOPSOIL DEPTH SHALL BE AS FOLLOWS : PLANTER BEDS 12" MINIMUM
- GRASS/SOD AREAS 4" MINIMUM (AFTER COMPACTION)
- 8. BACKFILL ALL TREES, SHRUBS, GROUNDCOVER WITH A MIXTURE OF 2 PARTS NATIVE SOIL AND 1 PART SOIL CONDITIONING WITH WOOD MULCH.
- 9. THE LANDSCAPE CONTRACTOR SHALL WATER TEST ALL PLANTING HOLE PRIOR TO PLANTING. IF HOLES DO NOT DRAIN PROPERLY, EXCAVATE FURTHER UNTIL IMPERMEABLE LAYER IS BREACHED. EXCAVATED PLANT PITS SHALL HAVE POSITIVE DRAINAGE. PLANT PITS (WHEN FULLY FLOODED WITH WATER) SHALL DRAIN WITHIN 1 HOUR OF FILLING. ENSURE THAT ALL PLANT PITS HAVE POSITIVE DRAINAGE.
- 10. ALL PLANTING BEDS SHALL BE TREATED WITH A PRE-EMERGENT HERBICIDE. PRE-EMERGENT HERBICIDE SHALL BE APPLIED PER MANUFACTURE'S RECOMMENDATIONS AND SHALL OCCUR AFTER TOPSOIL PLACEMENT AND PRIOR TO INSTALLATION OF PLANT MATERIALS AND MULCH.
- 11. FERTILIZE ALL PLANTS AT THE TIME OF PLANTING WITH A TIME RELEASE FERTILIZER PER BRAND'S SPECIFIED APPLICATION RATES.
- 12. ALL PLANTING BED SOILS SHALL BE AMENDED WITH 2" OF ORGANIC COMPOST
- 13. ALL TREES AND SHRUBS SHALL BE PLANTED IN SUCH A MANNER AS TO ENSURE THEIR SURVIVAL.
- 14. ANY ROPE OR WIRE BINDING THE BALL SHALL BE CUT PRIOR TO PREVENT GIRDLING OF THE TREE. REMOVE WIRE, TWINE, AND BURLAP FROM THE TOP HALF OF ALL B&B PLANT MATERIAL.
- 15. IF A NON-BIODEGRADABLE MATERIAL IS USED AROUND THE BALL, IT SHALL BE COMPLETELY REMOVED PRIOR TO BACKFILLING.
- 16. PRIOR TO INSTALLATION, THE ROOTS OF CONTAINER GROWN STOCK SHALL BE SEPARATED OR SPLIT TO ENSURE
- PROPER ROOT DEVELOPMENT.
- 17. CONTRACTOR SHALL BE RESPONSIBLE FOR DELIVERY SCHEDULE AND PROTECTION BETWEEN DELIVERY AND PLANTING TO MAINTAIN HEALTHY PLANT CONDITIONS.
- 18. ANY PLANT MATERIAL WHICH IS DISEASED, DISTRESSED, DEAD, OR REJECTED (PRIOR TO SUBSTANTIAL COMPLETION) SHALL BE PROMPTLY REMOVED FROM THE SITE AND REPLACED WITH MATERIAL OF THE SAME SPECIES, QUANTITY, AND SIZE AND MEETING ALL PLANT LIST SPECIFICATIONS. TREES & SHRUBS SHALL BE PLANTED AS SOON AS POSSIBLE AFTER DELIVERY.
- 19. ALL TREES MUST BE STRAIGHT-TRUNKED, FULL-HEADED AND MEET ALL REQUIREMENTS SPECIFIED.
- 20. ALL TREES MUST BE STAKED AS SHOWN IN THE DETAILS.
- 21. NO SUBSTITUTIONS OR ALTERNATIVES WILL BE ALLOWED FOR GROUND SURFACE MATERIALS UNLESS APPROVED IN WRITING BY THE LANDSCAPE ARCHITECT OR OWNER.
- 22. MAINTAIN 5' MIN. HORIZONTAL SEPARATION BETWEEN TREE PLANTINGS AND ALL UTILITIES UNLESS OTHERWISE SPECIFIED.
- 23. A FOUR INCH (4") TOP DRESSING/MULCHING OF BROWN/TAN 3/4" 1.5" DIA. DECOMPOSED GRANITE MULCH SHALL BE PLACED IN ALL PLANT BEDS AND AROUND ALL TREES. SINGLE TREES OR SHRUBS SHALL HAVE TOP DRESSING TO THE OUTSIDE EDGE OF THE MANUFACTURED EDGING OR LANDSCAPE ISLAND. (SEE PLANTING DETAILS) TOP DRESSING CAN BE WOOD MULCH, ROCK, OR ANY OTHER DECORATIVE MATERIAL SPECIFIED ON PLANS. SEE LANDSCAPE PLAN FOR TYPE.

NOTES FOR MULCH MATERIAL AND

POLYPROPYLENE MATERIAL WEED — BARRIER AT FINISH GRADE

STEEL STAKE DRIVEN FROM MULCH SIDE OF -

EDGING WITH TOP OF STAKE BELOW TOP OF

POLYPROPYLENE MATERIAL WEEL

EDGING SHALL BE USED

1. DEPICTION ABOVE IS FOR SODDED AREA WITH MULCH.

24. THE FOLLOWING PLANTING SEASONS ARE RECOMMENDED: EVERGREEN SHRUBBERY OCT-MAR DECIDUOUS SHRUBBERY & TREES OCT-MAR EVERGREEN TREES OCT-MAR

PLANT GUARANTEE, REPLACEMENT AND MAINTENANCE

A. GUARANTEE:

ACCEPTANCE OF GRADING AND SEEDING SHALL BE BY LANDSCAPE ARCHITECT AND/OR OWNER. THE CONTRACTOR SHALL ASSUME MAINTENANCE RESPONSIBILITIES UNTIL FINAL ACCEPTANCE. MAINTENANCE SHALL INCLUDE WATERING, WEEDING, RESEEDING AND OTHER OPERATIONS NECESSARY TO KEEP ALL LAWN AREAS IN A THRIVING CONDITION. UPON FINAL ACCEPTANCE, OWNER SHALL ASSUME ALL MAINTENANCE RESPONSIBILITIES. AFTER LAWN AREAS HAVE GERMINATED, AREAS WHICH FAIL TO SHOW A UNIFORM STAND OF GRASS FOR ANY REASON WHATSOEVER SHALL BE RE-SEEDED REPEATEDLY UNTIL ALL AREAS ARE COVERED WITH A SATISFACTORY STAND OF GRASS. MINIMUM ACCEPTANCE OF SEEDED LAWN AREAS MAY INCLUDE SCATTERED BARE SPOTS, NONE OF WHICH ARE LARGER THAN 1 SQUARE FOOT, AND WHEN COMBINED DO NOT EXCEED 2% OF TOTAL SEEDED LAWN AREA.

B. REPLACEMENT:

ANY PLANT UNDER THIS SPEC WHICH IS DEAD, MISSING, UNHEALTHY, OR OTHERWISE NOT ACCEPTABLE AND NOT IN SATISFACTORY GROWING CONDITION DURING CONSTRUCTION MAINTENANCE PERIOD, OR AT THE END OF THE GUARANTEE PERIOD, SHALL BE REMOVED FROM SITE AND REPLACED WITH SUITABLE, ACCEPTABLE PLANT AS SPECIFIED, WITHIN FIVE (5) DAYS.

C. MAINTENANCE: GENERAL CONTRACTOR SHALL PROVIDE TWO YEARS OF LANDSCAPE MAINTENANCE, FROM THE TIME THE PROJECT RECEIVES THE CERTIFICATE OF OCCUPANCY AND THERE AFTER, FOR ALL NEW LANDSCAPE. IF EXISTING LANDSCAPE EXISTS ON-SITE, GENERAL CONTRACTOR IS TO PROVIDE THE OPTION OF MAINTENANCE FOR THE OWNER'S REVIEW.

HERBICIDES NOTES

SEE STEPPING STONE DETAIL FOR

COMPACTED SAND SUB-BASE


NATURAL STEEL EDGING. NO PAINTED


BARRIER AT FINISH GRADE

EDGING SHALL BE USED

1. DEPICTION ABOVE IS FOR STEPPING STONE AREA WITH MULCH.

- 1. APPLICATION OF HERBICIDES SHALL BE IN COMPLIANCE WITH STATE PESTICIDES REGULATIONS. IT IS THE RESPONSIBILITY OF THE LANDSCAPE CONTRACTOR TO CONSULT WITH THE REGULATORY AGENCIES FOR LOCAL HERBICIDES APPLICATION REQUIREMENTS.
- 2. IF THERE IS A DISCREPANCY BETWEEN STATE REGULATIONS AND ADDITIONAL REQUIREMENTS BELOW, MOST STRINGENT SHALL RULE
- 3. NO AERIAL APPLICATION OF HERBICIDES IS PERMITTED ON SITE.
- 4. CARCINOGENS AND EPA TOXIC CATEGORY I AND II ARE PROHIBITED TO USE ON SITE.







CEI ENGINEERING ASSOCIATES, INC.
3108 SW REGENCY PKWY
BENTONVILLE, AR 72712
PHONE: (479) 273-9472
FAX: (479) 273-0844

RESTAURANT DEPOT
---1901-1915 MENAUL BLVD NE
ALBUQUEQUE, NEW MEXICO

FOR BIDDING NOT FOR CONSTRUCTION

PROFESSIONAL OF RECORD JDG
PROJECT MANAGER JEH
DESIGNER HMK
CEI PROJECT NUMBER 32348
DATE 8/22/2022
REVISION REV-0

LANDSCAPE NOTES

SHEET NUMBER

© 2022 CEI ENGINEERING ASSOCIATES, INC.

PROF PROJE DESIG