

City of Albuquerque

P.O. BOX 1293 ALBUQUERQUE, NEW MEXICO 87103

September 14, 1982

Mr. Raymond Hensley Star Hill Company, Inc. P. O. Box 10158 Alameda, New Mexico 87184

Re: Classic Hotel's Comprehensive Drainage Plan Dated 8/12/82 File No. H19-D3

Dear Mr. Hensley:

Thank you for your recent submittal of the Comprehensive Drainage Plan requested by me for the subject site. You may pick up your green tag from this office at your convenience.

Sincerely

Fred J. Aguirre, PE

b.) ProvisiCivil Engineer/Hydrology went the abatting sites from draing through this site.

FJA/el

cc: V Drainage File Reading File



P.O. BOX 10158 ALAMEDA, NEW MEXICO 87184 NM LICENSE 18160 TELEPHONE (505) 344-3471

Seprember 9, 1982

City of Albuquerque City Engineers P. O. Box 1293 Albuquerque, NM

Attn: Mr. Fred Aguirre

Dear Mr. Aguirre:

Enclosed are two copies of the as-built site development plans for the Classic Hotel.

I believe this completes the owner's obligation to the city for the release of the occupancy certificate. I appreciate your cooperation and patience in this matter.

If there are any questions, please call.

Thank you,

STAR HILL COMPANY

roject Coordinator

RH/tm Enc. SHELL STATION REMOVAL.

17

THE CLASSIC HOTEL

August 20, 1981

Star Hill Co., Contractors

Purpose:

The purpose of this study is to insure that the removal of the Shell Station and subsequent re-paving of the .548 acre parcel at the corner of Louisiana and Menaul will comply with the infent of the drainage report for the Classic Hotel.

Existing Site:

The existing 6.579 acre site contains the Classic Hotel, its surrounding parking areas and landscaped areas, and a Shell Station at the Southwest corner. Four ponding areas were originally specified in the site's drainage report. Fonds A,B, and C were built as specified, and the City of Albuquerque allowed pond D to be built smaller than specified under the stipulation that it be enlarged to the specified size when the Shell Station was removed.

Discription of work:

This project consists of removing the Shell Station and extending pond D. Our grading plan extends pond D towards the south and releases it through the existing grating. The total volume is 1780 Cu. Ft. The total required volume is 1320 Cu. Ft. An overflow will be provided at the top of the pond to release any excess runoff.





moore bryan & associates

william jette leon ross rusty shafter wayne andrews thomas fackelmen

> ARCHITECTS ENGINEERS PLANNERS

5608 zuni s.e. p.o. box 8266 iquerque, n.m. 87108 chone 505/268-6783 The land parcel under development is a portion of Block 1 and all of Block 2 of the Broad Acres Subdivision. It is bounded basically by Menaul Blvd., Louisiana Blvd., Phoenix Ave. and Chama St. The parcel contains 6.046 acres. It is presently essentially undeveloped land with a slope of 1.6% from northeast to southwest. For the 100 year storm, runoff generated would be as follows:

$$Q_1 = 6.046 \times 6.37 \times 0.4 = 15.41 \text{ cfs}$$

All of the area except Pond D will be considered as hard surfaced.

This amounts to 96% or 253,000 sf. For this condition, runoff would be:

 $Q_2 = 5.808 \times 7.42 \times 0.9 = 38.79$ cfs where t_c is developed for the most severe slope conditions.

The total volume of retention required is:

$$V = (0.9 - 0.4) \times \frac{2.4}{12} \times 263,364 = 26,336 \text{ cf}$$

Because of the siting of the building, it was necessary to develop four retention ponds. The pond retention volumes and watershed areas are as shown below. The roof areas which contribute to flow are included in the appropriate areas.

Pond		Retention Volume	Watershed Area
Α		10,920 cf	108,300 sf
В		8,560 cf	60,000 sf
С		7,280 cf	72,700 sf
D		1,320 cf	12,000 sf

Drainage Report Classic Hotel May 7, 1979 Page 2

Ponding areas B and D drain to the existing storm sewer system. Ponding area D is a landscaped area and little flow is anticipated except during the 100 year storm. Drainage from the pond inlets is controlled by orifice plates, with 1 1/8" diameter drilled orifices placed on the inlet structure. Design for the required perforations is as tabulated below:

Pon	C.F.	Release Time Hrs.	Release Rate CFS	Flow Rate per Orifice CFS	Perforations .
В	8,560	- 6	0.396	0.019	21
D	1,320	. 12	0.031	0.012	2

Pond B release time was reduced to keep icing problems to a minimum.

Ponds A and C are designed as total retention reservoirs. The media will be washed cobbles with a void volume of 35%. Flow will enter thru a fully grated inlet designed to permit dispersion in all directions. The reservoir will be overexcavated by 2 ft. more than the depth of cobbles, the stone placed and covered by a waterproof membrane and the soil replaced and compacted for pavement.

The reservoirs are as dimensioned in the following table:

Pond	Retention Volume Required	W x L x D ofCobbles in feet	Volume X 35% voids
Α	10,920 cf	100 x 78 x 4	10,920 cf
С	7,280 cf	40 x 100 x 5.2	7,280 cf



M. DENISH AND ASSOCIATES, INC.
Consultants to Developers

JUN 0 4 1982 CITY ENGINEER

June 2, 1982

Mr. Richard Heller City Engineer City of Albuquerque P.O. Box 1293 Albuquerque, NM 87103

Re: Z-72-231 Revised Development Plan

Dear Mr. Heller:

Pursurant to our conversation resterday afternoon, I am writing to confirm that the Los Pueblos Partnership will provide an easement from the site of The Classic Hotel (Tract I-A of the Broad Acres Subdivision) across the property line dividing it from the former site of the Shell gasoline station (Lots 2,3 and portions of Lots I and 4) as may be required for the surface conveyance storm-water. Both properties are presently in the same ownership. Maintenance of this easement is hereby made a condition of sale or further development of either property.

H-19-D3

Sincerely yours,

Herbert M. Denish

cc: L.W. Reynolds, Jr.

HMD/gg

	RSH_BYA	ADM
	HRO	SUR
	(3) CIN 44	SUR
	res	SEC
1:	INSP	(E)
Hadron	HYDRO	FE URN
This to be	against the	land per 6/8 ne (505) 842-6461

20 First Plaza, Suite 320 / Post Office Box 2001 / Albuquerque, New Mexico 87103 / Telephone (505) 842-6461



P.O. BOX 10158 ALAMEDA. NEW MEXICO 87114

February 23, 1981

Drainage and Flood Contro! City of Albuquerque 123 Central AVE NW Albuquerque, NM 87103

Attu: Fred Aguirre

RE: The Classic Hote1 6815 Menaul NF Albuquerque, № 87110

Gentlemen:

This is to confirm our conversation of February 19, 1981. As we discussed, your staff finds the building and site of the Classic Hotel acceptable for a final certificate of occupancy.

There is, however, a condition that exists at the boundary of the hotel property and that of the shell station to the southwest. It is understood that drainage design at that point is unacceptable on a permanent basis.

In view of the current acquisition proceedings of the station by the hotel, it was mutually agreeded that permanent remedies would be postponed to a later date. Specifically, that in approximately sixty (60) days a redesign of the drainage system will be submitted to the city building department in conjunction with various other items for review and approval.

I appreciate your help on this project. If you have any questions please call.

Sincerely,

Project Coordinate

RH/md
cc: C. O.
 Jack Holloway
 Bud Reynolds
 Leon Ross
 George Hensley

nto



M. DENISH AND ASSOCIATES, INC.
Consultants to Developers

H19-03

February 6, 1981

Mr. Richard Heller City Engineer City of Albuquerque P. O. Box 1293 Albuquerque, New Mexico 87103

Re: The Classic Hotel Drainage

Dear Dick:

Enclosed you will find the original and two copies of the letter requested by your department regarding the drainage structures at the Classic Hotel.

I hope this will meet your needs; if I can be of further help, be sure to give me a call.

Sincerely yours,

Hut

Herbert M. Denish

HMD/mk

Enclosures

cc: Mr. C. D. Sheppard

Mr. Bruno Conegliano

Mr. Fred Aguirre

RECEIVED

FEB 0 6 1981

CITY ENGINEER

20 First Plaza, Suite 320 / Post Office Box 2001 / Albuquerque. New Mexico 87103 / Telephone (505) 842-6461



william jette leon ross rusty shaffer wayne andrews jon moore

ARCHITECTS ENGINEERS PLANNERS

5608 zuni s.e. p.o. box 8266 albuquerque, n.m. 87198 telephone 505/268-6783 February 5, 1981

City of Albuquerque City Hall Albuquerque, New Mexico

Re: The Classic Hotel Menaul and Louisiana, N.E. Albuquerque, New Mexico

Gentlemen:

Based on our periodic inspections of the above referenced proj_t, this letter will confirm that the drainage structures for the retention of water were constructed in accordance with our plans and specifications.

Very truly yours,

GARLAN D. BRYAN

GDB:m1s



william jette leon ross rusty shaffer wayne andrews jon moore

ARCHITECTS ENGINEERS PLANNERS

5608 zuni s.e. p.o. box 8266 albuquerque, n.m. 87198 telephone 505/268-6783 February 5, 1981

City of Albuquerque City Hall Albuquerque, New Mexico

Re: The Classic Hotel Menaul and Louisiana, N.E. Albuquerque, New Mexico

Gentlemen:

Based on our periodic inspections of the above referenced project, this letter will confirm that the drainage structures for the retention of water were constructed in accordance with our plans and specifications.

Very truly yours,

Sala O Byan

GARLAN D. BRYAN

GDB:m1s



william jette leon ross rusty shaffer wayne andrews jon moore

ARCHITECTS ENGINEERS PLANNERS

5608 zuni s.e. p.o. box 8266 albuquerque, n.m. 87198 telephone 505/268-6783 February 5, 1981

City of Albuquerque City Hall Albuquerque, New Mexico

Re: The Classic Hotel
Menaul and Louisiana, N.E.
Albuquerque, New Mexico

Gentlemen:

Based on our periodic inspections of the above referenced project, this letter will confirm that the drainage structures for the retention of water were constructed in accordance with our plans and specifications.

Very truly yours,

GARLAN D. BRYAN

GDB:mls



February 2, 1981

Building Inspection Department City of Albuquerque 123 Central Avenue NW Albuquerque, NM 87103

> RE: The Classic Hotel 6815 Menaul NE Albuquerque, NM 87110

Gentlemen:

I am respectfully requesting an extension of the temporary occupancy certificate be allowed for a period of sixty (60) days effective immediately, for the property and buildings located at 6815 Mena NE. This property will be operated as a commercial facility known as ". Classic Hotel".

Thank you for your consideration in this matter.

Sincerely,

Raymond Ex Hensley Project Coordinator

REH/md

CC: C.O. File





william jetta leon ross rusty shaffer wayne andrews jon moore

> ARCHITECTS ENGINEERS PLANNERS

5608 zuni s.e. 3.o. box 8268 querrue, n.m. 87198 one 505/268-6783 October 6, 1980

H19-03

City of Albuquerque City Hall Albuquerque, New Mexico

Re: The Classic Hotel Menaul and Louisiana Albuquerque, New Mexico

Gentlemen:

Based on our periodic inspections of the above project, this letter will confirm, to the best of our knowledge and belief, that the drainage structures for retention of water were constructed in accordance with our plans and specifications.

Very truly yours,

GARLAN D. BRYAN

GDB:mls



DENISH AND ASSOCIATES, INC. Consultants to Developers

Herbert M. Denish

September 24, 1980

Mr. L. W. "Bud" Reynolds Controller The Maloof Companies c/o First National Bank in Albuquerque P. O. Box 1305 Albuquerque, New Mexico 87103

RE: Classic Hotel Storm Drainage System

Dear Mr. Reynolds:

We have received a verbal request from Richard Heller, Chief City Engineer, to establish a schedule for the inspection of the storm water drainage system at the hotel prior to final inspection and issuance of the Certificate of

The system design, with its underground retention ponds and discharge outlets, is unusual and Mr. Heller would like the opportunity to inspect the discharge pipes and rock masses prior to back-filling and paving of the parking lots. in addition, Mr. Helier would like to inspect the final grading of the parking lot to assure that surface retention areas and discharge pipes will function properly.

These inspections should be coordinated directly between the architect or contractor and the City Engineering office. Mr. Heller can be reached at 766-7441.

Sincerely yours, Lawrence S. Kline

LSK/mk

ce: Mr. Richard Heller

(cas DES FILE INSP RETURN

ADM SUR COUN SEC

Find A.

Post Office Box 2001 / Albuquerque, New Mexico 87103 / Telephone (505) 842-6461



City of Albuquerque

P.O. BOX 1293 ALBUQUEROUE, NEW MEXICO 37103

MAYOR

David Rusk

Ma 30, 1979

Mr. Wayne Andrews Flatow, Moore, Bryan & Assoc., Inc. 5608 Zuni S.E. Albuquerque, New Mexico 87108

Re: Los Pueblos Hotel

Dear Mr. Andrews:

Enclosed is a copy of a letter directed to your attention almost two months ago regarding the Los Pur los Hotel. Presently, grading and excavation is proceeding on the referenced site and I under from Mr. Fied Aguirre that a building permit has not yet been issued.

As of today, the City has not received the plans requested for in the second paragraph of the enclosed letter, nor any coordination has been established as requested. The proximity of the ponds to two major arterials without outflow provisions can seriously damage the existing pavement. It is, therefore, requested that construction plans indicated above be expeditiously submitted to this office in order to prevent an immediate "stop order",

Very truly yours,

Richard Heller City Engineer

BC/RSH/fs Enclosure

cc - Bruno Conegliano, Assist. City Engineer-Hydrology Fred Aguirre, Assist. Hydrology Engineer Dwayne Sheppard, Assist. City Engineer-Field George Ball -Drainage File



City of Albuquerque

P.O. BOX 1293 ALBUQUERQUE, NEW MEXICO 87103

MAYOR

David Rusk

April 3, 1979

Mr. Wayne Andrews Flatow, Moore, Bryan & Assoc., Inc. 5608 Zuni S.E. Albuquerq.e, N.M. 87103

Re: Los Pueblos Hotel

Dear Mr. Andrews:

I have reviewed the drainage report for the captioned project and I am in general agreement with the scheme proposed. Nevertheless I note that it is impossible to verify the figures of the individual watershed areas since no indication is given on how the roof of the building will drain. Please supply this information to demonstrate that no single ponding area will be overlooked. I am also requesting that one single discharge outlet be provided for the two ponds on the west side of the property. The storm sewer in Louisiana is deep enough to allow connection of the inlet in pond D to the inlet in pond C and from there to the manhole indicated. I am also requesting that a definite physical barrier be constructed around the landscaped ponding areas for safety reasons. Minor corrections in the grading plan will have to be performed and I suggest that your designer contact my assistant, Mr. Fred Aguirrez.

The actual implementation of the drainage plan within the streets R/W will require that the developer enter in an agreement with the City with a standard $AE^{\ast}A$ contract. Detailed plans of the planned connections to the City sewers will have to be submitted for review by the appropriate City departments and for supervision and inspection by the office of the Assistant City Egnineer-Construction.

Since substantial disruption to the traffic will result because of the construction, I'd like to suggest a meeting between yourself, the contractor for the developer, Mr. Dwayne Sheppard-Assistant City Engineer-Field, and Bob Fosnaugh-Traffic Engineer, in order to discuss the modality of execution. If you feel you need to discuss this matter further, please feel free to contact my office.

Very truly yours,

Bu Comple

Bruno Conegliano Assistant City Engineer-Hydrology

BC/fs

cc - Bob Fosnaugh, Traffic Engineer Dwayne Sheppard, Asst. City Engineer-Field

- AN EQUAL OPPORTUNITY EMPLOYER =



william jette leon ross rusty shaffer wayne andrews thomas fackelman

> ARCHITECTS ENGINEERS PLANNERS

5608 zuni s.e. p.o. box 8266 albuquerque, n.m. 87108 telephone 505/268-6783

A: 11 10, 1979

City of Albuquerque P. O. Box 1293 Albuquerque, New Mexico 87103

Attn: Bruno Conegliano Assistant City Engineer - Hydrology

Re: Los Pueblos Hotel Menaul and Louisana N.E.

Gentlemen:

We are transmitting to your office three (3) prints which are red-marked to show where the water from the roof run-off will be directed.

They also Indicate Panels "C" and "D" linked together with one discharge point on Louisiana.

Thank you.

Sincerely,

FLATOW, MOORE, BRYAN & ASSOCIATES

Wayne G. Andrews

WGA/mm

cc: Dick Heller - City Engineer



å

flatow moore bryan &

william jette leon ross rusty shaffer wayne andrews thomas fackelman

associates

ARCHITECTS ENGINEERS PLANNERS

5608 zuni s.e. p.o. box 8266 albuquerque, n.m. 87108 telephone 505/268-6783

BEREIVED Action of Files

SAR 3 0 1979

March 27, 1979



City Engineers Office City of Albuquerque P. O. Box 1293 87103 Albuquerque, New Mexico

Attn: Mr. Heller

Los Pueblos Hotel Re: Louisiana and Menaul Final SU-1 Review

Gentlemen:

We are transmitting to your office a signed copy of the Drainage Report for the above-mentioned project.

Your prompt attention to this matter will be greatly appreciated.

Thank you.

Sincerely,

FLATOW, MOORE, BRYAN & ASSOCIATES

May

Wayne G. Andrews

WGA/mm

Encl.





william jette leon ross rusty shaffer wayne andrews

ARCHITECTS ENGINEERS PLANNERS

5608 zuni s.e. p.o. box 8266 albuquerque, n.m. 87108 telephone 505/268-6783

RECEIVED

MAR 3 0 1979

DRAINAGE REPORT - LOS PUEBLOS HOTEL

CITY MICHNEERS

The land parcel under development is a portion of Block 1 and all of Block 2 of the Broad Acres Subdivision. It is bounded basically by Menaul Blvd., Louisiana Blvd., Phoenix Ave. and Chama St. The parcel contains 6.046 acres. It is presently essentially undeveloped land with a slope of 1.6% from northeast to southwest. For the 100 year storm, runoff generated would be as follows:

 $Q_1 = 6.046 \times 6.37 \times 0.4 = 15.41 \text{ cfs}$

All of the area except Ponds A, C and D will be considered as hard-surfaced. This amounts to 90% or 237,028 sf. For this condition, runoff would be:

 $Q_2 = 5.441 \times 7.42 \times 0.9 = 36.33$ where t_c is developed for the most severe slope conditions.

The total volume of retention required is:

$$V = (0.9 - 0.4) \times \frac{2.4}{12} \times 263,364 = 26,336 \text{ cf}$$

Because of the siting of the building, it was necessary to develop four retention ponds. The pond retention volumes and watershed areas are as shown below. The roof areas which contribute to flow are included in the appropriate areas.

Pond	Retention Volume	Watershed Area
Α	13,000 cf	99,800 sf
В	8,560 cf	60,000 sf
С	6,600 cf	65,300 sf
D	1,320 cf	12,000 sf

RESEIVED.

NAR 30 1979

Page 5 - Drainage Report - Los Pueblos Hotel - March 21, 1979

All of the ponding areas except Pond B are landscaped and little flow is anticipated from the pond drains except for the 100 year storm.

Drainage from the pond inlet is controlled by orifice plates, with 1 1/8" diameter drilled orifices, placed on the inlet structure. Design for the required perforations is as tabulated below:

Pond	Capacity	Release Time Hrs.	Releast Rate CFS	Flow Rate per Orifice CFS	Perforations
A	13,000	12	0.301	0.019	16
В	8,560	6	0.396	0.019	21
С	6,600	12	0.153	0.019	8
D	1,320	12	0.031	0.019	2

Pond B release time was reduced to keep icing problems to a minimum.



RESEIVED.

NAR 30 1979

Pages - Drainage Report - Los Pueblos Hotel - March 21, 1979

CITY MARINE PAGES - Drainage Report - Los Pueblos Hotel - March 21, 1979

All of the ponding areas except Pond B are landscaped and little flow is anticipated from the pond drains except for the 100 year storm.

Drainage from the pond inlet is controlled by orifice plates, with 1 1/8" diameter drilled orifices, placed on the inlet structure. Design for the required perforations is as tabulated below:

Pond	Capacity	Release Time Hrs.	Releast Rate CFS	Flow Rate per Orifice CFS	Perforations	
A	13,000	12	0.301	0.019	16	
В	8,560	6	0.396	0.019	21	
С	6,600	12	0.153	0.019	8	
D	1,320	12	0.031	0.019	2	

Pond B release time was reduced to keep icing problems to a minimum.





william jette leon ross rusty shaffer wayne andrews

ARCHITECTS ENGINEERS PLANNERS

5608 zuni s.e. p.o. box 8266 albuquerque, n.m. 87108 telephone 505/268-6783

DRAINAGE REPORT - LOS PUEBLOS HOTEL

The land parcel under development is a portion of Block 1 and all of Block 2 of the Broad Acres Subdivision. It is bounded basically by Menaul Blvd., Louisiana Blvd., Phoenix Ave. and Chama St. The parcel contains 6.046 acres. It is presently essentially undeveloped iand with a slope of 1.6% from northeast to southwest. For the 100 year storm, runoff generated would be as follows:

$$Q_1 = 6.046 \times 6.37 \times 0.4 = 15.41 \text{ cfs}$$

All of the area except Ponds A, C and D will be considered as hard-surfaced. This amounts to 90% or 237,028 sf. For this condition, runoff would be:

 $Q_2 = 5.441 \times 7.42 \times 0.9 = 36.33$ where t_c is developed for the most severe slope conditions.

The total volume of retention required is:

$$V=(0.9-0.4)\times\frac{2.4}{12}\times263,364=26,336$$
 cf Because of the siting of the building, it was necessary to develop four retention ponds. The pond retention volumes and watershed areas are as shown below. The roof areas which contribute to flow are included in the appropriate areas.

Pond	Retention Volume	Watershed Area
Α	13,000 cf	99,800 sf
В	8,560 cf	60,000 sf
C	6,600 cf	65,300 sf
D	1,320 cf	12,000 sf


Page 2 - Drainage Report - Los Pueblos Hotel - March 21, 1979

All of the ponding areas except Pond B are landscaped and little flow is anticipated from the pond drains except for the 100 year storm.

Drainage from the pond injet is controlled by orifice plates, with 1 1/8" diameter drilled orifices, placed on the injet structure. Design for the required perforations is as tabulated below:

Pond	Capacity	Release Time Hrs.	Releast Rate CFS	Flow Rate per Orifice CFS	Perforations :
A	13,000	12	0.301	0.019	16
В	8,560	6	0.396	0.019	21
С	6,600	12	0.153	0.019	8
D	1,320	12	0.031	0.019	2

Pond B release time was reduced to keep icing problems to a minimum.



WHILE Y	ou	WERE AWAY	_A:M
Bob S	h	ephand	
or			
PHONE NO. 2L	øΥ	-10783	
TELEPHONED S	V	RET'D YOUR CALL	
PLEASE CALL	Y	URGENT	25
WILL CALL AGAIN		WANTS TO SEE YOU	
ESSAGE			

DETOBER	1 4	A DEC	EMBER 1 1 3
123			3 4 5 6 10 11 12 13
9 13 14 15 16 17 1	18	14 15 1 21 22 2 28 29 3	6 17 18 19 20 3 24 25 26 27
19 20 21 22 23 24 7 27 28 29 30 31	NOV.	1980 23 23	0 31
	_ NUV.		
1:00			
1:30			
9:00			
9:30			
10:00			5
10:30			
11:00		1/2	1
11:30	Date	1 vens	len
12:00	Ling		-)
	50		
1:00	~7	100	
1:30	ON	11	
	91		7
1:30	9-		-/
00.00	9.		7
1:30 250.00 2:30	9.		7
1:30 250 . O O 2:30 3:00	9.		1

Hotel a Conisram es Mand Flatin. Hotel for la Pueblo



william jette teon ross rusty shaffer wayne andrews

ARCHITECTS ENGINEERS PLANNERS

5608 zuni s.e. p.o. box 8266 albuquerque, n.m. 87108 telephone 505/268-6783

DRAINAGE REPORT - LOS PUEBLOS HOTEL

The land parcel under development is a portion of Block 1 and all of Block 2 of the Broad Acres Subdivision. It is bounded basically by Menaul Blvd., Louisiana Blvd., Phoenix Ave. and Chama St. The parcel contains 6.046 acres. It is presently essentially undeveloped land with a slope of 1.6% from northeast to southwest. For the 100 year storm, runoff generated would be as follows:

 Q_1 = 6.046 x 6.37 x 0.4 = 15.41 cfs All of the area except Ponds A, C and D will be considered as hard-surfaced. This amounts to 90% or 237,028 sf. For this condition, runoff would be:

 Q_2 = 5.441 \times 7.42 \times 0.9 = 36.33 where t_c is developed for the most severe slope conditions.

The total volume of retention required is:

 $V = (0.9 - 0.4) \times \frac{2.4}{12} \times 263,364 = 26,336 \text{ cf}$ Because of the siting of the building, it was necessary to develop four retention ponds. The pond retention volumes and watershed areas are as shown below. The roof areas which contribute to flow are included in the appropriate areas.

Pond	Retention Vo		Watershed	Area
A	13,000 cf	10893 ft	99,800	
В	8,560 cf	1	60,000	st morenat
С	6,600 cf			
D	1,320 cf	1573 ft3	12,000	sf

THE VOLUMES AS IN REO BRE THE VOLUMES DRAINING TO ITS
RESPECTIVE PONDS. THESE VOLUMES DO NOT INCLUDE THE RUN OFF
FROM THE ROUF.

Page 2 - Drainage Report - Los Pueblos Hotel - March 21, 1979

All of the ponding areas except Pond B are landscaped and little flow is anticipated from the pond drains except for the 100 year storm.

Drainage from the pond inlet is controlled by orifice plates, with 1 1/8" diameter drilled orifices, placed on the inlet structure. Design for the required perforations is as tabulated below:

Po	ond Capacity	Release Time Hrs.	Releast Rate CFS	Flow Rate per Orifice CFS	Perforations ·
A	13,000	12	0.301	0.019	16
В	8,560	6	0.396	0.019	21
С	6,600	12	0.153	0.019	8
D	1,320	12	0.031	0.019	2

Pond B release time was reduced to keep icing problems to a minimum.



william jette leon ross rusty shaffer wayne andrews

ARCHITECTS ENGINEERS PLANNERS

5608 zuni s.e. p.o. box 8266 albuquerque, n.m. 87108 telephone 505/268-6783

DRAINAGE REPORT - LOS PUEBLOS HOTEL

The land parcel under development is a portion of Block 1 and all of Block 2 of the Broad Acres Subdivision. It is bounded basically by Menaul Blvd., Louisiana Blvd., Phoenix Ave. and Chama St. The parcel contains 6.046 acres. It is presently essentially undeveloped land with a slope of 1.6% from northeast to southwest. For the 100 year storm, runoff generated would be as follows:

 $Q_1=6.046\times6.37\times0.4=15.41$ cfs All of the area except Ponds A, C and D will be considered as hard-surfaced. This amounts to 90% or 237,028 sf. For this condition, runoff would be:

 $Q_2 = 5.441 \times 7.42 \times 0.9 = 36.33$ where t_c is developed for the most severe slope conditions.

The total volume of retention required is:

$$V = (0.9 - 0.4) \times \frac{2.4}{12} \times 263,364 = 26,336 \text{ cf}$$

Because of the siting of the building, it was necessary to develop four retention ponds. The pond retention volumes and watershed areas are as shown below. The roof areas which contribute to flow are included in the appropriate areas.

Pond	Retention Volume	Watershed Area
Α	13,000 cf	99,800 sf
В	8,560 cf	60,000 sf
С	6,600 cf	65,300 sf
D	1,320 cf	12,000 sf

All of the ponding areas except Pond B are landscaped and little flow is anticipated from the pond drains except for the 100 year storm.

Drainage from the pond inlet is controlled by orifice plates, with 1 1/8" diameter drilled orifices, placed on the inlet structure. Design for the required perforations is as tabulated below:

Pond	Capacity	Release Time Hrs.	Releast Rate CFS	Flow Rate per Orifice CFS	Perforations '
A	13,000	12	0.301	0.019	16
В	8,560	6	0.396	0.019	21
C	6,600	12	0.153	0.019	8
D	1,320	12	0.031	0.019	2
					and the second

Pond B release time was reduced to keep icing problems to a minimum.



william jette leon ross rusty shaffer wayne andrews thomas fackelman

> ARCHITECTS ENGINEERS PLANNERS

5608 zuni s.e. p.o. box 8266 Ibuquerque, n.m. 87108 Iephone 505/268-6783

DRAINAGE REPORT - THE CLASSIC HOTEL

The land parcel under development is a portion of Block 1 and all of Block 2 of the Broad Acres Subdivision. It is bounded basically by Menaul Blvd., Louisiana Blvd., Phoenix Ave. and Chama St. The parcel contains 6.046 acres. It is presently essentially undeveloped land with a slope of 1.6% from northeast to southwest. For the 100 year storm, runoff generated would be as follows:

 $Q_1 = 6.046 \times 6.37 \times 0.4 = 15.41 \text{ cfs}$

All of the area except Pond D will be considered as hard-surfaced.

This amounts to 96% or 253,000 sf. For this condition, runoff would be:

 $\rm Q_2$ = 5.808 \times 7.42 \times 0.9 = 38.79 cfs where t_c is developed for the most severe slope conditions.

The total volume of retention required is:

$$V = (0.9 - 0.4) \times \frac{2.4}{12} \times 263,364 = 26,336 \text{ cf}$$

Because of the siting of the building, it was necessary to develop four retention ponds. The pond retention volumes and watershed areas are as shown below. The roof areas which contribute to flow are included in the appropriate areas.

Pond	Retention Volume	Watershed Area
A	10,920 cf	108,300 sf
В	8,560 cf	60,000 sf
c	7,280 cf	72,700 sf
D	1,320 cf	12,000 sf

Drainage Report Classic Hotel May 7, 1979 Page 2

Ponding areas B and D drain to the existing storm sewer system. Ponding area D is a landscaped area and little flow is anticipated except during the 100 year storm. Drainage from the pond inlets is controlled by orifice plates, with 1 1/8" diameter drilled orifices placed on the inlet structure. Design for the required perforations is as tabulated below:

Pone	C.F.	Release Time Hrs.	Release Rate CFS	Flow Rate ner Orifice CFS	Perforations
В	8,560	6	0.396	0.019	21
D	1,320	12	0.031	0.012	2

Pond B release time was reduced to keep icing problems to a minimum.

Ponds A and C are designed as total retention reservoirs. The media will be washed cobbles with a void volume of 35%. Flow will enter thru a fully grated inlet designed to permit dispersion in all directions. The reservoir will be overexcavated by 2 ft. more than the depth of cobbles, the stone placed and covered by a waterproof membrane and the soil replaced and compacted for pavement.

The reservoirs are as dimensioned in the following table:

Pond	Retention Volume Required	W x L x D ofCobbles in feet	Volume X 35% voids
A	10,920 cf	100 × 78 × 4	10,920 cf
C	7,280 cf	40 x 100 x 5.2	7,280 cf



w Iliam jette leon ross rusty shaffer wayne andrews thomas lackelman

> ARCHITECTS ENGINEERS PLANNERS

56()6 zuni s.e. p.c. box 8266 albuquerque. n.m. 87108 telephone 505/268-6783

DRAINAGE REPORT - THE CLASSIC HOTEL

The land parcel under development is a portion of Block 1 and all of Block 2 of the Broad Acres Subdivision. It is bounded basically by Menaul Blvd., Louisiana Blvd., Phoenix Ave. and Chama St. The parcel contains 6.046 acres. It is presently essentially undeveloped land with a slope of 1.6% from northeast to southwest. For the 100 year storm, runoff generated would be as follows:

$$Q_1 = 6.046 \times 6.37 \times 0.4 = 15.41 \text{ cfs}$$

All of the area except Pond D will be considered as hard-surfaced.

This amounts to 96% or 253,000 sf. For this condition, runoff would be:

 $Q_2 = 5.808 \times 7.42 \times 0.9 = 38.79$ cfs where t_c is developed for the most severe slope conditions.

The total volume of retention required is:

$$V = (0.9 - 0.4) \times \frac{2.4}{12} \times 263,364 = 26,336 \text{ cf}$$

Because of the siting of the building, it was necessary to develop four retention ponds. The pond retention volumes and watershed areas are as shown below. The roof areas which contribute to flow are included in the appropriate areas.

Pond	Retention Volume	Watershed Area
Α	10,920 cf	108,300 sf
В	8,560 cf	60,000 sf
C	7,280 cf	72,700 sf
D	1,320 cf	12,000 sf

Drainage Report Classic Hotel May 7, 1979 Page 2

17 1

Ponding areas B and D drain to the existing storm sewer system. Ponding area D is a landscaped area and little flow is anticipated except during the 100 year storm. Drainage from the pond inlets is controlled by orifice plates, with 1 1/8" diameter drilled orifices placed on the inlet structure. Design for the required perforations is as tabulated below:

Pond	Capacity C.F.	Release Time Hrs.	Release Rate CFS	Flow Rate per Orifice CFS	Perforations
В	8,560	6	0.396	0.019	21
D	1,320	12	0.031	0.012	2

Ponds A and C are designed as total retention reservoirs. The media will be washed cobbles with a void volume of 35%. Flowwill enter thru a fully grated inlet designed to permit dispersion in all directions. The reservoir will be overexcavated by 2 ft. more than the depth of cobbles, the stone placed and covered by a waterproof membrane and the soil replaced and compacted for pavement.

The reservoirs are as dimensioned in the following table:

Pond	Retention Volume Required	W x L x D ofCobbles in feet	Volume X 35% voids
Α	10,920 cf	100 × 78 × 4	10,920 cf
С	7,280 cf	40 x 100 x 5.2	7,280 cf



william jette leon ross rusty shaffer wayne andrews thomas fackelman

> ARCHITECTS ENGINEERS PLANNERS

5608 zuni s.e. p.o. box 8266 buquerque, n.m. 87108 lephone 505/268-6783

DRAINAGE - REPORT - THE CLASSIC HOTEL

The land parcel under development is a portion of Block I and all of Block 2 of the Broad Acres Subdivision. It is bounded basically by Menaul Blvd., Louisiana Blvd., Phoenix Ave. and Chama St. The parcel contains 6.046 acres. It is presently essentially undeveloped land with a slope of 1.6% from northeast to southwest. For the 100 year storm, runoff generated would be as follows:

All of the area except Pond D will be considered as hard-surfaced.

This amounts to 96% or 253,000 sf. For this condition, runoff would be: $Q_2 = 5.808 \times 7.42 \times 0.9 = 38.79$ cfs where t_c is developed for

the most severe slope conditions.

The total volume of retention required is:

 $V = (0.9 - 0.4) \times \frac{2.4}{12} \times 263,364 = 26,336 \text{ cf}$

Because of the siting of the building, it was necessary to develop four retention ponds. The pond retention volumes and watershed areas are as shown below. The roof areas which contribute to flow are included in the appropriate areas.

10,920 cf	108,300 sf	== p.5
8,560 cf	60,000 sf	00.00
7,280 cf	72,700 sf	c 10.50
1,320 cf	12,000 sf	c \$0.55
	8,560 cf 7,280 cf	8,560 cf 60,000 sf 7,280 cf 72,700 sf 1,320 cf 12,000 sf

Drainage Report Classic Hotel May 7, 1979 Page 2

Ponding areas B and D drain to the existing storm sewer system. Ponding area D is a landscaped area and little flow is anticipated except during the 100 year storm. Drainage from the pond inlets is controlled by orifice plates, with 1 1/8" diameter drilled orifices placed on the inlet structure. Design for the required perforations is as tabulated below:

Pond	Capacity	Release Time Hrs.	Release Rate CFS	Flow Rate ner Orifice CFS	Perforations
В	8,560 '	(6.)	0.396	0.019	21 ،
D	1,320 '	12	0.031	0.012	2 .

Pond B release time was reduced to keep icing problems to a minimum.

Fonds (A and C are designed as total retention reservoirs. The media will 24 lux values?)

be washed cobbles with a void volume of 35%. Flow will enter thru a fully grated inlet designed to permit dispersion in all directions. The reservoir will be overexcavated by 2 ft. more than the depth of cobbles, the stone placed and covered by a waterproof membrane and the soil replaced and compacted for pavement.

The reservoirs are as dimensioned in the following table:

Pond	Retention Volume Required	W x L x D ofCobbles in feet	Volume X 35% voids
Α	10,920 cf ·	100 x 78 x 4	10,920 cf
С	7,280 cf ·	40 × 100 × 5.2	7,280 cf

From unlets, Need some outlet pipes in to



City of . Ilbuquerque

P.O. BOX 1293 ALBUQUERQUE, NEW MEXICO 87103

MAYOR David Rusk

May 30, 1979

Mr. Wayne Andrews Flatow, Moore, Bryan & Assoc., Inc. 5608 Zuni S.E. Albuquerque, New Mexico 87108

Re: Los Pueblos Hotel

Dear Mr. Andrews:

Enclosed is a copy of a letter directed to your attention almost two months ago regarding the Los Pueblos Hotel. Presently, grading and excavation is proceeding on the referenced site and I understand from Mr. Fred Aguirre that a building permit has not yet been issued.

As of today, the City has not received the plans requested for in the second paragraph of the enclosed letter, nor any coordination has been established as requested. The proximity of the ponds to two major arterials without outflow provisions can seriously damage the existing pavement. It is, therefore, requested that construction plans indicated above be expeditiously submitted to this office in order to prevent an immediate "stop order",

Very truly yours, Richard S Hill

Richard Heller City Engineer

BC/RSH/fs Enclosure

13

cc - Bruno Conegliano, Assist. City Engineer-Hydrology — Passery Fred Aguirre, Assist. Hydrology Engineer Dwayne Sheppard, Assist. City Engineer-Field George Ball Drainage File



william jette leon ross rusty shaffer wayne andrews thomas fackelman

> ARCHITECTS ENGINEERS PLANNERS

5608 zuni s.e. p.o. box 8266 albuquerque, n.m. 87108 telephone 505/268-6783

DRAINAGE REPORT - THE CLASSIC HOTEL

The land parcel under development is a portion of Block 1 and all of Block 2 of the Broad Acres Subdivision. It is bounded basically by Menaul Blvd., Louisiana Blvd., Phoenix Ave. and Chama St. The parcel contains 6.046 acres. It is presently essentially undeveloped land with a slope of 1.6% from northeast to southwest. For the 100 year storm, runoff generated would be as follows:

$$Q_1 = 6.046 \times 6.37 \times 0.4 = 15.41 \text{ cfs}$$

All of the area except Pond D will be considered as hard-surfaced.

This amounts to 96% or 253,000 sf. For this condition, runoff would be:

 $\rm Q_2$ = 5.808 x 7.42 x 0.9 = 38.79 cfs where $\rm t_c$ is developed for the most severe slope conditions.

The total volume of retention required is:

$$V = (0.9 - 0.4) \times \frac{2.4}{12} \times 263,364 = 26,336 \text{ cf}$$

Because of the siting of the building, it was necessary to develop four retention ponds. The pond retention volumes and watershed areas are as shown below. The roof areas which contribute to flow are included in the appropriate areas.

Pond	Retention Volume	Watershed Area
Α	10,920 cf	108,300 sf
В	8,560 cf	60,000 sf
C	7,280 cf	72,700 sf
D	1,320 cf	12,000 sf

Drainage Report Classic Hotel May 7, 1979 Page 2

Ponding areas B and D drain to the existing storm sewer system. Ponding area D is a landscaped area and little flow is anticipated except during the 100 year storm. Drainage from the pond inlets is controlled by orifice plates, with 1 1/8" diameter drilled orifices placed on the inlet structure. Design for the required perforations is as tabulated below:

Pond	Capacity C.F.	Release Time Hrs.	Release Rate CFS	Flow Rate ner Orifice CFS	Perforations
В	8,560	6	0.396	0.019	21
D	1.320	12	0.031	0.012	2

Pond B release time was reduced to keep icing problems to a minimum.

Ponds A and C are designed as total retention reservoirs. The media will be washed cobbles with a void volume of 35%. Flow will enter thru a fully grated inlet designed to permit dispersion in all directions. The reservoir will be overexcavated by 2 ft. more than the depth of cobbles, the stone placed and covered by a waterproof membrane and the soil replaced and compacted for pavement.

The reservoirs are as dimensioned in the following table:

Pond	Retention Volume Required	W x L x D ofCobbles in feet	Volume X 35% voids
Α.	10,920 cf	100 × 78 × 4	10,920 cf
С	7,280 cf	40 × 100 × 5.2	7,280 cf

SHELL STATION REMOVAL

AT

THE CLASSIC HOTEL

August 20, 1981

Star Hill Co., Contractors

Purpose:

The purpose of this study is to insure that the removal of the Shell Station and subsequent re-paving of the .548 acre parcel at the corner of Louisiana and Menaul will comply with the infent of the drainage report for the Classic Hotel.

Existing Site:

The existing 6.579 acre site contains the Classic Hotel, its surrounding parking areas and landscaped areas, and a Shell Station at the Southwest corner. Four ponding areas were originally specified in the site's drainage report(, Ponds A,B, and C per built as specified, and the City of Albuquerque allowed pond D to be built smaller than specified under the stipulation that it be enlarged to the specified size when the Shell Station was removed.

Discription of work:

This project consists of removing the Shell Station and extending pond D. Our grading plan extends pond D towards the south and releases it through the existing grating. The total volume is 1780 Cu. Ft. The total required volume is 1320 Cu. Ft. An overflow will be provided at the top of the pond to release any excess runoff.





flatow moore bryan & associates

william jette leon ross rusty shafter wayne andrews thomas fackelman

> ARCHITECTS ENGINEERS PLANNERS

5608 zuni s.e. p.o. box 8266 iquerque, n.m. 87108 chone 505/268-6783 The land parcel under development is a portion of Block 1 and all of Block 2 of the Broad Acres Subdivision. It is bounded basically by Menaul Blvd., Louisiana Blvd., Phoenix Ave. and Chama St. The parcel contains 6.046 acres. It is presently essentially undeveloped land with a slope of 1.6% from northeast to southwest. For the 100 year storm, runoff generated would be as follows:

$$Q_1 = 6.046 \times 6.37 \times 0.4 = 15.41 \text{ cfs}$$

All of the area except Pond D will be considered as hard-surfaced.

This amounts to 96% or 253,000 sf. For this condition, runoff would be:

 $Q_2 = 5.808 \times 7.42 \times 0.9 = 38.79$ cfs where t_c is developed for the most severe slope conditions.

The total volume of retention required is:

$$V = (0.9 - 0.4) \times \frac{2.4}{12} \times 263,364 = 26,336 \text{ cf}$$

Because of the siting of the building, it was necessary to develop four retention ponds. The pond retention volumes and watershed areas are as shown below. The roof areas which contribute to flow are included in the appropriate areas.

Pond	Retention Volume	Watershed Area	
A B C D	10,920 cf	108,300 sf	
В	8,560 cf	60,000 sf	
С	7,280 cf	72,700 sf	
D	1,320 cf	12,000 sf	

Drainage Report Classic Hotel May 7, 1979 Page 2

Ponding areas B and D drain to the existing storm sewer system. Ponding area D is a landscaped area and little flow is anticipated except during the 100 year storm. Drainage from the pond inlets is controlled by orifice plates, with 1 1/8" diameter drilled orifices placed on the inlet structure. Design for the required perforations is as tabulated below:


Pond	Capacity C.F.	Release Time Hrs.	Release Rate CFS	Flow Rate per Orifice CFS	Perforations •
В	8,560	6	0.396	0.019	21
D	1,320	. 12	0.031	0.012	2


Pond B release time was reduced to keep icing problems to a minimum.

Ponds A and C are designed as total retention reservoirs. The media will be washed cobbles with a void volume of 35%. Flow will enter thru a fully grated inlet designed to permit dispersion in all directions. The reservoir will be overexcavated by 2 ft. more than the depth of cobbles, the stone placed and covered by a waterproof membrane and the soil replaced and compacted for payement.

The reservoirs are as dimensioned in the following table:

Pond	Retention Volume Required	W x L x D ofCobbles in feet	Volume X 35% voids
Α	10,920 cf	100 × 78 × 4	10,920 cf
C	7,280 cf	40 x 100 x 5.2	7,280 cf





SUITE 1206
FIRST NATIONAL BANK
BUILDING - EAST
ALBUQUERQUE,
NEW MEXICO, 57102
(503) 255-5186

December 4, 1975

Dyer/McClernon Architects 6320 D Linn Avenue, N.E. Albuquerque, New Mexico 87108

Dear Sirs:

Transmitted herewith is the "Storm Drainage Study of 7-Acre Tract at Northeast Corner of Menaul and Louisiana." This study is an analysis in accordance with the requirements of the City of Albuquerque and the Albuquerque Metropolitan Arroyo Flood Control Authority.

Thank you for the opportunity of serving you.

espectfully submitted,

Jacob A. Vigil, P.E. New Mexico Registration No. 4570

STORM DRAINAGE STUDY
7-AGRE TRACT AT NORTHEAST CORNER
OF MENAUL AND LOUISIANA
ALBUQUERQUE, NEW MEXICO

December 4, 1975

JACOB A. VIGIL

Consulting Engineers

Albuquerque, New Mexico

TABLE OF CONTENTS

LETTER OF TRANSMITTAL

STORM	DRAINAGE STUDY	
1.	Purpose Pa	age 1
2.		1
3.		1
4.	Existing Drainage	1
5.	Proposed Development	1
6.	Proposed Drainage Plan	2
7.	Conclusions and Recommendations	2-3
APPEND	IX	
1.	Exhibit A - Design CalculationsPag	e 1-8
2.	Exhibit B - MapPlat	

STORM DRAINAGE STUDY 7-ACRE TRACT AT NORTHEAST CORNER OF MENAUL AND LOUISIANA

- I. <u>Purpose</u>: The purpose of this report is to present means of controlling storm drainage from the above-mentioned tract.
- II. Scope: This report is limited to consideration of runoff from the 7-acre tract under consideration.

General engineering methods are presented for calculation of the storm drainage. No detailed construction drawings are included.

- III. <u>Location</u>: The tract under consideration is at the northeast corner of Menaul Boulevard and Louisiana Boulevard and measures approximately 600 feet by 600 feet.
- IV. Existing Drainage: The report area presently drains into Menaul Boulevard and into Louisiana Boulevard.
- V. <u>Proposed Development</u>: It is proposed to re-grade the tract and to construct buildings and paved parking areas there-on.

VI. Proposed Drainage Plan:

- A. <u>General</u>: It is proposed to restrict flow from the tract during a 100-year storm to a maximum flow equal to the peak flow from the tract before development. Chart 1 of the Master Plan of Drainage, City of Albuquerque was used to define the Project Storm.
- B. <u>Calculations</u>: Sufficient ponding volume must be provided within each of the two tract areas to contain the flows in excess of the design maximum flow.

In addition it will be necessary to construct outlets to the four pond areas of a size which will restrict flow to the maximum cited above.

Calculations are appended as Exhibit A.

VII. Conclusions and Recommendations: The flow from the tract into city streets will not exceed the 100-year flow peak from the same tract in its undeveloped state in the following conditions are met:

- a. Area A, North and. Curb at 08 or higher, 24" 7,A.J. contours as shown in Exhibit B, 4" x 36" outlet as shown.
- b. Area A, South pond. Curb at 06 or higher, contours as shown, 4" x 36" outlet as shown.

- c. Area B, West pond. Curb at 06 or higher, con30"JAJ.
 tours as shown, 4" x 40" gutter outlet as shown.
- d. Area B, East pond. Curb at 07 or higher, contours as shown, 4" x 40" gutter outlet as shown.
- e. The building shall have controlled Roof top drains as added control for Runoff.

EXHIBIT A DRAINAGE REPORT ON TRACT COINER OF MEDIAL & LOUISIANA (DYER/MECLERISM)

Jikos A. Vigil DEC. 3, 1975 SHT. 1 DEB

OI, DETERMINE SLOPE OF DRAININGE AREAS AND TO:

DETECHINED FROM FIGURE 2-3.

VELOCITIES FOR UPLAND

METHOD OF ESTIMATINA TO,

CHAPTER 2 ENGINEERING

FIELD MANUAL, V.S.D.A.

SOIL COUSERVATION SERVICE

TZ = 1/40)

". USE TO SINIUM)

I'. USE TO SINIUM IN ALL CASES BECAUSE RAINEAUL IS RECORDED IN

TIPPING -BUCKET GAGES AND INTENSITY CURVES COMPUTED

IN 5 MIN INCREMENT OF TIME.

EXHIBIT A" DRAIDAGE REPORT (MENNAL LOUISIANA) DEC 3, 1975
SHT. Z OF B

P. DETERMINE INTENSITY:
(FROM CHART), MASTER PLAN OF DRAINAGE - GORDON HERKENHOFF)
++25

AREA A (PAUED): I = 189 = 6.30 TW/HE

AREA B (PAUED): I,00 = 189 = 6.30 IN/HR

AREA A(NATURAL): I,00= 189 = 5.73 IN/HR

AREA B(NATURAL): I 100 - 189 = 5.73 2N/HR

3. DETERMINE PEAK RUNOFF :

ACEA A (PAVED): Q=CIA Q=0.90 (6.30)(3.45 ACRES)

Q = 19,56 CFS

AREA B (PAVED): Q=0,90(6.30)(3.71 ACRES)

= 21.04 CFS

AREA A (NATURAL): Q=0.45 (5.78)(3.45 ACRES)

= 8,90CFS

AREA B(NATURAL): Q=0,46(5.73)(3.71 ACRES) = 9.57 CFS

MAXIMUM DISCHARGE OF POUDIUG AREA FOR DRAINAGE AREA "A" = 8.9 CFS

MAXIMUM DISCHARGE OF PONDING AREA FOR DRAINAGE AREA "B" = 9.6 CES EXHIBIT'A'

DEALUAGE REPORT (MENUALE

JACOB A. VIGIL DEC. 3, 1975 SHT, BOCB

4. DETERMINE VOLUME OF PUNOFF:

SINCE 95% OF 24 HE PERCIPITATION OCCURS IN OHE HOUR

DURATION OF STORM OF I HE IS USED!

FROM USDA 1004R 24-HOUR PRECIPITATION MAP 4-R-34422

PRECIPITATION = 3.0 INCHES

FROM USDA DAILY RAINFALL DISTRIBUTION MAP 4-R-34432 ALBUQUERQUE IS IN SD-1 (75) MAJOR AND SUB LAND RESOURCE AREAS.

FROM STUDIES SOIL CONSERVATION SERVICE HAS DETERMINED LAG TIME (L) = 0.6 TO (TIME OF CONCENTRATION REFERENCE HYDROLOGY HANDBOOK CHAPTER 4, S.C.S.

AREA A (PAVED): V- 3.0(.75)(0.90)(3.45)

V4 = 0.58 AC-FT.

AREA B(PAUED): V= 3.0 (0.75)(0.90)(3.71)

VB . 0.63 AC-FT.

AREA A (NATURAL): V= 30 (0.75) (0.45)(3.45)

V. . 0.26 AL-FT.

AREA B(NATURAL): V = 3.0 (0.75)(0.45)(3,45)


VB = 0.31 AC-FT.

EXHIBIT A" DEMINAGE REPORT (MENUAL & LOUISIANA)

DEC. 3, 1975 SHT. 40F3

5. DETERMINE HYDROGRAPHS!

DETERMINE TO (TIME BASE):



AREA A (PAVED): V= 0.58 AC-FT OR 25,265 FT 8

Preat = 19.56CFS OR 1174 CUEK FEET PER MIN.

The 25,265(2)(1.67) CONVERT FROM TRIANGULAR HYDROGRAPH
TO PARABOLIC!

Tb = 72 MIN.

Tp= Tb 2.67

Tp= 72 = 27 MIN

AREA B (PANED): V= 0.63 AC-FT DE 27, 643 FT3

APEA B (PANED): V= 0.63 AC-FT DE 27, 643 FT3/MIN

Tb = 27,443(2)(1.67) = 18 MIN.

Tp= 78

TP = 29.24 MIN.

EXIBIT "A"

DRAINAGE REPORT

DEC 3, 1975 SHT. 5 OF B

O G. DETERMINE VOLUME OF STORAGE REQUIRED.

THE FOLLOWING ASSUMPTION AREMADE!

- I. THAT THE HYDROGRAPH IS TRIANGULAR WAEN IN ACTUALITY
 IT IS PARABOLIC
- 2. THAT THE COFFECIENT OF RUNOFF C"IS CONSTANT
- 3. THAT THE DRAWAGE AREAS INVOLVED ARE TOO SMALL TO TUSTIFY AN RESERVOIR ROUTING TECHNIQUES.
- 4. DISCHARGE THROUGH FIRE IS CONSTANT AUTHOUGH IN ACTUALITY DISCHARGE IS VARIABLE WITH INCREMENTS OF HEAD.

DEALUAGE AREA "A":

STORAGE REQUIREMENT: 19.56 10.66 X

X = 39.24 MAI.

5 = 10.66 x 60 x 39.24

5 = 12549 FT3 OR 0,29 Ac-FT.

CONNERT FROM SA. 0.29 = 0.17 Ac-FT TRIAUGULAR

DRAINAGE AREA B": STORAGE REQUIREMENT: 21.04 - 11.47

X . 42.52 MIN

56 = 11.47 x 60 x 4252

= 14631 FT or 0.34 Ac-FT.

CONVERT FROM So = 0.34 = 0.20 Ac-FT.
TRANSULAR

ACTUAL STORAGE PROJOED:

AREA "A" = 0.29 AC-FT (SEE SHT 6). > 0.17 Acf. AREA "B" = 0.36 AC-FT (SEE SHT 6). > 0.20 Acf.

EXHIBIT A"	DEAINA (MENU)	GE REPORT	4)	2Dec 75 La-Menaul. Coen
0	Actual S North Por	torage Vole	ame South P	#3065 SHT, 60= 8
Elev.	area, ft.		area, ft.2	vol. fd. 3
08 (curb)	14200	8270		
07	2340			
06		873	urb) 3097	2848
05			-1800	675
		9148 = 0.2	LIO ac. ft.	3523=0.081ac. +9148
0		Total A	Trea A 237 ac-ft. regul	12671 = 0.231 ac1
Elev	West Pond area, ft.2	Area B	East 1 area, ft.2	Pond vol. 44.3
07			urb) 10368	6957
06 (Curl	0000	6561	3546	1188
05	3222	1208 7769 = 0.1	78 ac- A.	8145 = 0.1870c-4, 7769
0		vs. 0.251 a	cre-ft, required	15914 413.0365k

EXHIBIT 'A"

DRAINAGE REPORT (MENUAL : LOUISIANA) JACOB A. VIGIL. DEC 3, 1975 SHT. 10F.8

M. DESIGN OF DISCHARGE STEUCTURES:

DRAINAGE AREA A": NORTH POND - INVERT EL. = 6.25
TOP OF POND = 8.00
A h = 1.75 FT.

SOUTH POND - INVERT EL. . 4.25

TOP OF POND = 6.00

Ah = 1.75 FT.

AUERAGE HEAD = 1.75: 0.90FT

Q= Cavzgh

C=.605 FROM KING'S HANDBOOK
USING SMITH'S COEFFICIENT.
A= 4'x 24" = 96 m2 OR 0.67 FT2

Q= 0.605 (0.67) 2(322)(9)

Q = 3.09 CFS FER INLET

ZINLETS = 6.18 CFS < 8.90 CFS N.G.

Tey: 4"x 30" OPENIUG A= 0.83 FT3

Q= 0.605 (0.83) \ 2(322)(9)

Q= 3.82 CFS ZINLETS = 7.65 CFS < 8.90 CFS N.6.

TRY: 4" x36" OPENING A: 1.00 FT2

Q = 0.605 (1.0) 2(322)(.9)
Q = 4.61 CFS
2 INLETS = 9.21 CFS > 8.90 CFS O.K.

EXHIBIT'A" PRAINAGE REPORT (MENUACE LOUISIANA)

JACOR A. VICIL DEC. 4, 1975 SHT. B OF B

7. DESIGN OF DISCHARGE STENCTURES COUT'D:

DRAINAGE AREA 'B":

WEST POND - INVERT EL.: 4.25 TOP OF POND : 6.00 Ah- 1.75 FT

EAST POND - INVEST EL. = 05.33 TOP OF POND = 01.00 1.67 FT

WEST: AVERAGE HEAD = 1.75 = 0.90 FT.

Q=Ca Vzgh C=0.605

TRY: 4"x40" OPENING A: 1.11FT2

Q= 0.605 (1.11) /2(322)(0.90)

Q = 5.11 CFS WEST POUD!

EAST: AVERAGE HEAD = 1.67, 0.83

Q = 0.605(1.11) \(\frac{2(32.2\(0.63 \)}{2} \)

Q= 4.91 CFS

TOTAL DISCHARGE = 5.11 + 4.91 = 10.02 CFS 7 9.56 O.K.

B. SUMMARY: THE INLETS FOR THE PONDING AREAS ALONG LOUISIANA BLVD. SHALL BE 4"X 36" IN CROSS SECTIONAL AREA.

THE INLETS FOR THE PONDING AREAS ALONG MEDUAL BUD. SHALL BE 4"x 40" IN CROSS SECTIONAL AREA.

THE BUILDINGS SHALL HAVE CONTROLLED ROSE TOP DEAINS AS ADDED CONTROL FOR RUNOFF.