

February 20, 2020

Rennaker Holden  
Short Elliot Hendrickson Inc.  
934 Main Ave Unit C  
Durango CO 81301

**Re: Project Name**  
2402 Central Ave. SW, Albuquerque  
**Traffic Circulation Layout**  
Engineer's/Architect's Stamp 02-13-20 (J12D032)

Dear Mr. Rennaker,

Based upon the information provided in your submittal received 02-13-2020, the above referenced plan cannot be approved for Building Permit until the following comments are addressed:

1. Please show a vicinity map showing the location of the development in relation to streets and well known landmarks.
2. The ADA accessible spaces must include an access aisle. Van accessible aisles should be 8ft wide; all others should be 5ft wide. Please show the dimension of access space.
3. The ADA accessible parking sign must have the required language per 66-7-352.4C NMSA 1978 **"Violators Are Subject to a Fine and/or Towing."** Please call out detail and location of signs.
4. The ADA access aisles shall have the words **"NO PARKING"** in capital letters, each of which shall be at least one foot high and at least two inches wide, placed at the rear of the parking space so as to be close to where an adjacent vehicle's rear tire would be placed. (66-1-4.1.B NMSA 1978)
5. Motorcycle parking spaces shall be designated by its own conspicuously posted upright sign, either free-standing or wall mounted per the zoning code.
6. All bicycle racks shall be designed according to the following guidelines:
  - a. The rack shall be a minimum 30 inches tall and 18 inches wide.
  - b. The bicycle frame shall be supported horizontally at two or more places. Comb/toaster racks are not allowed.
  - c. The rack shall be designed to support the bicycle in an upright position. See the IDO for additional information.
  - d. The rack allows varying bicycle frame sizes and styles to be attached.
  - e. The user is not required to lift the bicycle onto the bicycle rack.

PO Box 1293

Albuquerque

NM 87103

[www.cabq.gov](http://www.cabq.gov)

- f. Each bicycle parking space is accessible without moving another bicycle.
- 7. Bicycle racks shall be sturdy and anchored to a concrete pad.
- 8. A 1-foot clear zone around the bicycle parking stall shall be provided.
- 9. Bicycle parking spaces shall be at least 6 feet long and 2 feet wide.
- 10. Refuse vehicle maneuvering shall be contained on-site. The refuse vehicle shall not back into the public right of way.; provide a copy of refuse approval.
- 11. Add a note stating "All broken or cracked sidewalk must be replaced with sidewalk and curb & gutter." A build note must be provided referring to the appropriate City Standard drawing.


Once corrections are complete resubmit

- 1. The Traffic Circulation Layout
- 2. A Drainage Transportation Information Sheet (DTIS)
- 3. Send an electronic copy of your submittal to [PLNDRS@cabq.gov](mailto:PLNDRS@cabq.gov).
- 4. No fee

for log in and evaluation by Transportation.

If you have any questions, please contact me at (505) 924-3675.

Sincerely,

A handwritten signature in black ink, appearing to read 'Mojgan Maadandar', with a long horizontal flourish extending to the right.

Mojgan Maadandar, E.I.  
Associate Engineer, Planning Dept.  
Development Review Services

\MM via: email  
C: CO Clerk, File