

CITY OF ALBUQUERQUE

DRAINAGE FACILITIES WITHIN CITY RIGHT-OF-WAY

J-14-841
Gerry J.
Hydrology
2/28/85




VICINITY MAP

SCALE: 1" = 800'

J-14

RECEIVED
MAR 01 1985
HYDROLOGY SECTION



NOTICE TO CONTRACTOR

1. An excavation/construction permit will be required before beginning any work within City right-of-way. An approved copy of these plans must be submitted at the time of application for this permit.
2. All work detailed on these plans to be performed, except as otherwise stated or provided hereon, shall be constructed in accordance with "Public Works Contract No. 84-1".
3. Two working days prior to any excavation, contractor must contact Line Locating Service, 765-1234, for location of existing utilities.
4. Prior to construction, the contractor shall excavate and verify the horizontal and vertical locations of all obstructions. Should a conflict exist, the contractor shall notify the engineer so that the conflict can be resolved with a minimum amount of delay.
5. Backfill compaction shall be according to RESIDENTIAL street use.

Hankins & Co. O'Connor

TOM T. MANN JOB NO. 40521 0-77

APPROVALS	NAME	DATE	TITLE
A.C.E./DESIGN	<i>A. O'Connor</i>	5/18/84	CURB PENETRATION
INSPECTOR	<i>R. Salas</i>	2-26-85	1617 LOS TOMASES DR. N.W.
A.C.E./FIELD	<i>T. Mann</i>	2/28/85	PERMIT NO. 18636
			SHEET 1 OF 2
			MAP NO. J-14

DRAINAGE FACILITIES WITHIN CITY RIGHT-OF-WAY

LOT 3 BLOCK 16, ALBRIGHT MOORE ADDITION

**A.C.S. BENCHMARK 2-H14, A SQUARE, CHISLED ON TOP OF CONCRETE CURB AT THE NNE CURB RETURN, LOCATED AT THE INTERSECTION OF 4TH STREET N.W. AND HAINES AVE. N.W. IN THE NORTHEAST QUADRANT OF THE INTERSECTION
ELEV. 4959.98 FEET (M.S.L.D.)**



1. REMOVE & REPLACE STANDARD CURB & GUTTER TO NEAREST JOINT. CONSTRUCT 4" P.V.C. CURB PENETRATION PER CITY OF ALBUQUERQUE STD. DRAWING K-15. REMOVE REPLACE 12" MIN. WIDTH ASPHALT PAVEMENT ADJACENT TO LIP OF NEW GUTTER.
2. REMOVE & REPLACE EXIST. 4" THICK CONCRETE SIDEWALK TO NEAREST JOINT.



TOM T. MANN JOB NO. 40621

P-77

APPROVALS	NAME	DATE	TITLE:	
A.C.E./DESIGN	<i>H. Olson</i>	<i>5/18/89</i>	CURB PENETRATION 1617 LOS TOMASES DR. N.W.	
INSPECTOR	<i>H. Salas</i>	<i>2-26-85</i>	PERMIT NO. <i>18636</i> SHEET <i>2</i> OF <i>2</i>	MAP NO. J-14
A.C.E./FIELD	<i>W. McNamara</i>	<i>2/28/85</i>		