



FL 61.07

TC 57.65
FL 57.00

59.50

TA 59.56

⊕ TG 59.56

TD 59.56

EXISTING SPOT ELEVATION,
CURB FLOWLINE

EXISTING TOP OF CURB FLOWLINE
EXISTING CURB FLOWLINE ELEVATION

EXISTING SPOT ELEVATION

PROPOSED SPOT ELEVATION:
TOP OF ASPHALT

PROPOSED SPOT ELEVATION:
TOP OF CATCH BASIN GRATE

PROPOSED SPOT ELEVATION:
TOP OF DIRT

EXISTING CONTOUR LINE


LANDSCAPE AREA

DIRECTION OF FLOW

SUBMERSIBLE PUMP SPECIFICATIONS
1/2 HP
2" DISCHARGE
CAST IRON VOLUTE
F & W MODEL SEPP OR EQUAL



H. T. 2.



- 1 AN EXCAVATION/CONSTRUCTION PERMIT SHALL BE REQUIRED BEFORE BEGINNING ANY WORK WITHIN CITY RIGHT-OF-WAY. AN APPROVED COPY OF THIS PLAN MUST BE SUBMITTED AT THE TIME OF APPLICATION FOR THIS PERMIT.
- 2 ALL WORK DETAILED ON THIS PLAN TO BE PERFORMED EXCEPT AS OTHERWISE PROVIDED HEREON SHALL BE CONSTRUCTED IN ACCORDANCE WITH CITY OF ALBUQUERQUE INTERIM STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION, 1985.
- 3 TWO WORKING DAYS PRIOR TO ANY EXCAVATION CONTRACTOR MUST CONTACT LINE LOCATING UTILITIES.
- 4 PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL EXCAVATE AND VERIFY THE HORIZONTAL AND VERTICAL LOCATIONS OF ALL CONSTRUCTIONS. SHOULD A CONFLICT EXIST, THE CONTRACTOR SHALL NOTIFY THE ENGINEER SO THAT THE CONFLICT CAN BE RESOLVED WITH MINIMUM DELAY.
- 5 BACKFILL COMPACTION SHALL BE ACCORDING TO COMMERCIAL STREET USE.
- 6 MAINTENANCE OF THESE FACILITIES SHALL BE THE RESPONSIBILITY OF THE PROPERTY SERVED.

During a 100-year storm, the runoff discharge after the proposed development will not adversely impact, nor be adversely impacted, by the surrounding area.



Oct 7/17

APPROVALS	NAME	DATE	TITLE:
A.C.E.--DESIGN			JAGUAR PRECISION MACHINE BUILDING ADDITION
			ALBERT MONTE ADDITION
INSPECTOR			DRAINLINE THRU CURB
A.C.E.--FIELD			PERMIT NO.
			SHEET 1 OF 1

DRAINAGE AND GRADING PLAN
BUILDING ADDITION
JAGUAR PRECISION MACHINE, INC.

