



SCALE: 3/4"=1'-0'



1. HANDICAPPED ACCESSIBLE AISLE STRIPING PER LOCAL CITY CODE & STANDARDS WITH THE WORD "NO-PARKING" MIN. 12" HIGH 2" STROKE, BLUE COLOR. 4" WIDE WHITE STRIPING @ 1'-6" O.C. AT 45° ANGLE, TYPICAL.
2. ACCESSIBLE PARKING SIGN. EITHER BUILDING MOUNTED, OR POLE MOUNTED, SEE DETAIL B, THIS SHEET.
3. SIDEWALK TO HAVE NO RUNNING SLOPE, AND A 1% CROSS SLOPE AWAY FROM BUILDING
4. 5'-0" x 2'-0" DETECTABLE WARNING SURFACE EXTENDING 24" IN THE DIRECTION OF TRAVEL.
5. 8.3% MAX SLOPE AT ACCESSIBLE RAMP
6. 10% MAX SLOPE SLOPE AT FLARED SIDES
7. INTERNATIONAL SYMBOL OF ACCESSIBILITY, CENTER IN PARKING SPACE, SYMBOL SHALL BE COLOR WHITE ON BLUE BACKGROUND.

