

Project: Kelleher I-40 South
Simulation Run: DEVEX_1 Reservoir: POND 4
Start of Run: 23Mar2014, 00:00 Basin Model: I-40 South_DEVEX1
End of Run: 27Mar2014, 00:05 Meteorologic Model: 100Yr-24Hr NOAA 14
Compute Time: 14Jul2014, 07:32:19 Control Specifications: Control 1
Volume Units: AC-FT

Computed Results

Peak Inflow :	203.529 (CFS)	Date/Time of Peak Inflow :	23Mar2014, 06:20
Peak Outflow :	109.309 (CFS)	Date/Time of Peak Outflow :	23Mar2014, 06:45
Total Inflow :	23.474 (AC-FT)	Peak Storage :	6.373 (AC-FT)
Total Outflow :	23.474 (AC-FT)	Peak Elevation :	5154.43 (FT)