

Project: Kelleher I-40 South
Simulation Run: DEVEX_2 Reservoir: Pond 5
Start of Run: 23Mar2014, 00:00 Basin Model: I-40 SOUTH_DEVEX2
End of Run: 27Mar2014, 00:05 Meteorologic Model: 100Yr-24Hr NOAA 14
Compute Time: 14Jul2014, 07:35:09 Control Specifications: Control 1
Volume Units: AC-FT

Computed Results

Peak Inflow :	98.227 (CFS)	Date/Time of Peak Inflow :	23Mar2014, 06:10
Peak Outflow :	78.427 (CFS)	Date/Time of Peak Outflow :	23Mar2014, 06:20
Total Inflow :	5.431 (AC-FT)	Peak Storage :	1.592 (AC-FT)
Total Outflow :	5.431 (AC-FT)	Peak Elevation :	5164.86 (FT)