

Project: Kelleher I-40 South
Simulation Run: DEVEX_OPTION1 Reservoir: POND 4
Start of Run: 23Mar2014, 00:00 Basin Model: DEVEX-Option1
End of Run: 27Mar2014, 00:05 Meteorologic Model: 100Yr-24Hr NOAA 14
Compute Time: 14Jul2014, 07:43:19 Control Specifications: Control 1

Volume Units: AC-FT

Computed Results

Peak Inflow :	147.128 (CFS)	Date/Time of Peak Inflow :	23Mar2014, 06:20
Peak Outflow :	96.443 (CFS)	Date/Time of Peak Outflow :	23Mar2014, 06:50
Total Inflow :	23.474 (AC-FT)	Peak Storage :	4.934 (AC-FT)
Total Outflow :	23.474 (AC-FT)	Peak Elevation :	5153.33 (FT)