




Summary of Pond Routings												
Pond	Model Description	Design Volume	100 Yr-24 Hr Peak Storage Volume	100 Yr-24 Hr Inflow Volume	100 Yr-24 Hr Outflow Volume	100 Yr-24 Hr Inflow	100 Yr-24 Hr Outflow	Elevation of Emergency Spillway	100 Yr-24 Hr Peak Water Surface Elevation	Freeboard from Emergency Spillway	Available Storage	Comments
		ac-ft	ac-ft	ac-ft	cfs	cfs	cfs	ft	ft	ft	ac-ft	
		a						a		b		
Pond 4	Ex Conditions HEC-HMS	8.51	3.49	12.2	12.2	63.6	19.6	5155.1	5152.1	3.0	5.02	Model uses current watershed conditions using latest NOAA 14 100 Yr-24 Hr rainfall depth of 2.52 in. Pond 5 not modeled
Pond 6	Ex Conditions HEC-HMS	9.01	5.74	10.5	10.5	170.1	50.4	5177.9	5176.57	1.3	3.27	

a- All values reported on this table are taken directly from The Master Drainage Plan for the West Side Transit Facility
100 Yr-24 Hr rainfall depth based on latest NOAA Atlas 14 data
b - Freeboard = Elevation of Emergency Spillway - Peak Water Surface Elevation

EXISTING CONDITIONS - HEC-HMS INPUT PARAMETERS																											
General Subbasin Data				Time of Concentration (Tc) Data																	Log Time Results		Tc and tp Results			Sub-basin	
				Upper Reach (or Entire Reach (L to 400-ft Length))																	Middle Reach (400-to-1600-ft Length)		Log Time	Actual Tc	Final Tc		Composite CN
Sub-basin	Sub-basin Area	Sub-basin Area	Number of Reaches	L Length	Lca Centroid Length	Sc Composite Slope	Kc Composite K	Top Elevation at beginning of water course	Bottom Elevation (L)	Length (L)	S (S)	Kx1	Kc	V1	Elevation at lower end of water course	Length (L)	Slope (S)	Kc	Kc	V1	Log Time (hours)	Log Time (minutes)	hours	minutes	hours	minutes	
a	acres	a	a	ft	ft	ft	ft	ft	ft	ft	ft	ft	ft	ft	ft	ft	ft	ft	ft	ft	(hours)	(minutes)	h	m	h	m	
A-10	19.758	0.039	2	1.642	NA	0.0292	1.4457	5258	5252	400	0.0330	1.0	1.22	520	1.242	0.0338	2.0	1.68	0.5	0.5	0.18	0.28	0.13	69	A-10		
A-11	11.951	0.041	2	1.96	NA	0.0344	1.2501	3221	319	400	0.0388	1.0	1.47	307	586	0.0403	2.0	1.48	0.5	0.5	0.18	0.28	0.13	90	A-20		
A-14	19.628	0.037	2	1.97	NA	0.0272	1.5032	5193	5005	400	0.0330	1.0	1.60	5185	479	0.0367	2.0	1.25	0.5	0.5	0.18	0.28	0.13	91	A-30		
C-2	6.981	0.0103	2	1.53	NA	0.0651	0.4480	5186	5210	400	0.0150	0.7	0.86	5202	153	0.1961	2.0	0.86	0.5	0.5	0.13	0.28	0.13	63	C-20		
C-10	12.376	0.0193	2	1.84	NA	0.0332	0.8363	5216	5210	400	0.0150	0.7	0.86	5188	444	0.0495	2.0	1.45	0.5	0.5	0.16	0.28	0.13	65	C-10A		
C-20.2	26.803	0.0419	2	1.644	NA	0.0233	1.4545	5006	5192	400	0.0330	1.0	1.47	5104	1344	0.0333	2.0	2.77	0.5	0.5	0.17	0.28	0.13	69	C-20A2		
D-11	6.566	0.0099	2	1.607	NA	0.0176	1.0773	5212	5207	400	0.0225	1.0	1.13	5206	60	0.0097	2.0	2.08	0.5	0.5	0.11	0.28	0.13	87	D-11		
D-12	1.298	0.0020	2	1.63	NA	0.0233	1.3885	5206	5198	400	0.0175	1.0	1.14	5196	555	0.0217	2.0	1.23	0.5	0.5	0.15	0.13	0.28	87	D-12		
LV-1	0.721	0.00113	2	1.67	NA	0.0498	1.2222	5217	5198	400	0.0225	1.0	1.29	5188	207	0.0386	2.0	1.39	0.5	0.5	0.06	0.28	0.13	87	LV-1		
LV-2	1.225	0.00191	2	1.607	NA	0.0408	1.4428	5188	5175	400	0.0225	1.0	1.80	5164	567	0.0394	2.0	2.79	0.5	0.5	0.12	0.28	0.13	87	LV-2		
O-1	2.832	0.00416	2	1.870	NA	0.0271	1.4742	5214	5200	400	0.0225	0.7	1.31	5182	1470	0.0222	2.0	2.21	0.20	0.2	0.12	0.27	0.18	66	O-1		
HD-1	7.3624	0.0115	2	1.749	NA	0.0176	1.0359	5275	5273.5	400	0.0360	0.7	0.55	5250	1079	0.0318	2.0	1.03	1.14	0.30	0.30	0.20	89	HD-1			
HD-2	3.999	0.00019	2	1.85	NA	0.0159	1.0431	5250	5247	400	0.0300	0.7	0.59	5234	426	0.0197	2.0	1.2	0.15	0.15	0.13	0.18	89	HD-2			
S-3	2.0761	0.00334	2	1.409	NA	0.0171	0.6651	5234	5228	400	0.0150	0.7	0.86	5227	9	0.1111	2.0	0.15	0.5	0.5	0.13	0.28	0.13	89	S-3		
HA-4	1.9764	0.00309	1	1.841	NA	0.0176	0	5200	5221	341	0.0176	0.7	0.93	5221	1	0.0000	2.0	0	0.5	0.5	0.10	0.28	0.13	83	HA-4		

(a) All measurements were obtained from the Drainage Basin Maps, based on Lidar contour mapping dated 2010.

(b) Obtained from Table F-6 in the DPM, pg. 22-64.

(c) Obtained from Table F-6 in the DPM, pg. 22-64.

(d) $V = 10 \times K_c \times 0.5$ - determined from $V = K \times 10^{0.001 \times K_c}$

(f) See DPM, pages 22-43 through 22-65 for following formulas:

$T_c < 4000$ ft.:

$T_c = [L(1 + 1.2L^2 + 1.35 \times 10^{0.001} \text{ sech}^2 L)] / 4.83$

T_c is between 4000 ft. and 12,000 ft.:

$T_c = [(72.024 \times L) / (7.007 \times K_c^{0.5} S^{0.5})] - [4.0007 \times 10^4 (\text{Ln}(L) / 3) / (552.2 \times V^{0.5} S^{0.5})]$ (ignore upper reach Kc if insignificant for long lengths and assume middle reach Kc for this equation)

$T_c > 12,000$ ft.:

$T_c = (43 / (28 \times K_c^{0.5} L^{0.5} S^{0.5})) + (5280 \times 2 \times 10^{0.001 \times K_c} / S^{0.5})$

(g) Tc or Tc is computed to be less than 0.2 hours, then use 0.2 hours

(h) $T_c = 22.37$ per DPM pg. 22-38

(i) $T_c = (1.35 \times L^{0.75} / (2.50 \times K_c^{0.5} S^{0.5}))$ per DPM pg. 22-65

(j) $T_c = (0.5 \times S^{0.5} / (4.1 \times K_c^{0.5} S^{0.5})) + (2 \times 10^{0.001 \times K_c} / S^{0.5})$ per DPM pg. 22-65

EX POND 4 RATING CURVE		
Elevation	Storage	Discharge
ft.	ac-ft.	cfs
5147	0	0
5148	0.08	0
5149	0.51	3
5150	1.3	5.7
5151	2.29	7.5
5151.9	3.26	8.7
5152	3.37	11.7
5152.5	3.94	50.6
5153	4.52	92.5
5154	5.76	104.3
5155	7.18	115.9
5156	8.51	124.6

DATA FROM MASTER DRAINAGE
PLAN FOR THE WEST SIDE TRANSIT
FACILITY

EXISTING CONDITIONS DRAINAGE BASIN
MAP WITH HEC-HMS INPUT AND OUTPUT
SUMMARY
~~JULY, 2014~~
NOVEMBER, 2014