



LEGEND	
---	BOUNDARY LINE
---	RIGHT OF WAY LINE
---	LIMITS OF DISTURBANCE
---	STORM DRAIN
---	WADDE
EROSION DETAILS	
CE	TEMPORARY STONE CONSTRUCTION EXIT
SF	TEMPORARY SILT FENCE
IP1	INLET SEDIMENT FILTER
SB	TEMPORARY SEDIMENT BASIN
TPS	TEMPORARY PARKING AND STORAGE (LABEL WHEN CONSTRUCTED)
SS	SWPPP INFORMATION SIGN
CE	CONSTRUCTION ENTRANCE
W	WATTLE
RR	RIP-RAP

- MAINTENANCE**
- ALL MEASURES STATED ON THIS EROSION AND SEDIMENT CONTROL PLAN, AND IN THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP), SHALL BE MAINTAINED IN FULLY FUNCTIONAL CONDITION UNTIL NO LONGER REQUIRED FOR A COMPLETED PHASE OF WORK OR FINAL STABILIZATION OF THE SITE. ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSPECTED BY A QUALIFIED PERSON AT LEAST ONCE EVERY FOURTEEN CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A 0.25" RAINFALL EVENT, AND CLEANED AND REPAIRED IN ACCORDANCE WITH THE FOLLOWING:
1. INLET PROTECTION DEVICES AND BARRIERS SHALL BE REPAIRED OR REPLACED IF THEY SHOW SIGNS OF UNDERMINING, OR DETERIORATION.
 2. ALL SEEDED AREAS SHALL BE CHECKED REGULARLY TO SEE THAT A GOOD STAND IS MAINTAINED. AREAS SHOULD BE FERTILIZED, WATERED, AND RESEED AS NEEDED.
 3. SILT FENCES SHALL BE REPAIRED TO THEIR ORIGINAL CONDITIONS IF DAMAGED. SEDIMENT SHALL BE REMOVED FROM THE SILT FENCES WHEN IT REACHES ONE-HALF THE HEIGHT OF THE SILT FENCE.
 4. THE CONSTRUCTION ENTRANCES SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE CONSTRUCTION ENTRANCES AS CONDITIONS DEMAND. ROADWAY SHOULD BE SWEEPED IF SIGNS OF TRACK-OUT ARE PRESENT.
 5. THE TEMPORARY PARKING AND STORAGE AREA SHALL BE KEPT IN GOOD CONDITION (SUITABLE FOR PARKING AND STORAGE). THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE TEMPORARY PARKING AS CONDITIONS DEMAND.
 6. OUTLET STRUCTURES IN THE SEDIMENTATION BASINS SHALL BE MAINTAINED IN OPERATIONAL CONDITIONS AT ALL TIMES. SEDIMENT SHALL BE REMOVED FROM SEDIMENT BASINS OR TRAPS WHEN THE DESIGN CAPACITY HAS BEEN REDUCED BY 50%.

- SEQUENCE OF CONSTRUCTION**
1. Post SWPPP Sign at entrance to site.
 2. Install stabilized entrance/exit.
 3. Sandbag existing pond outlet.
 4. Construct silt fencing at site perimeter.
 5. Clear and grub site.
 6. Begin mass grading.
 7. Define sediment ponds, swales and berms.
 8. Prepare building pad and utility installations.
 9. Designate temporary storage and laydown area on ESC Plan when established.
 10. Protect drainage inlets when constructed.
 11. Re-work sediment pond.
 12. Complete landscaping and final stabilization of entire site.
 13. Contact SWPPP Inspector/Preparer to file Notice of Termination (NOT).

ENGINEER'S SEAL	FEDEX GROUND ALBUQUERQUE, NM SEDIMENTATION AND EROSION CONTROL PLAN	DRAWN BY DY
		DATE 5/18/14
		2013075-SWPPP
RONALD R. BOHANNON P.E. #7868	 TIERRA WEST, LLC 5571 MIDWAY PARK PLACE NE ALBUQUERQUE, NM 87109 (505) 858-3100 www.tierrawestllc.com	SHEET # EC-1 JOB # 2013075