

**NEW MEXICO
DEPARTMENT OF
TRANSPORTATION,
BERNALILLO
COUNTY,
CITY OF
ALBUQUERQUE**

**SUNPORT
BOULEVARD
EXTENSION**

**BROADWAY TO
I-25**

**DRAINAGE
REPORT
AMENDMENT**

Prepared for:

BOHANNAN HUSTON
7500 Jefferson St. NE
Albuquerque, New Mexico 87109

Prepared by:

MOLZEN CORBIN
2701 Miles Road SE
Albuquerque, New Mexico 87106
Phone: (505) 242-5700 Fax: (505) 242-0673

FINAL

December 2020


MOLZEN CORBIN
ENGINEERS | ARCHITECTS | PLANNERS

ENGINEER OF RECORD

Molzen Corbin
2701 Miles Road, S.E.
Albuquerque, New Mexico 87106
(505) 242-5700

The technical material and data contained in this Master Plan was prepared under the supervision and direction of the undersigned, whose seal as a Professional Engineer, licensed to practice in the State of New Mexico, is affixed below.

(SEAL)



 12-17-2020
Jonah S. Ruybalid, P.E.

N.M.P.E. No. 23909

All questions about the meaning or intent of these documents shall be submitted only to the Engineer of Record, stated above, in writing.

TABLE OF CONTENTS

EXECUTIVE SUMMARY	ES-1
OVERVIEW	OV-1
1.0 INTRODUCTION	1-1
2.0 DESIGN CRITERIA AND METHODOLOGY	1-1
3.0 EXISTING SITE CONDITIONS	1-1
4.0 EXISTING DRAINAGE CONDITIONS	4-1
5.0 PROPOSED DRAINAGE CONDITIONS	5-1
5.1 Proposed Drainage Basins	5-4
5.1.1 Basins XL, XD1, XF, and XK	5-4
5.1.2 Basins XF, XE1, XE2, H, and I	5-4
5.1.3 Basin XM1, M1, M2, and N	5-4
5.1.4 Basins C, D, and T	5-5
5.1.5 Basins Q, R, S, and P	5-5
5.1.6 Basins A and B (Woodward Road west of Broadway)	5-5
6.0 CONCLUSION	6-1

LIST OF TABLES

Table 5-1	Proposed Hydrology	5-2
Table 5-2	Analysis Points	5-3

LIST OF FIGURES

Figure OV-1	Preliminary Drainage Report Pond Location	OV-2
Figure 4-1	GIS MAP Viewer – Captured Screenshot of Project Area	4-1
Figure 5-1	Proposed Basin Map	5-6
Figure 5-2	Proposed Drainage Basin Routing	5-7
References		

APPENDICES

PRELIMINARY DRAINAGE REPORT

Appendix A Sunport Boulevard Extension - excerpts from 30% Plans

- Typical Sections - Sheets 2-1 to 2-5
- Roadway Plan and Profile - Sheets 3-2 to 3-12
- Drainage Plan and Profile - Sheets 10-1 to 10-5

Appendix B Natural Resources Conservation Service (NRCS) Websoil Survey

Appendix C AHYMO Input and Output

Appendix D Hydrology Worksheets

- Excerpts from Existing Drainage Report
- Water Quality Pond Calculations
- Proposed Channel in Basin XE1
- Sunport Boulevard and Broadway Boulevard Detention Pond and Private Pond
- Sunport Boulevard 10-year Flow Depth and Spread
- Broadway Boulevard Linear Ditches

DRAINAGE REPORT AMENDMENT

Appendix A Sunport Boulevard Extension - excerpts from 100% Plans

- Drainage Plans - Sheets 10-1 to 10-7
- Drainage Structure Sections - Sheets 10-8 to 10-15
- Drainage Sections and Details - Sheets 10-16 to 10-25

Appendix B No Change

Appendix C AHYMO Data

- AHYMO Input
- AHYMO Summary
- AHYMO Output

APPENDICES (continued)

DRAINAGE REPORT AMENDMENT (continued)

Appendix D Hydrology Worksheets

- Summary of Hydrology and Hydraulic Calculations
- Subbasin AHYMO Inputs
- Subbasin Hydrology Results
- Pond Elevation-Storage-Discharge Tables
- Basin Map (24x36)
- Hydraulic Grade Line Graphical Results
- Drop Inlet Spread Calculations

EXECUTIVE SUMMARY

Bohannon Huston Inc. was contracted to complete the Sunport Boulevard Extension Project from Broadway to I-25. Molzen Corbin has been contracted by Bohannon Huston, Inc. as a sub-consultant to complete various portions of the Project including the drainage analysis and design.

URS Corporation, now known as “AECOM”, prepared a Preliminary Drainage Report (PDR) in February 2011 for the Sunport Boulevard Extension Broadway to I-25 Project. This PDR was prepared for Bernalillo County Public Works Division under Bernalillo County Project No. TS 09-06 and New Mexico Department of Transportation (NMDOT) Control No. A300160. In addition to the PDR, AECOM prepared 30% plans for the roadway Project.

Molzen Corbin was instructed to utilize the 30% level plans and the City approved PDR for the basis of design of the Sunport Boulevard Extension Project. All PDR updates and/or revisions were to be documented in this Drainage Report Amendment.

All of the existing drainage basins were utilized. However, the addition of multiple drop inlets or updated design geometry caused the basins from the PDR to be split into multiple drainage basins. For example, Basin G became Basin G and Basin G1. The Arid Lands Hydrology Model (AHYMO) was updated and executed to produce updated hydrologic results. Autodesk Storm and Sanitary Analysis (SSA) and Hydraflow Extension were utilized to model the storm sewer system and perform the drop inlet analysis. The plans and structure sections have been revised to include the updated design geometry and structures, discharge rates, and hydraulic grade lines.

The PDR suggests the use of linear ditches adjacent to the roadway along Broadway Boulevard. As part of the updated design, the typical section was revised to include curb and gutter. These storm water flows were then routed to the proposed detention pond facility southeast of the Broadway/Sunport intersection.

OVERVIEW

This update is based on the PDR prepared by AECOM dated February 2011 and the Preliminary Design 30% Review Plans prepared by AECOM dated January 2011. This document identifies the assumptions, criteria and constraints proposed for the preparation of the update and a summary of the proposed changes from the City approved PDR.


The design criteria and methodology listed in the PDR are used for evaluating and developing the Amendment including:

- City of Albuquerque (COA) Development Process Manual (DPM) as the primary source of drainage criteria.
- AHYMO for hydrology. The PDR AHYMO results were utilized for the Update. This model includes a sediment bulking factor of 1.10.
- The 100-year 24-hour event as the design storm.
- NMDOT curb and gutter, median curb and gutter, and inlets east of Broadway Boulevard with COA curb and gutter, median curb and gutter, and inlets on Broadway and Woodward.
- Conformance with the South Broadway Sector Drainage Management Plan.

Revisions and exceptions to the design criteria and methodology used in the PDR include the following:

- Grade and Alignment - Grade, cross section, lane geometry, and alignment changes during the 30% update, 60% review, and 90% review will be incorporated into the final drainage computations. Significant changes in drainage design for Sunport Boulevard are not anticipated.

- Sunport and Broadway Boulevards Intersection Drainage. Major revisions to the drainage collection and the detention ponds are proposed:
 - Broadway Detention Pond Relocation - At the request of the County, the proposed pond at the southeast corner of Broadway Boulevard and Sunport Boulevard has been relocated further east. This will result in a deeper pond and larger conveyance to convey the runoff to the pond. The relocated pond detains approximately 3.15 acre-feet and will drain at a peak rate of 1.6 cfs to the existing SD manhole in the intersection of Broadway/Woodward and then to the San Jose Drain (SJD). The pond is approximately 8.3 feet deep at the west end and approximately 15 feet deep on the east end. Side slopes are 2:1 and lined with rip-rap from an elevation of 4,941.50 feet down to the bottom elevation of 4,933.20 feet. Stormwater quality treatment is provided by allocating infiltration/evapotranspiration retention volume in the pond.



**FIGURE OV-1
PRELIMINARY DRAINAGE REPORT POND LOCATION**

- o Broadway Boulevard Drainage System - The drainage philosophy implemented in the PDR was to pond portions of the runoff in “V” ditches along the west side of Broadway Boulevard for infiltration and evaporation. There was not adequate volume on the west side to contain the 100-year runoff. Along the east side of Broadway Boulevard, the runoff was conveyed via a combination of “V” ditches and storm drain into the detention pond at the southeast corner of the intersection. The roadway runoff west of the South Diversion Channel (SDC) was conveyed to the pond in a storm drain system.

The proposed system collects runoff from Broadway Boulevard in the reconstruction area, as well as runoff from Sunport Boulevard west of the SDC. Stormwater is conveyed through curb and gutter with drop inlets to the detention pond southeast of the Broadway/Sunport Boulevard intersection.

- o A V-ditch pond is located at one location immediately southeast of the Broadway/Sunport intersection adjacent to Broadway Boulevard. This pond detains offsite stormwater from the adjacent property from discharging onto Broadway Boulevard. The stormwater is instead conveyed through the pond and storm drain line to the storm drain system.
- o The runoff collected in Broadway Boulevard drains via a 42-inch pipe to the detention pond. The runoff in excess of the water quality volume is discharged through a restricted outlet junction box to the existing manhole in the intersection of Broadway and Woodward and then to the SJD. The storm drain system is constrained by the roadway elevations and the existing manhole invert elevation in the intersection. The resulting pipe slope is 0.1%. This is not adequate to provide self-cleaning velocities and median inlets that do not have a curb opening are used to minimize debris in the system. Due to the shallow system, ductile iron pipe is proposed in select locations. Drop inlets located in sag areas are designed for double the design storm event to account for 50% clogging.

- Stormwater Quality Volume - The Preliminary Design incorporated a stormwater quality volume of runoff from a 0.25 inch storm at the entrance to the SDC. Stormwater quality was not explicitly addressed for the runoff west of the SDC.
- SDC Water Quality Pond (WQP) - This revision impacts the water quality pond at the discharge into the Albuquerque Metropolitan Arroyo Flood Control (AMAFCA) SDC. The detention pond includes a 2 foot +/- thick gravel and rock filter with an underdrain system to provide treatment. The undeveloped areas upstream of the WQP will either discharge directly to the SDC as they do now, or will discharge into a proposed storm drain line which routes flow around the WQP to discharge onto the rundown downstream of the WQP, which discharges into the SDC.
 - The water quality pond will be modified to capture the runoff only from the roadway east of the SDC, but will allow the runoff from the undeveloped area to discharge directly to the SDC. The water quality volume will be modified to satisfy the 90th percentile storm criteria. The gravel-rock filter with subdrain treatment method is proposed. The pond incorporates reverse slope outfall pipes sized for the 10-year storm and a 100-year spillway to discharge flow into the SDC via the existing baffle chute rundown.
- Broadway/Sunport Pond Water Quality - The Broadway Pond collects runoff from Sunport Boulevard west of the SDC, the Broadway Boulevard corridor within the Project limits, and Woodward Road (east). Most of this runoff is from paved areas. The water quality volume is approximately 0.69 acre-feet. The proposed treatment method is to dedicate the first level in the pond, approximately 1 foot, as a retention infiltration/evapotranspiration zone. This zone is stored below the invert of the discharge pipe and does not discharge to the SJD.
 - The COA DPM requires that appropriate techniques such as infiltration, extended filtration, water harvesting, evapotranspiration and other appropriate techniques be utilized for the StormWater Quality Volume. For drainage areas smaller than 40 acres, the runoff volume can be determined by multiplying the drainage area by a value of 1,037 cubic feet/ac for sites with 80% impervious are or 1,670 cubic feet/ac for sites with 100% impervious area. These values are consistent with a runoff depth of

0.36 and 0.46 inches respectively. Stormwater control measures should manage first flush runoff and runoff from impervious surfaces.

- Woodward Road (west) Water Quality - The small drainage area on Woodward Road west of Broadway Boulevard is connected directly to the existing 30-inch pipe draining to the SJD as proposed in the PDR. A practical method to treat this runoff was not identified; therefore, the water quality volume is not treated in this portion of the system. Basins A and B contribute a runoff volume of 0.232 ac-ft. Basin XV for the existing Rio Grande Service Center located northwest of the Broadway/Woodward intersection has an existing connection to the existing 30-inch storm drain line which will be re-connected to the new manhole during construction.
- XE Channel - Edmunds Street to SDC. The channel from the 36-inch culvert on Edmunds Street to the SDC in the PDR is revised to account for different basin delineation assumptions impacting the flow rate.

There is a 36-inch culvert under I-25 draining from east to west that flows to the Edmunds Street 36-inch culvert. The PDR assumed this discharge, as well as the local area (Basin XD1) drains northward to Woodward Avenue. Based on field observation, the I-25 culvert and the local area both drain to the Edmunds Street culvert in a 3-foot to 6-foot deep incised ditch. The I-25 36-inch culvert discharge is defined in the Molzen Corbin 1996 Sunport Boulevard Final Drainage Report as 33.7 cfs. Also, the portion of the local drainage area between I-25 and Edmunds Street appears to split with approximately 2/3 flowing to the Edmunds Street 36-inch culvert. Based on this analysis, the total flow at the Edmunds Street 36-inch culvert is estimated to be 46.3 cfs.

The XE Channel conveys this flow, as well as the drainage from local basin XE1, to the existing rundown into the SDC. Currently, this natural arroyo flow meanders under the Sunport Boulevard footprint. As part of the Project, the arroyo is channelized to protect the roadway wall and the stormwater quality pond. The PDR identified the channel design flow as 14 cfs. Based on the revised hydrology, a flow rate of 50.4 cfs is required.

Note that the Sunport Boulevard runoff is conveyed through the stormwater quality pond to the SDC rundown and does not enter the XE Channel.

It was determined that the best way to manage this stormwater discharge is through a closed 36-inch storm drain line. The storm drain line will be routed around the north side of the stormwater quality pond and discharge onto the apron of the rundown into the SDC.

- Utility Conflicts - Based on available data and preliminary analysis, storm drain conflicts with existing gravity systems can be avoided. However, conflicts with pressurized systems such as water and gas lines may require adjustment.

1.0 INTRODUCTION

Drainage plans for the 90% design 10 sheets are included in Appendix A instead of the 30% plans prepared by AECOM.

2.0 DESIGN CRITERIA AND METHODOLOGY

Hydraflow Extension was used to perform the drop inlet calculations. SSA was used to analyze the storm sewer system to determine Hydraulic Grade Line elevations. Both the Hydraflow Extension and SSA calculations are further described within Appendix D

3.0 EXISTING SITE CONDITIONS

No updates.

4.0 EXISTING DRAINAGE CONDITIONS

The following information provides a summary of the drainage plans for existing developments adjacent to the Project limits based on the drainage plans available online from the COA Geographic Information System (GIS) Map Viewer. Figure 4-1 shows a screen shot of the GIS Map Viewer of the project area.




FIGURE 4-1
GIS MAP VIEWER – CAPTURED SCREENSHOT OF PROJECT AREA

Southwest of Broadway/Woodward Intersection:

- The parcel immediately southwest of the Broadway/Woodward intersection and as part of M14D009 does not contribute to the Project. Existing runoff is retained in a retention pond immediately south of Woodward or drains to the SJD.

- The three parcels as part of the Ben E. Keith Foods Project and as part of M14D010 on the southwest side of the Broadway/Woodward intersection were designed to retain their runoff with a retention pond just west of Broadway Boulevard.
- Northwest of Broadway/Woodward Intersection.
- The site as part of the Cauwels Warehouse Project and associated with M14D030 was allowed discharge into City drainage facilities. The Site, as noted by the plans, is designed to drain into the SJD. The Site is divided into two basins. The west basin drains into the SJD while the east basin drains through a water quality inlet before connecting to an existing inlet at the intersection of Broadway and Woodward. The east basin has a 100-year volume of 13,380 cubic feet and a 100-year peak discharge of 12.6 cfs which discharges through a 10-inch DI which connects to an existing manhole at Broadway/Woodward and then conveys the stormwater through a 30-inch RCP line to the SJD.

The existing 10-inch storm drain line will be re-connected as part of this Project to the existing 30-inch storm drain line which drains to the SJD.

Northwest of Broadway/Wesmeco Drive:

- The parcel immediately northwest of the Broadway/Wesmeco Drive intersection is part of the Cesar Sierra Metal Building Project and associated with M14D027, did not have plans available for review.
- The parcel located northwest of Broadway/Wesmeco Drive as part of the Private Garage for A&E Auto Sales and associated with M14D0001A. The Drainage Plan shows a retention pond on the northwest side of the property.

Northeast of Broadway/Wesmeco Drive:

- The parcel northeast of the Broadway/Wesmeco intersection known as the Ahern Rentals property associated with M14D0003, has a drainage plan on file. The drainage plan states that the site drains from east to west. There is a 30-inch storm drain that terminates

at the intersection of Broadway and Wesmeco. The storm drain runs west within Wesmeco and drains into the SJD. Half of the property (Basins 10 and 11) drain into the existing storm drain in Wesmeco. Part of the property (Basins 21 and offsite) drains to a pond along the south side of the property. Basin 20 (3.3 cfs and 5,069 cubic feet as part of the 100-year 6-hour event) drains into an existing drop inlet that connects to the existing storm drain system within Broadway/Wesmeco. The Drainage Plan states that the site is allowed a discharge rate of 2 cfs/acre which is equivalent to 9.88 cfs from the site.

Northeast of Broadway/Woodward Intersection:

- The parcel associated with Aguamatic Landscaping and M14D033 is located immediately northeast of the existing Broadway/Woodward intersection. The Drainage Plan shows two detention ponds on the southside of the property with volumes of 814 and 1,389 cubic feet respectively. These facilities discharge through a culvert pipe which connects to a drop inlet on the northeast side of the Woodward/Broadway intersection. That drop inlet connects to the Woodward 30-inch storm drain.

The existing storm drain line will be connected to the storm drain installed as part of this Project which drains to the proposed detention pond.

5.0 PROPOSED DRAINAGE CONDITIONS

The Drainage Basins have been updated based on the updated design. Where additional Drainage Basins were added, the Drainage Basin at that location from the PDR was split into multiple basins. For example, Basin G from the PDR was split into two Basins which are named Basin G and Basin G1 in this Drainage Report Amendment. Existing sites with previously approved discharges to the Woodward storm drain were incorporated into the drainage analysis.

The AHYMO model was revised to include the updated Drainage Basin areas and routing. The AHYMO model was updated to utilize National Oceanic and Atmospheric Administration (NOAA) Atlas 14 precipitation values rather than the NOAA Atlas 2 precipitation values. Table 5-1 has been revised to show the updated results and have been arranged in alphabetical order, but with existing basins shown first. Table 5-2 has been revised to show analysis points as a result of the updated hydrology. The analysis points for the updated hydrology were considered to be specific junctions within the drainage system such as inlets and outlets of the ponds. Figure 5-1 has been revised to show the revised Drainage Basins.

It should be noted that any areas included in this drainage analysis that are not developed, should be restricted to pre-development discharges in the future. The current runoff volumes and peak discharges will need to be maintained.

**TABLE 5-1
PROPOSED HYDROLOGY**

Basin (hydrograph identification)	Area (sq mi)	Peak Discharge (cfs)	Runoff Volume (ac-ft)
A	0.00089	2.68	0.12
B	0.00082	2.49	0.112
C	0.00038	1.15	0.052
D	0.00032	0.97	0.044
G	0.00107	3.25	0.147
G1	0.00124	3.76	0.17
H	0.00066	2.02	0.091
H1	0.00025	0.78	0.035
H2	0.00054	1.65	0.074
H3	0.00028	0.87	0.039
H4	0.00122	3.71	0.168
I	0.00064	1.95	0.088
I1	0.00062	1.89	0.085
I2	0.00025	0.76	0.034
I3	0.00131	3.98	0.18
I4	0.00059	1.8	0.081
M1	0.00186	4.74	0.184
M2	0.00061	1.85	0.083
M3	0.00033	1.02	0.046
M4	0.00035	1.07	0.048
N	0.00368	7.23	0.207
P	0.00047	1.43	0.064
P1	0.00097	2.86	0.125
Q	0.00079	2.37	0.104
Q1	0.00019	0.58	0.025
R	0.00058	1.73	0.076
R1	0.0003	0.91	0.039
S	0.00044	1.36	0.061
S1	0.00058	1.72	0.075
T	0.00126	3.83	0.173
XC	0.0044	10.16	0.336
XD1	0.00156	3.19	0.103
XD2	0.00165	3.4	0.114
XD3	0.00174	3.51	0.109
XD4	0.00021	0.52	0.018
XD5	0.00233	4.36	0.125
XE1	0.00005	0.12	0.004
XE2	0.00003	0.07	0.002
XE3	0.00369	4.73	0.143
XF	0.00379	6.5	0.209
XJ	0.00755	12.48	0.364
XJ1	0.01045	18.34	0.528
XM1	0.00057	1.47	0.055
XM2	0.00105	2.46	0.082
XV	0.00305	8.99	0.396

**TABLE 5-2
ANALYSIS POINTS**

Analysis Point #	Basin	Contributing Basins	Area (sq mi)	100-Year 24-Hour Peak Discharge (cfs)	100-Year 24-Hour Runoff Volume (ac-ft)
1	SDC (Discharge to the SDC from overland flow).	XE3, XD5	0.00756	9.09	0.268
2	SDC (Discharge to SDC from Storm Drain line).	*culvert, XD3, XD4, XE2, XF	0.00577	*10.6	*0.336
3	SDC (Discharge from WQP).	I4, I3, H3, H3	0.00345	10.48	0.471
4	Water Quality Pond (Discharge to the WQP from storm drain).	I4, I3, H3, H4	0.00345	7.74	0.467
5	Water Quality Pond (Total Discharge to the pond).	I4, I3, H3, H4, XE2, XF, XE1	0.0114	17.91	0.5649
6	Water Quality Pond (Discharge out of the pond).	I4, I3, H3, H4, XE2, XF, XE2	0.0114	16.729	0.5649
7	Detention Pond (Total Discharge to detention pond).	XJ1, XJ, G1, G, D, C, Q, R, Q1, R1, T, S1, P1, S, P, XC, M1, XM1, M2, N, XM2, XD2, M3, XD1	0.0456	102.37	3.712
8	Detention Pond (Discharge to the detention pond from the storm drain on the east side).	M1, XM1, M2, N, XM2, XD2, M3, XD1	0.01463	35.47	1.33
9	Detention Pond (Discharge to the detention pond from the storm drain on the west side).	G1, G, D, C, Q, R, Q1, R1, T, S1, P1, S, P	0.013	25.92	1.1553
10	Detention Pond (Discharge out of the detention pond).	XJ1, XJ, G1, G, D, C, Q, R, Q1, R1, T, S1, P1, S, P, XC, M1, XM1, M2, N, XM2, XD2, M3, XD1	0.04563	1.45	3.068
11	Discharge to San Jose Drain.	A, B, XV, DetPond Out	0.05039	16.14	3.695
*values do not include the 52 cfs for the culvert discharging into basin XD3 captured by storm drain line, routed to SDC					

5.1 Proposed Drainage Basins

5.1.1 Basins XL, XD1, XF, and XK

Basin XL was not included in this analysis as it does not discharge into the Project drainage system. Basin XK was absorbed by Basin XF with the updated basin map.

Basin XF flows overland to Basin XE2 where it makes its way into the storm drain line around the WQP.

5.1.2 Basins XF, XE1, XE2, H, and I

Basin XF was increased in area to the south to eliminate Basin XK as it did not appear that Basin XK was needed. Basin XE1 area was revised, but includes the WQP. As part of construction of the WQP, a berm will be constructed on the north side of the pond. Basin XE3 remains very similar to what was shown in the PDR for Basin XE2.

Basins H and I were divided in to multiple basins including basins H, H1, H2, H3, H4 and I, I1, I2, I3, I4. The division was a result of updated design geometry that includes a bike lane separated from travel lanes by a wall, and the placement of drop inlets.

5.1.3 Basin XM1, M1, M2, and N

The area for Basin XM1 was divided into Basins XM1 and XM2, but still includes offsite flows from the structure and property adjacent to Woodward Road. Basins M3 and M4 were added due to updated design geometry. Basin N remains virtually identical to the PDR.

5.1.4 Basins C, D, and T

Basins C and D areas are smaller due to the increase in size of Basin G and G1 along with updated design geometry. Basin T varies in size slightly due to the relocation of the detention pond to the east.


5.1.5 Basins Q, R, S, and P

Basins Q, R, S, and P have been divided into two basins each based on the updated design geometry and the location of drop inlets.

5.1.6 Basins A and B (Woodward Road west of Broadway)

Basins A and B remain virtually identical.

LAST MODIFIED: Dec 23, 2019 - 9:45am BY USER: jrbahold
DWG. LOCATION: E:\PROJECTS\111616-11\BASIN SERV TO I-25\DWG\Misc\station\Proposed Drainage
DWG. NAME: 111616-11_BasinMap.dwg



MOLZENCORBIN


0 50' 100' 200' 400'
1"=200'



SEE APPENDIX D FOR 24"x36" VERSION OF THIS BASIN MAP

Sunport Boulevard Extension Broadway to I-25

Figure 5-1 Proposed Drainage Basin Map
Drainage Report Amendment



6.0 CONCLUSION

- The SJD is extremely restricted in the rate of flow it can accept. The PDR suggests the use of a standpipe outlet. The updated design files limit the flow through a slightly different outlet structure.
- The PDR recommends stormwater retention within the Right-of-Way (ROW) within linear ditches. The updated design files provide an urban typical section for Broadway Boulevard with curb and gutter, and drop inlets. The drop inlets route the stormwater runoff to the detention pond southeast of the Broadway/Sunport intersection. There is one location where a linear pond is utilized within Basin T to prevent offsite stormwater from discharging onto Broadway Boulevard.
- The PDR suggests that the existing pond and driveway on the northeast quadrant of the Broadway/Sunport intersection must be relocated. The existing pond will not be relocated and will be allowed to drain into the storm drain system.
- The PDR suggests that a water quality pond be planned to collect flow from the proposed roadway basins and the existing adjacent arroyo and outflow into the SDC. A culvert system was designed to intercept stormwater flows from the existing arroyo and direct those flows around the WQP and into the diversion channel through the energy dissipation structure. The WQP receives roadway runoff prior to discharge over a weir into the SDC energy dissipation structure.

REFERENCES

AECOM (Formerly known as URS Corporation). *Sunport Boulevard Extension Broadway to I-25*
PDR. CNA300160, TS09-06, February 2011

APPENDIX A
100% DRAINAGE PLANS

DRAINAGE KEY NOTES

- 1 GRADE AROUND EXISTING CATCH BASIN. MAINTAIN EXISTING 18" INLET & OUTLET.
- 1A MAINTAIN CONNECTIONS TO NEW P-20. (SEE NOTE TO CONTRACTOR, THIS SHEET.) NOTE: RECENT FIELD OBSERVATIONS OBSERVED THAT THE DIAMETER OF THESE STORM DRAIN PIPES WERE 18" IN DIAMETER, NOT THE 15" DIAMETER THAT WAS PRESENTED WITH THE ORIGINAL PROJECT SURVEY AND SUBSEQUENT "SUE" INVESTIGATIONS. CONTRACTOR TO VERIFY IN FIELD PRIOR TO INSTALLATION OF P-20.
- 2 INLET OF EXISTING 18" CONCRETE PIPE WAS NOT LOCATED IN FIELD AS PART OF SURVEY DATA COLLECTION, AND THEREFORE ASSUMED TO BE ABANDONED. CONTRACTOR TO CONFIRM IF THE EXISTING INLET IS ACTIVE, AND COORDINATE WITH PROJECT MANAGER IF ACTIVE. MAINTAIN CONNECTION IF ACTIVE.


IF NOT ACTIVE, THE CONTRACTOR SHALL CUT THE DRAINAGE LINE OUTSIDE THE LIMIT OF THE NEW P-20 STRUCTURE, AND PLUG WITH STRUCTURAL CONCRETE CLASS A. THIS WORK IS INCIDENTAL TO ITEM 601000.

DRAINAGE STRUCTURE BUILD NOTES

- P-1 COA SDI DOUBLE TYPE D STA 4998+23.60, LT 25.47' (LOG) LIP OF GUTTER 4939.29 FLOWLINE ELEV 4939.27 = GRATE TOC 4939.83 18" OUT 4935.71
- P-2 COA DRAIN MANHOLE TYPE C - 6' DIA. STA 998+20.67, RT 29.39' RIM/COVER ELEV 4938.95 18" IN (N) 4935.30 18" IN (S) 4935.04 36" EXIST IN (E) OUT (W) 4933.5+/-
- P-3 COA SDI DOUBLE TYPE D STA 998+20.67, RT 43.95' (LOG) LIP OF GUTTER 4938.66 FLOWLINE ELEV 4938.64 = GRATE TOC 4939.20 18" OUT 4935.10
- P-25A SEE SHEET 10-6
- P-4 NMDOT SDI TYPE II - B STA 1001+55.00, LT 35.00' (LOG) LIP OF GUTTER 4940.42 FLOWLINE ELEV 4940.30 GRATE 4940.07 TOC 4940.96 24" OUT 4936.30
- P-5 NMDOT SDI TYPE II - B STA 1001+55.00, RT 41.0' (LOG) LIP OF GUTTER 4940.30 FLOWLINE ELEV 4940.18 GRATE 4939.95 TOC 4940.84 24" IN (N) 4935.93 24" OUT (S) 4935.88
- P-14 COA DRAIN MANHOLE TYPE C - 8' DIA. STA 4999+40.00, RT 32.62' RIM/COVER ELEV 4940.15 36" IN (S) 4934.91 36" IN (N) 4934.93 42" OUT (E) 4934.86
- P-15 COA DRAIN MANHOLE TYPE C - 8' DIA. STA 1001+55.0, RT 60.63' RIM/COVER ELEV 4941.20 42" IN (W) 4934.74 24" IN (N) 4935.81 42" OUT (E) 4934.69
- P-19 COA DRAIN MANHOLE TYPE C - 4' DIA. STA 1000+96.16, RT 47.51' RIM/COVER ELEV 4941.18 18" IN (E) 4933.95 18" OUT (W) 4933.90
- P-19A COA DRAIN MANHOLE TYPE C - 8' DIA. STA 1000+34.13, RT 36.74' RIM/COVER ELEV 4940.29 18" IN (E) 4933.84 18" OUT (W) 4933.83 (SEE DETAILS, SHEET 10-22)
- P-19B STA 1000+56.3, LT 0.5' REMOVE AND DISPOSE OF EXISTING CATCH BASIN. BUILD COA DRAIN MANHOLE TYPE C - 4' DIA. RIM/COVER ELEV 4940.60 12" IN (NE) 4936.8+/- 12" OUT (SW) 4936.8+/- CONTRACTOR TO CONFIRM INLET/OUTLET PIPE IN FIELD. (EXISTING 6" CI WATER LINE IS NOT TO BE DISTURBED)
- P-20 REMOVE AND DISPOSE OF EXIST DMH BUILD COA DRAIN MANHOLE TYPE C - 6' DIA. STA 1000+04.86, RT 31.67' RIM/COVER ELEV 4940.17 18" IN (E) 4933.8+/- 30" (EXIST) OUT (W) 4933.8+/- SEE NOTE TO CONTRACTOR, THIS SHEET, FOR EXISTING INLET ELEVATIONS.

NOTE: (TYPICAL ALL 10 SHEETS)

1. "LOG" = "LIP OF GUTTER"
2. ALL DRAINAGE INLETS WITHIN "UNIT 2" COA MAINTENANCE TO HAVE GRATE(S) ONLY, WITH NO CURB OPENINGS. ALL DRAINAGE ITEMS (STORM DRAIN CULVERTS, INLETS AND MANHOLES, ETC.,) TO BE UNDER CITY OF ALBUQUERQUE SPECIFICATIONS, PAY ITEMS, AND STANDARD DRAWINGS, UNLESS OTHERWISE NOTED. SEE COA STD DWG 2220-MODIFIED (SHEET 10-23).
3. ALL GRATE ELEVATIONS TO BE CONFIRMED IN FIELD AND APPROVED BY THE PROJECT MANAGER PRIOR TO INSTALLATION.
4. ALL STORM DRAIN MANHOLE COVERS WITHIN UNIT 2 SHALL BE NEENAH FOUNDRY MODEL R-6460-B MANHOLE COVER (PRESSURE TYPE), OR ENGINEER APPROVED EQUIVALENT.
5. SEE SHEET 10-22 FOR COA TYPE "D" INLET CURB AND GUTTER TRANSITIONS.
6. "TOC" = TOP OF CURB ELEVATION.
7. ALL DRAIN INLET GRATES WITHIN UNIT 1 PAVED ROADWAY AND ADJACENT TO BICYCLE LANES SHALL BE "URBAN" TYPE AND SUITABLE FOR BICYCLE TRAFFIC. NMDOT STD DWG 623-01-1/1.
8. IN AREAS WHERE COVER BETWEEN FINISHED PAVEMENT GRADE AND TOP OF STORM DRAIN CULVERT PIPE IS 1'-6" OR LESS, CONTRACTOR SHALL REFER TO THE MINIMUM COVER STORM DRAIN DETAIL, SHEET 10-18. THIS WORK IS INCIDENTAL TO THE APPLICABLE STORM DRAIN PIPE ITEM NUMBER.



CN: A300161 STA 126+75.00 =
CN: A300160 STA 995+28.46
BEGIN PROJECT

STORM DRAIN CULVERT BUILD NOTES

- SD-1 BUILD 52' X 18" RCP CL IV BETWEEN P-1 & P-2
- SD-2 BUILD 12' X 18" RCP CL IV BETWEEN P-2 & P-3
- SD-3A BUILD 23' X 18" DUCTILE IRON PIPE BETWEEN P-20 & P-19A
- SD-3 BUILD 58.5' X 18" DUCTILE IRON PIPE BETWEEN P-19A & P-19 (NMDOT)
- SD-4 BUILD 235' X 18" DUCTILE IRON PIPE BETWEEN P-19 & P-18 (NMDOT)
- SD-5 BUILD 116' X 42" RCP CL IV BETWEEN P-14 & P-15
- SD-6 BUILD 75' X 24" STORM DRAIN CULV PIPE, BETWEEN P-4 & P-5
- SD-7 BUILD 13' X 24" STORM DRAIN CULV PIPE BETWEEN P-5 & P-15
- SD-8 BUILD 131' X 42" RCP CL IV BETWEEN P-15 & P-16
- SD-9 SEE SHEET 10-6
- SD-9A SEE SHEET 10-6
- SD-32 SEE SHEET 10-6

NOTE TO CONTRACTOR:
EXISTING DMH (AT P-20) EXISTING CULVERT PIPE DIAMETER AND INVERT INFORMATION FROM FEBRUARY 2019 SUPPLEMENTAL SURVEY (BHI):

- 36" CONCRETE (W) INV = 3933.47
18" CONCRETE (NW) INV = 3934.27
12" CONCRETE (NE) INV = 3935.37
18" CONCRETE (SE) INV = 3935.37

CONTRACTOR TO CONFIRM IN FIELD AND COORDINATE WITH PROJECT MANAGER AND ENGINEER.

DRAINAGE PROFILE SHEET REFERENCES

SYSTEM	SHEET
P-1 TO P-3	10-8
P-4 TO P-15	10-8
P-9 TO P-17	10-10
P-17A TO P-20	10-11
P-22 TO P-14	10-11
P-24 TO P-26	10-9

TYPICAL ALL SHEETS

TH # = SUE LEVEL A TEST HOLE (SEE 11 SHEETS FOR ADDITIONAL INFORMATION)

SEE SHEETS 10-5 & 10-6 FOR BROADWAY BLVD DRAINAGE (NORTH & SOUTH OF INTERSECTION)




DESIGN REVIEW COMMITTEE

CITY ENGINEER APPROVAL

NO.	DESCRIPTION	DATE	BY
4			
3			
2			
1			

BERNALILLO COUNTY
PUBLIC WORKS DIVISION
TECHNICAL SERVICES DEPARTMENT

SUNPORT BOULEVARD EXTENSION
DRAINAGE PLAN
WOODWARD RD. / SUNPORT BLVD.



DRAINAGE KEY NOTES

- 3

BUILD OUTLET PAD WITH STRUCTURAL CONCRETE CLASS A. SEE SHEETS 10-20 & 10-21 FOR ADDITIONAL INFORMATION)
- 4

BUILD DETENTION POND WITH HDPE LINER. (SEE SHEETS 10-20 TO 10-22B, FOR ADDITIONAL INFORMATION)
- 5

BUILD 16' WIDE MAINTENANCE ACCESS RD (SEE SHEET 10-20 FOR ADDITIONAL INFORMATION)
- 6

BUILD 10' W X 2' THICK RIPRAP PAD. ADJUST LIMITS IN FIELD, AS NEEDED.
(SEE SHEETS 10-10, 10-13 & 10-20 FOR ADDITIONAL INFORMATION)
- 6A

BUILD 5' W X 1' THICK RIPRAP CLASS A FROM P-45C TO P-45. (SEE PROFILE, SHEET 10-15 FOR ADDITIONAL INFORMATION)
- 6B

BUILD 1' THICK RIPRAP CL A LINED 2:1 SLOPE TREATMENT. (SEE DETAIL, SHEET 10-20 FOR ADDITIONAL INFORMATION.)
- 6C

BUILD CONCRETE MAINTENANCE ACCESS STAIRS WITH PLATFORMS AND PEDESTRIAN RAILINGS. (SEE SHEETS 10-20 & 10-22 FOR ADDITIONAL INFORMATION)
- 8

BUILD 5' W X 1' THICK RIPRAP CL A AROUND PERIMETER OF INLET.
GEOTEXTILE INCIDENTAL TO RIPRAP.

DRAINAGE STRUCTURE BUILD NOTES

P-6 NMDOT SDI TYPE II - B STA 1002+93.64, LT 35.0' (LOG) LIP OF GUTTER 4942.20 FLOWLINE ELEV 4942.21 GRATE 4941.85 TOC 4942.74 24" OUT (S) 4937.85 P-7 NMDOT SDI TYPE II - B 1002+93.64, RT 41.00' (LOG) LIP OF GUTTER 4942.08 FLOWLINE ELEV 4941.96 GRATE 4941.73 TOC 4942.62 24" IN (N) 4937.47 24" OUT (S) 4937.42 P-17B STA 1003+02.2, RT 160.1' 42" END SECTION (NMDOT) INV OUT 4934.32	P-16 COA DRAIN MANHOLE TYPE C - 8' DIA. STA 1002+93.64 , RT 60.63' RIM/COVER ELEV 4942.29 42" IN (W) 4934.56 24" IN (N) 4937.36 42" OUT (E) 4934.51 P-16A - 8' DIA SPECIAL MANHOLE (PAID UNDER ITEM 622100 - SPECIAL MANHOLE) STA 1002+92.7, RT 72.6' RIM/COVER ELEV 4942.2 42" IN (N) 4934.57 42" OUT (S) 4934.52 (SEE DETAIL, SHEET 10-25) P-17 COA DRAIN MANHOLE TYPE C - 8' DIA. STA 1002+85.7, RT 158.8' RIM/COVER ELEV 4941.7 42" IN (N) 4934.38 42" OUT (E) 4934.33 P-17A COA MODIFIED INLET TYPE D SINGLE GRATE (ALBUQUERQUE) STD DWG 2220-MODIFIED (SEE SHEET 10-21 FOR DETAILS) STA 1003+35.02, RT 87.0', GRATE ELEV 4938.0 18" OUT 4934.28
---	--

P-18 COA DRAIN MANHOLE TYPE C - 4' DIA. STA 1003+35.06, RT 47.75' RIM/COVER ELEV 4943.63 18" IN (S) 4934.24 18" OUT (W) 4934.19 P-31 NMDOT SDI TYPE I - A CURB STA 1008+78.94, RT 47.20' (LOG) LIP OF GUTTER 4973.18 FLOWLINE ELEV 4973.16 = GRATE TOC 4973.72 24" IN (E) 4969.16 24" OUT (NW) 4969.11 P-45 STA 351+03.54, RT 62.63' 24" END SECTION INV IN = 4960.61
--

P-32 NMDOT SDI TYPE I-B (*) STA 1008+33.86, RT 5.39' (LIP OF GUTTER) LIP OF GUTTER 4970.67 FLOWLINE 4970.65 = GRATE TOC 4971.14 24" IN (SE) 4965.65 24" OUT (W) 4965.60 P-33 NMDOT STORM DRAIN MANHOLE TYPE C 6' DIA STA 1008+00.00, RT 6.59' RIM/COVER ELEV 4968.45 24" IN (NE) 4960.53 18" IN (E) 4963.67 24" OUT (SW) 4954.75

P-33B NMDOT STORM DRAIN MANHOLE TYPE C 6' DIA STA 1006+69.9, RT 102.1' RIM/COVER ELEV 4949.10 24" INV IN (NE) 4943.23 24" INV IN (E) 4943.23 24" INV OUT (SW) 4943.18

P-46 24" END SECTION STA 1006+17.6, RT 124' INV OUT = 4938.48

P-33C NMDOT MEDIAN DROP INLET TYPE I STA 1008+05.00, RT 110' GRATE ELEV 4959.8 24" OUT (W) = 4953.8
--

* = MODIFIED TO MATCH
TYPE 'D' CURB & GUTTER

STORM DRAIN CULVERT BUILD NOTES

SD-4 SEE SHEET 10-1 SD-8 SEE SHEET 10-1 SD-10 BUILD 76' X 24" STORM DRAIN CULV PIPE BETWEEN P-6 & P-7 SD-11 BUILD 12' X 24" STORM DRAIN CULV PIPE BETWEEN P-7 & P-16 SD-8A BUILD 4' X 42" RCP CL IV BETWEEN P-P-16 & P-16A SD-12 BUILD 79' X 42" RCP CL IV BETWEEN P-16A & P-17 SD-12A BUILD 5' X 42" RCP CL IV BETWEEN P-17 & P-17B SD-13 BUILD 35.5' X 18" DUCTILE IRON PIPE BETWEEN P-17A & P-18 (NMDOT) SD-14 BUILD 148' X 24" STORM DRAIN CULV PIPE BETWEEN P-33 & P-33B	SD-14B BUILD 4' X 24" STORM DRAIN CUL PIPE BETWEEN P-33B & P-33A SD-14A BUILD 50' X 24" STORM DRAIN CULV PIPE BETWEEN P-33A & P-46 SD-15 BUILD 107' X 24" STORM DRAIN CULV PIPE BETWEEN P-33 & P-45 SD-16 BUILD 30' X 24" STORM DRAIN CULV PIPE BETWEEN P-33 & P32 SD-17 BUILD 57.5' X 24" STORM DRAIN CULV PIPE BETWEEN P-32 & P-31 SD-18 SEE SHEET 10-3 SD-15A BUILD 44' X 24" STORM DRAIN CULV PIPE BETWEEN P-45A & P-45B SD-15B BUILD 18' X 24" STORM DRAIN CULV PIPE BETWEEN P-45B & P-45C SD-14C BUILD 118' X 24" STORM DRAIN CULV PIPE BETWEEN P-33C & P-33B
--	---

DESIGN REVIEW COMMITTEE

CITY ENGINEER APPROVAL



4			
3			
2			
1			
NO.	DESCRIPTION	DATE	BY
REVISIONS (OR CHANGE NOTICES)			
BERNALILLO COUNTY PUBLIC WORKS DIVISION TECHNICAL SERVICES DEPARTMENT SUNPORT BOULEVARD EXTENSION SHEET 10-2 DRAINAGE NOTES SUNPORT BLVD.			

EMAIL:

PHONE:

DESIGNED BY:

DRAINAGE KEY NOTES

- 3

BUILD OUTLET PAD WITH STRUCTURAL CONCRETE CLASS A. SEE SHEETS 10-20 & 10-21 FOR ADDITIONAL INFORMATION)
- 4

BUILD DETENTION POND WITH HDPE LINER. (SEE SHEETS 10-20 TO 10-22A, FOR ADDITIONAL INFORMATION)
- 5

BUILD 16' WIDE MAINTENANCE ACCESS RD (SEE SHEET 10-20 FOR ADDITIONAL INFORMATION)
- 6

BUILD 10' W X 2' THICK RIPRAP PAD. ADJUST LIMITS IN FIELD, AS NEEDED.
(SEE SHEETS 10-10, 10-13 & 10-20 FOR ADDITIONAL INFORMATION)
- 6A

BUILD 5' W X 1' THICK RIPRAP CLASS A FROM P-45C TO P-45. (SEE PROFILE, SHEET 10-15 FOR ADDITIONAL INFORMATION)
- 6B

BUILD 1' THICK RIPRAP CL A LINED 2:1 SLOPE TREATMENT. (SEE DETAIL, SHEET 10-20 FOR ADDITIONAL INFORMATION.)
- 6C

BUILD CONCRETE MAINTENANCE ACCESS STAIRS WITH PLATFORMS AND PEDESTRIAN RAILINGS. (SEE SHEETS 10-20 & 10-22 FOR ADDITIONAL INFORMATION)
- 8

BUILD 5' W X 1' THICK RIPRAP CL A AROUND PERIMETER OF INLET.
GEOTEXTILE INCIDENTAL TO RIPRAP.

DRAINAGE STRUCTURE BUILD NOTES

P-6 NMDOT SDI TYPE II - B STA 1002+93.64, LT 35.0' (LOG) LIP OF GUTTER 4942.20 FLOWLINE ELEV 4942.21 GRATE 4941.85 TOC 4942.74 24" IN (N) 4937.36 24" OUT (S) 4937.85 P-7 NMDOT SDI TYPE II - B 1002+93.64, RT 41.00' (LOG) LIP OF GUTTER 4942.08 FLOWLINE ELEV 4941.96 GRATE 4941.73 TOC 4942.62 24" IN (N) 4937.47 24" OUT (S) 4937.42 P-17B STA 1003+02.2, RT 160.1' 42" END SECTION (NMDOT) INV OUT 4934.32	P-16 COA DRAIN MANHOLE TYPE C - 8' DIA. STA 1002+93.64 , RT 60.63' RIM/COVER ELEV 4942.29 42" IN (W) 4934.56 24" IN (N) 4937.36 42" OUT (E) 4934.51 P-16A - CS-8 CASCADE SEPARATOR, 8' DIA (PAID UNDER ITEM 622100 - SPECIAL MANHOLE) STA 1002+92.7, RT 72.6' RIM/COVER ELEV 4942.2 42" IN (N) 4934.57 42" OUT (S) 4934.52 (SEE DETAIL, SHEET 10-25) P-17 COA DRAIN MANHOLE TYPE C - 8' DIA. STA 1002+85.7, RT 158.8' RIM/COVER ELEV 4941.7 42" IN (N) 4934.38 42" OUT (E) 4934.33 P-17A COA MODIFIED INLET TYPE D SINGLE GRATE (ALBUQUERQUE) STD DWG 2220-MODIFIED (SEE SHEET 10-21 FOR DETAILS) STA 1003+35.02, RT 87.0', GRATE ELEV 4938.0 18" OUT 4934.28	P-18 COA DRAIN MANHOLE TYPE C - 4' DIA. STA 1003+35.06, RT 47.75' RIM/COVER ELEV 4943.63 18" IN (S) 4934.24 18" OUT (W) 4934.19 P-31 NMDOT SDI TYPE I - A CURB STA 1008+78.94, RT 47.20' (LOG) LIP OF GUTTER 4973.18 FLOWLINE ELEV 4973.16 = GRATE TOC 4973.72 24" IN (E) 4969.16 24" OUT (NW) 4969.11 P-45 STA 351+03.54, RT 62.63' 24" END SECTION INV IN = 4960.61	P-32 NMDOT SDI TYPE I-B (*) STA 1008+33.86, RT 5.39' (LIP OF GUTTER) LIP OF GUTTER 4970.67 FLOWLINE 4970.65 = GRATE TOC 4971.14 24" IN (SE) 4965.65 24" OUT (W) 4965.60 P-33 NMDOT STORM DRAIN MANHOLE TYPE C 6' DIA STA 1008+00.00, RT 6.59' RIM/COVER ELEV 4968.45 24" IN (NE) 4960.53 18" IN (E) 4963.67 24" OUT (SW) 4954.75 P-33B NMDOT STORM DRAIN MANHOLE TYPE C 6' DIA STA 1006+69.9, RT 102.1' RIM/COVER ELEV 4949.10 24" INV IN (NE) 4943.23 24" INV IN (E) 4943.23 24" INV OUT (SW) 4943.18 P-46 24" END SECTION STA 1006+17.6, RT 124' INV OUT = 4938.48 P-33C NMDOT MEDIAN DROP INLET TYPE I STA 1008+05.00, RT 110' GRATE ELEV 4959.8 24" OUT (W) = 4953.8	P-33A C-6 CASCADE SEPARATOR (PAID UNDER ITEM 622100 - SPECIAL MANHOLE) STA 1006+52.7, RT 99.6' (SEE DETAIL, SHEET 10-24) RIM/COVER ELEC 4948.9 24" INV IN (NE) = 4941.47 24" INV OUT (SW) = 4941.42 P-45A NMDOT SDI TYPE III - B STA 351+00.00, LT 17.00' (LOG) LIP OF GUTTER 4967.54 FLOWLINE ELEV 4967.52 = GRATE TOC 4968.08 24" OUT (E) = 4963.68 P-45B NMDOT SDI TYPE II - B STA 351+00, RT 25.96' (LOG) LIP OF GUTTER 4967.36 FLOWLINE ELEV 4967.34 = GRATE TOC 4967.90 24" INV IN (W) = 4963.46 24" INV OUT (E) = 4963.41 P-45C STA 351+10.3, RT 50.82' 24" END SECTION INV OUT = 4963.26
---	---	--	--	--

STORM DRAIN CULVERT BUILD NOTES

SD-4 SEE SHEET 10-1 SD-8 SEE SHEET 10-1 SD-10 BUILD 76' X 24" STORM DRAIN CULV PIPE BETWEEN P-6 & P-7 SD-11 BUILD 12' X 24" STORM DRAIN CULV PIPE BETWEEN P-7 & P-16 SD-8A BUILD 4' X 42" RCP CL IV BETWEEN P-P-16 & P-16A SD-12 BUILD 79' X 42" RCP CL IV BETWEEN P-16A & P-17 SD-12A BUILD 5' X 42" RCP CL IV BETWEEN P-17 & P-17B SD-13 BUILD 35.5' X 18" DUCTILE IRON PIPE BETWEEN P-17A & P-18 (NMDOT) SD-14 BUILD 148' X 24" STORM DRAIN CULV PIPE BETWEEN P-33 & P-33B	SD-14B BUILD 4' X 24" STORM DRAIN CUL PIPE BETWEEN P-33B & P-33A SD-14A BUILD 50' X 24" STORM DRAIN CULV PIPE BETWEEN P-33A & P-46 SD-15 BUILD 107' X 24" STORM DRAIN CULV PIPE BETWEEN P-33 & P-45 SD-16 BUILD 30' X 24" STORM DRAIN CULV PIPE BETWEEN P-33 & P32 SD-17 BUILD 57.5' X 24" STORM DRAIN CULV PIPE BETWEEN P-32 & P-31 SD-18 SEE SHEET 10-3 SD-15A BUILD 44' X 24" STORM DRAIN CULV PIPE BETWEEN P-45A & P-45B SD-15B BUILD 18' X 24" STORM DRAIN CULV PIPE BETWEEN P-45B & P-45C SD-14C BUILD 118' X 24" STORM DRAIN CULV PIPE BETWEEN P-33C & P-33B
--	---

DESIGN REVIEW COMMITTEE

CITY ENGINEER APPROVAL

4			
3			
2			
1			
NO.	DESCRIPTION	DATE	BY

REVISIONS (OR CHANGE NOTICES)



BERNALILLO COUNTY
PUBLIC WORKS DIVISION
TECHNICAL SERVICES DEPARTMENT

SUNPORT BOULEVARD EXTENSION
SHEET 10-2 DRAINAGE NOTES
SUNPORT BLVD.



EMAIL:

PHONE:

DESIGNED BY:

DRAINAGE STRUCTURE BUILD NOTES

P-27
NMDOT MEDIAN DROP INLET TYPE I
STA 1012+00.00, LT 38.12'
(AT FACE OF CWB)
GRATE ELEV 4997.44
24" INV OUT = 4993.44

P-28
NMDOT SDI TYPE I - B (*)
STA 1012+00.00, LT 8.12' (LOG)
LIP OF GUTTER 4996.63
FLOWLINE ELEV 4996.61
TOC 4997.17
24" IN (N) = 4992.61
24" OUT (S) = 4992.56

P-29
NMDOT MEDIAN DROP INLET TYPE I
STA 1012+00.00, RT 37.88'
(AT FACE OF CWB)
GRATE ELEV 4995.87
24" INV IN = 4991.87
24" INV OUT = 4991.82

P-30
NMDOT SDI TYPE I - A CURB
STA 1012+00.00, RT 45.88' (LOG)
LIP OF GUTTER 4995.66
FLOWLINE ELEV 4995.64 = GUTTER
TOC 4996.20
24" IN (N) = 4991.64
24" OUT (W) = 4991.59

P-47
NMDOT SDI TYPE II - B
STA 357+80, LT 17.0' (LOG)
LIP OF GUTTER 4987.50
FLOWLINE ELEV 4987.48 = GRATE
TOC 4987.92
24" INV OUT (SW) = 4982.48

P-48
NMDOT SDI TYPE II - B
STA 357+20, RT 17.0' (LOG)
LIP OF GUTTER 4984.40
FLOWLINE ELEV 4984.38 = GRATE
TOC 4984.84
24" INV IN (NE) = 4978.40
24" INV OUT (SW) = 4978.35

P-49
STA 356+69.3, RT 38.8'
24" END SECTION
INV OUT = 4978.24

(*) = MODIFIED TO MATCH
TYPE 'D' CURB & GUTTER

STORM DRAIN CULVERT BUILD NOTES

SD-18
BUILD 310.5' X 24" STORM DRAIN
CULV PIPE BETWEEN P-31 & P-30

SD-19
BUILD 7.5' X 24" STORM DRAIN
CULV PIPE BETWEEN P-30 & P-29

SD-20
BUILD 40' X 24" STORM DRAIN
CULV PIPE BETWEEN P-29 & P-28

SD-21
BUILD 30' X 24" STORM DRAIN
CULV PIPE BETWEEN P-28 & P-27

SD-38
BUILD 67.5' X 24" STORM DRAIN
CULV PIPE BETWEEN P-47 & P-48


SD-39
BUILD 53.5' X 24" STORM DRAIN
CULV PIPE BETWEEN P-48 & P-49

DRAINAGE PROFILE
SHEET REFERENCES

SYSTEM	SHEET
P-30 TO P-46	10-12 & 10-13
P-27 TO P-30	10-13
P-47 TO P-49	10-15

DRAINAGE KEY NOTES

6C BUILD 5' W X 1' THICK RIPRAP CLASS A
(SEE SHEET 10-15 FOR ADDITIONAL
INFORMATION)



DESIGN REVIEW COMMITTEE

CITY ENGINEER APPROVAL



BERNALILLO COUNTY
PUBLIC WORKS DIVISION
TECHNICAL SERVICES DEPARTMENT

SUNPORT BOULEVARD EXTENSION
DRAINAGE PLAN
SUNPORT BLVD.





DRAINAGE STRUCTURE BUILD NOTES

P-8
COA SDI SINGLE TYPE D
STA 4993+34.52, LT 24.00' (LOG)
LIP OF GUTTER 4939.71
FLOWLINE ELEV 4939.69 = GRATE
TOC 4940.25
18" OUT 4936.15

P-9
COA DRAIN MANHOLE
TYPE C - 4' DIA.
STA 4993+34.52, RT 17.19'
RIM/COVER ELEV 4939.85
18" IN (E) 4936.12
18" IN (W) 4936.11
30" OUT (N) 4936.06

P-10
COA SDI SINGLE TYPE D
STA 4993+34.52, RT 24.00' (LOG)
LIP OF GUTTER 4939.71
FLOWLINE ELEV 4939.69 = GRATE
TOC 4940.25
18" OUT 4936.15

STORM DRAIN CULVERT BUILD NOTES



SD-29
BUILD 39' X 18" RCP CL IV
BETWEEN P-8 & P-9

SD-30
BUILD 5' X 18" RCP CL IV
BETWEEN P-9 & P-10

SD-31
BUILD 484' X 30" RCP CL IV
BETWEEN P-9 & P-12

DRAINAGE PROFILE
SHEET REFERENCES

SYSTEM	SHEET
P-9 TO P-17	10-10
P-8 TO P-10	10-8



DESIGN REVIEW COMMITTEE

CITY ENGINEER APPROVAL

4			
3			
2			
1			
NO.	DESCRIPTION	DATE	BY
REVISIONS (OR CHANGE NOTICES)			
BERNALILLO COUNTY PUBLIC WORKS DIVISION TECHNICAL SERVICES DEPARTMENT			
SUNPORT BOULEVARD EXTENSION DRAINAGE PLAN BROADWAY BLVD.			

DESIGNED BY: bbailey 7/9/2020 10:30:30 AM

DRAINAGE STRUCTURE BUILD NOTES

P-11
COA SDI SINGLE TYPE D
STA 4998+23.60, LT 25.47' (LOG)
LIP OF GUTTER 4939.29
FLOWLINE ELEV 4939.27 = GRATE
TOC 4939.83
24" OUT 4935.71

P-12
COA DRAIN MANHOLE
TYPE C - 6' DIA.
STA 4998+23.60, RT 31.97'
RIM/COVER ELEV 4939.16
30" IN (S) 4935.07
30" IN (E) 4935.10
24" IN (W) 4935.43
36" OUT (N) 4935.02

P-13
COA SDI DOUBLE TYPE D &
COA SDI SINGLE TYPE D
STA 4998+23.60, RT 52.30' (LOG)
LIP OF GUTTER 4938.75
FLOWLINE ELEV 4938.73
TOC 4939.29
30" OUT 4935.19

P-14, P-20, P-19, P-19A & P-19B
SEE SHEET 10-1

P-24
COA SDI DOUBLE TYPE D
STA 5001+22.31, LT 39.57' (LOG)
LIP OF GUTTER 4939.09
FLOWLINE ELEV 4938.97 = GRATE
TOC 4939.63
24" OUT 4935.53

P-26
COA SDI DOUBLE TYPE D
STA 5001+22.31, RT 38.18' (LOG)
LIP OF GUTTER 4939.11
FLOWLINE ELEV 4938.99 = GRATE
TOC 4939.65
24" OUT 4935.55

P-13A
STA 4998+26.22, RT 69.76'
TOP OF PERFORATED
OUTLET COVER (INCIDENTAL TO 18" RCP CL IV)
4939.5+/-

P-25
COA DRAIN MANHOLE
TYPE C - 6' DIA.
STA 5001+22.31, RT 33.33'
RIM/COVER ELEV 4939.21
36" IN (N) 4935.18
18" IN (E) 4935.54
24" IN (W) 4935.18
36" OUT (S) 4935.13

P-25A
COA DRAIN MANHOLE
TYPE C - 6' DIA.
STA 5000+76.32, RT 35.58'
RIM/COVER ELEV 4939.75
36" IN (N) 4935.12
36" OUT (S) 4935.07

DRAINAGE PROFILE
SHEET REFERENCES

SYSTEM	SHEET
P-9 TO P-17	10-10
P-11 TO P-13	10-8
P-17A TO P-20	10-11
P-24 TO P-26	10-9
P-22 TO P-14	10-11
P-19B	10-1

STORM DRAIN CULVERT BUILD NOTES

SD-9
BUILD 44' X 36" DUCTILE IRON PIPE
BETWEEN P-25 & P-25A

SD-9A
BUILD 132' X 36" DUCTILE IRON PIPE
BETWEEN P--25A & P-14

SD-31
SEE SHEET 10-5

SD-31A
BUILD 55' X 24" RCP CL IV
BETWEEN P-11 & P-12

SD-31B
BUILD 17' X 24" RCP CL IV
BETWEEN P-12 & P-13

SD-32
BUILD 110' X 36" RCP CL IV
BETWEEN P-12 & P-14

SD-33
BUILD 71' X 29" S x 18" R
ELLIPTICAL CULVERT PIPE ARCH
BETWEEN P-24 & P-25


SD-34
BUILD 3' X 18" RCP CL IV
BETWEEN P-25 & P-26

SD-35
BUILD 359' X 36" RCP CL IV
BETWEEN P-22 & P-25

SD-40
BUILD 15' X 18" RCP CL IV
BETWEEN EXFILTRATION TRENCH (P-13A)
& P-13

DRAINAGE KEY NOTES

9A STA 4998+21.3 TO STA 4999+26.1, RT
BUILD 1' THICK RIPRAP CL A
EXFILTRATION TRENCH. (SEE DETAIL
THIS SHEET)



P-13
COA SDI DOUBLE TYPE D &
COA SINGLE TYPE D
STA 4998+23.60, RT 52.30' (LOG)

P-12
COA DRAIN MANHOLE
TYPE C - 6' DIA.
STA 4998+23.60, RT 31.97'

FUTURE SIDEWALK
WITH BUFFER

PROPOSED ROW

P-13A
STA 4998+26.22, RT 69.76'
TOP OF PERFORATED
OUTLET COVER (INCIDENTAL TO 18" RCP CL IV)
4939.5+/-
1' THICK RIPRAP CL A
WITH GEOTEXTILE

SD-40 - 18" RCP CL IV
WITH 90° BEND


FUTURE
HEADER CURB

18" INV IN = 4935.24

24" INV OUT = 4935.19

SD-40
(EXFILTRATION TRENCH (P-13A) TO P-13)
Q = 3.8 CFS
V = 2.17 FT/SEC

DETAIL
RIPRAP LINED EXFILTRATION TRENCH
NOT TO SCALE



NO.	DESCRIPTION	DATE	BY
4			
3			
2			
1			

REVISIONS (OR CHANGE NOTICES)








BERNALILLO COUNTY
PUBLIC WORKS DIVISION
TECHNICAL SERVICES DEPARTMENT

SUNPORT BOULEVARD EXTENSION
DRAINAGE PLAN
BROADWAY BLVD.

DESIGN REVIEW COMMITTEE

CITY ENGINEER APPROVAL



SCALE: 1" = 20' (HORIZONTAL & VERTICAL)

DESIGN REVIEW COMMITTEE

CITY ENGINEER APPROVAL

NO.	DESCRIPTION	DATE	BY
4			
3			
2			
1			

REVISIONS (OR CHANGE NOTICES)




BERNALILLO COUNTY
PUBLIC WORKS DIVISION
TECHNICAL SERVICES DEPARTMENT

SUNPORT BOULEVARD EXTENSION

DRAINAGE PROFILES


DESIGN REVIEW COMMITTEE

CITY ENGINEER APPROVAL




DRAINAGE PROFILE
P-9 TO P-17B

STA 4993+34.52, RT 17.19' TO STA 1003+02.2, RT 160.1'
(SEE SHEET 10-1 & 10-2)



DRAINAGE PROFILE
P-9 TO P-17B


STA 4993+34.52, RT 17.19' TO STA 1003+02.2, RT 160.1'
(SEE SHEET 10-1 & 10-2)



DRAINAGE PROFILE
P-9 TO P-17B

STA 4993+34.52, RT 17.19' TO STA 1003+02.2, RT 160.1'
(SEE SHEET 10-1 & 10-2)

SCALE: 1" = 20' (HORIZONTAL & VERTICAL)








DRAINAGE PROFILE
P-9 TO P-17B

STA 4993+34.52, RT 17.19' TO STA 1003+02.2, RT 160.1'
(SEE SHEET 10-1 & 10-2)

NO.	DESCRIPTION	DATE	BY
4			
3			
2			
1			
REVISIONS (OR CHANGE NOTICES)			
BERNALILLO COUNTY PUBLIC WORKS DIVISION TECHNICAL SERVICES DEPARTMENT			
SUNPORT BOULEVARD EXTENSION			
DRAINAGE PROFILES			

SEE NOTE TO CONTRACTOR FOR SUPPLEMENTAL SURVEY INFORMATION FOR EXISTING DMH (P-20) SHEET 10-1 AND ADDITIONAL EXISTING CULVERT PIPE INVERTS.



DESIGN REVIEW COMMITTEE			
NO.	DESCRIPTION	DATE	BY
4			
3			
2			
1			

SCALE: 1" = 20' (HORIZONTAL & VERTICAL)

CITY ENGINEER APPROVAL			
REVISIONS (OR CHANGE NOTICES)			
BERNALILLO COUNTY PUBLIC WORKS DIVISION TECHNICAL SERVICES DEPARTMENT			
SUNPORT BOULEVARD EXTENSION			
DRAINAGE PROFILES			




REVISONS (OR CHANGE NOTICES)

 BERNALILLO COUNTY
PUBLIC WORKS DIVISION
TECHNICAL SERVICES DEPARTMENT

SUNPORT BOULEVARD EXTENSION

DRAINAGE PROFILES



DRAINAGE PROFILE
P-30 TO P-46

STA 1012+00.00, RT 45.88' TO STA 1006+17.6, RT 124'
(SEE SHEET 10-2 & 10-3)


P-30
NMDOT SDI TYPE I - A CURB
STA 1012+00.00, RT 45.88' (LOG)
LIP OF GUTTER 4995.66
FLOWLINE ELEV 4995.64 = GUTTER
TOC 4996.20
24" IN (N) = 4991.64
24" OUT (W) = 4991.59

* = MODIFIED TO MATCH TYPE 'D'
CURB & GUTTER

P-29
NMDOT MEDIAN DROP INLET TYPE I
STA 1012+00.00, RT 37.88'
GRATE ELEV 4995.87
24" INV IN = 4991.87
24" INV OUT = 4991.82


P-28
NMDOT SDI TYPE I - B (*)
STA 1012+00.00, LT 8.12' (LOG)
LIP OF GUTTER 4996.63
FLOWLINE ELEV 4996.61
TOC 4997.17
24" IN (N) = 4992.61
24" OUT (S) = 4992.56

P-27
NMDOT MEDIAN DROP INLET TYPE I
STA 1012+00.00, LT 38.12'
GRATE ELEV 4997.44
24" INV OUT = 4993.44



DRAINAGE PROFILE
P-27 TO P-30

STA 1012+00.00, LT 38.12' TO STA 1012+00.00, RT 45.88'
(SEE SHEET 10-3)



DRAINAGE PROFILE
P-36 TO P-36A

STA 1016+63.55, LT 36.95' TO STA 1016+90.89, LT 75.79'
(SEE SHEET 10-4)



SCALE: 1" = 20' (HORIZONTAL & VERTICAL)

DESIGN REVIEW COMMITTEE

CITY ENGINEER APPROVAL

4			
3			
2			
1			
NO.	DESCRIPTION	DATE	BY



REVISIONS (OR CHANGE NOTICES)



BERNALILLO COUNTY
PUBLIC WORKS DIVISION
TECHNICAL SERVICES DEPARTMENT

SUNPORT BOULEVARD EXTENSION

DRAINAGE PROFILES






K. W. E. T.



7/10/2020

SHEET NO. 10-14



SCALE: 1" = 20' (HORIZONTAL & VERTICAL)

CITY ENGINEER APPROVAL

DESIGN REVIEW COMMITTEE

4			
3			
2			
1			
NO.	DESCRIPTION	DATE	BY


REVISIONS (OR CHANGE NOTICES)




BERNALILLO COUNTY
PUBLIC WORKS DIVISION
TECHNICAL SERVICES DEPARTMENT

SUNPORT BOULEVARD EXTENSION

DRAINAGE PROFILES



PLAN
WATER QUALITY BASIN AND OUTLET CHANNEL
SCALE: 1" = 20'



A - A
ELEVATION WATER QUALITY BASIN
AND OUTLET CHANNEL

CONCRETE CHANNEL & SLOPE PAVING
KEY GEOMETRY LAYOUT POINTS
(ALL STATIONS REFERENCE WATER QUALITY BASIN CENTERLINE CONSTRUCTION)

- 1 STA 0+89.2+/-
BEGIN 8" PCCP OUTLET CHANNEL PAVING
MATCH EXISTING SDC CONCRETE SPILLWAY
ELEV 4995.6+/-
- 2 STA 0+95.68
MATCH FACE OF SDC ACCESS ROAD WALL
BEGIN 2% PCCP OUTLET CHANNEL
ELEV 4998.0
- 3 STA 1+33.1+/-
END 8" PCCP OUTLET CHANNEL PAVING
MATCH WQB BERM SLOPE PAVING
ELEV 4998.7+/-

PLAN LEGEND

- 8" PCCP CONCRETE CHANNEL
- 4" CONCRETE SLOPE PAVING
(MATCH 8" PCCP CONCRETE CHANNEL)
- CONCRETE SPILLWAY WITH 3:1
SIDESLOPES TO MATCH TOP OF
WQB BERM. (CONSTRUCTED
WITH 4" CONCRETE SLOPE PAVING)

- NOTES:
- THE WATER QUALITY BASIN IS TO BE CONSTRUCTED WITH 3:1 SIDE SLOPES FROM THE BOTTOM OF THE BASIN AT ELEV 5000.38 TO THE TOP OF THE WQB BERM AT ELEV 5004.38 USING THE WQB BOTTOM BASELINE ALIGNMENT.
 - CONSTRUCTION OF THE WATER QUALITY BASIN AND FINAL GRADING PAID UNDER ITEM 203000 - UNCLASSIFIED EXCAVATION.
 - 8" PCCP PAID UNDER ITEM 450080 - CONCRETE PAVEMENT-8". (PER NMDOT STD DWG 450-01-1/2 & 2/2)
 - 4" CONCRETE SLOPE PAVING PAID UNDER ITEM 511000- STRUCTURAL CONCRETE CL A (PER NMDOT STD DWG 511-05-1/1), WELDED WIRE FABRIC INCIDENTAL TO ITEM 511000.

NOTE:
SEE SHEET 10-17 FOR WQB BOTTOM
BASELINE HORIZONANTAL ALIGNMENT
INFORMATION, AND MAINTENANCE ACCESS
ROAD HORIZONTAL AND VERTICAL ALIGNMENT
INFORMATION.

- KEY NOTES
- A = 3 - 6" REVERSE SLOPE DRAIN PIPES.
 - B = FACE OF MSE RETAINING WALL
(SEE 5C SHEETS FOR ADDITIONAL INFORMATION)
 - C = DRILL AND EPOXY #4 DOWELS AT 18" O.C. AT THE
INTERFACE BETWEEN THE DROP STRUCTURE
APRON AND THE PCCP. DOWELS SHALL BE 18"
IN LENGTH AND SHALL BE EMBEDDED VIA
DRILL/EPOXY A MINIMUM OF 6" INTO THE EXISTING
CONCRETE APRON. DOWELS SHALL BE PLACED
SO THAT THEY ARE CENTERED IN THE PCCP.
THE #4 DOWEL INTERFACE REINFORCING SHALL
BE INCIDENTAL TO THE PCCP BID ITEM.

WATER QUALITY BASIN
HORIZONTAL GEOMETRY

	STATION	NORTHING	EASTING
POB	0+00.00	1473579.327	1523737.943
PI	0+84.41	1473545.843	1523815.427
Tangent Direction: S 66°37'43.4" E			
Tangent Length: 84.41'			
PI	0+84.41	1473545.843	1523815.427
PI	1+08.17	1473536.970	1523837.467
Tangent Direction: S 68°04'11.9" E			
Tangent Length: 23.76'			
PI	1+08.17	1473536.970	1523837.467
PI	1+29.95	1473526.696	1523856.668
Tangent Direction: S 61°51'03.0" E			
Tangent Length: 21.78'			
PI	1+29.95	1473526.696	1523856.668
PI	1+55.20	1473512.663	1523877.664
Tangent Direction: S 56°14'32.8" E			
Tangent Length: 25.25'			
PI	1+55.20	1473512.663	1523877.664
PI	1+69.13	1473501.794	1523886.372
Tangent Direction: S 38°42'00.7" E			
Tangent Length: 13.93'			
PI	1+69.13	1473501.794	1523886.372
POE	3+92.96	1473430.036	1524098.392
Tangent Direction: S 71°18'05.7" E			
Tangent Length: 223.84'			



NO.	DESCRIPTION	DATE	BY
4			
3			
2			
1			

REVISIONS (OR CHANGE NOTICES)

BERNALILLO COUNTY
PUBLIC WORKS DIVISION
TECHNICAL SERVICES DEPARTMENT

SUNPORT BOULEVARD EXTENSION
WATER QUALITY BASIN DETAILS


WATER QUALITY BASIN BOTTOM BASELINE HORIZONTAL GEOMETRY

WQB MAINTENANCE ACCESS RD
HORIZONTAL GEOMETRY


CURVE #1	STATION	NORTHING	EASTING	CURVE #2	STATION	NORTHING	EASTING	CURVE #3	STATION	NORTHING	EASTING	CURVE #4	STATION	NORTHING	EASTING
PC	0+00.00	1473457.852	1523986.573	PC	0+16.85	1473469.510	1523995.797	PC	1+28.71	1473509.190	1523894.153	PC	1+45.56	1473497.532	1523884.929
PI	0+05.00	1473456.249	1523991.309	PI	0+21.85	1473474.246	1523997.400	PI	1+33.71	1473510.793	1523889.417	PI	1+50.56	1473492.796	1523883.326
CC	1473462.588	1523988.176		CC	1473471.113	1523991.061		CC	1473504.454	1523892.550		CC	1473495.929	1523889.665	
PT	0+07.85	1473460.985	1523992.912	PT	0+24.71	1473475.849	1523992.664	PT	1+36.56	1473506.057	1523887.814	PT	1+53.42	1473491.193	1523888.062
Radius:	5.00'			Radius:	5.00'			Radius:	5.00'			Radius:	5.00'		
Delta:	90°00'00.0" Left			Delta:	90°00'00.0" Left			Delta:	90°00'00.0" Left			Delta:	7.85'		
Length:	7.85'			Length:	7.85'			Length:	7.85'			Length:	5.00'		
Tangent:	5.00'			Tangent:	5.00'			Tangent:	5.00'			Tangent:	5.00'		
Chord:	7.07'			Chord:	7.07'			Chord:	7.07'			Chord:	7.07'		
Middle Ordinate:	1.46'			Middle Ordinate:	1.46'			Middle Ordinate:	1.46'			Middle Ordinate:	1.46'		
External:	2.07'			External:	2.07'			External:	2.07'			External:	2.07'		
Tangent (Back):	S 71°18'05.7" E			Tangent (Back):	N 18°41'54.3" E			Tangent (Back):	N 71°18'05.7" W			Tangent (Back):	S 18°41'54.3" W		
Tangent (Ahead):	N 18°41'54.3" E			Tangent (Ahead):	N 71°18'05.7" W			Tangent (Ahead):	S 18°41'54.3" W			Tangent (Ahead):	S 71°18'05.7" E		

CURVE #1	STATION	NORTHING	EASTING
PC	10+00.00	1473405.215	1524262.967
PI	11+24.52	1473418.722	1524139.180
CC	1473518.132	1524150.027	
PT	11+46.29	1473423.410	1524117.968
Radius:	100.00'		
Delta:	12°28'16.4" Right		
Length:	21.77'		
Tangent:	10.93'		
Chord:	21.72'		
Middle Ordinate:	0.59'		
External:	0.60'		
Tangent (Back):	N 83°46'22.1" W		
Tangent (Ahead):	N 71°18'05.7" W		


PT	11+46.29	1473423.410	1524117.968
POE	12+87.79	1473468.774	1523983.934
Tangent Direction:	N 71°18'05.7" W		
Tangent Length:	141.50'		




WQB ACCESS RD TYPICAL SECTION
NOT TO SCALE
(SEE SHEET 10-16)




B - B
NOT TO SCALE
(SEE SHEET 10-16)




C - C
NOT TO SCALE
(SEE SHEET 10-16)



WQB MAINTENANCE ACCESS RD
PROFILE



DETAIL
P-39 PLACEMENT
NOT TO SCALE
(SEE SHEET 10-4)



DETAIL "A"
NOT TO SCALE



BEGIN ACCESS RD
MATCH EXISTING
ROADWAY



DESIGN REVIEW COMMITTEE	CITY ENGINEER APPROVAL

NO.	DESCRIPTION	DATE	BY
4			
3			
2			
1			
REVISIONS (OR CHANGE NOTICES)			
BERNALILLO COUNTY PUBLIC WORKS DIVISION TECHNICAL SERVICES DEPARTMENT			
SUNPORT BOULEVARD EXTENSION WATER QUALITY BASIN BOTTOM AND MAINTENANCE ACCESS ROAD ALIGNMENTS AND MISCELLANEOUS DETAILS			

NOTE:
SEE SHEET 10-13 & 5C SHEETS
FOR ADDITIONAL INFORMATION
REGARDING MSE WALL.



FOR CONTRACTOR'S INFORMATION ONLY:
POTENTIAL LOCATIONS FOR USE OF THIS
DETAIL ARE:

SD-31 FROM P-9 TO STA 4994+24.5, RT
SD-32 FROM P-12 TO STA 4999+26, RT
SD-35 FROM P-22 TO P-25
SD-9 FROM P-25 TO STA 5000+71+/-, RT


CONTRACTOR TO CONFIRM WITH
PROJECT MANAGER ON ACTUAL LOCATIONS
PRIOR TO INSTALLATION.



DESIGN REVIEW COMMITTEE	CITY ENGINEER APPROVAL

NO.	DESCRIPTION	DATE	BY
4			
3			
2			
1			
REVISIONS (OR CHANGE NOTICES)			
BERNALILLO COUNTY PUBLIC WORKS DIVISION TECHNICAL SERVICES DEPARTMENT			
SUNPORT BOULEVARD EXTENSION ENERGY DISSIPATOR DETAILS AND MINIMAL COVER STORM DRAIN DETAIL			

DESIGNED BY: designer
PHONE: phone
EMAIL: email



- NOTES:
1. NMDOT STD DWG 623-01-1/1
 2. FOR STRUCTURAL OR WALL DETAILS
CONTACT STRUCTURE SECTION OR WALL
MANUFACTURER.
 3. 18" DUCTILE IRON POLYWRAPPED DOWN DRAIN
PIPE EXTENDING FROM MEDIAN DROP INLET
TO WATER QUALITY BASIN OUTLET
CONNECTION TO INCLUDE ALL NECESSARY
FITTINGS AND THRUST BLOCK WILL BE INCIDENTAL
TO CONSTRUCTION OF SHOULDER DROP INLET.
 4. DETAIL OF GRADE SEPERATION
OR WALL PENETRATION AT PIPE CROSSING
TO BE PROVIDED BY WALL MANUFACTURER.

4			
3			
2			
1			
NO.	DESCRIPTION	DATE	BY

REVISIONS (OR CHANGE NOTICES)



BERNALILLO COUNTY
PUBLIC WORKS DIVISION
TECHNICAL SERVICES DEPARTMENT

**SUNPORT BOULEVARD EXTENSION
DETAILS
DROP INLET WITH
DUCTILE IRON DOWN DRAIN**

N REVIEW COMMITTEE

CITY ENGINEER APPROVAL





CLF-01
STA 8+17.40, RT 40.00' TO
STA 8+01.40, RT 40.00'
BUILD 1,267 LF - CHAIN LINK
FENCE 6', AND ASSOCIATED
POSTS AND CORNER BRACES.

CLG-01
STA 8+01.40, RT 40.00' TO
STA 8+17.40, RT 40.00'
BUILD 2 - 9' S X 6' R CHAIN
LINK GATES

**MISCELLANEOUS
KEY LAYOUT NOTES**



- 1 BEGIN 10' WIDE X 2' THICK
RIPRAP PAD AT
24" END SECTION OUTLET
(SEE SHEET 10-13 FOR
ADDITIONAL INFORMATION)
- 2 END 10' WIDE X 2' THICK
RIPRAP PAD. ADJUST LIMIT IN
FIELD, AS NEEDED.
(SEE SHEET 10-13 FOR
ADDITIONAL INFORMATION)
- 3 ACCESS RD STA 0 +00
BEGIN ACCESS ROAD
CONSTRUCTION AT TOP
OF DETENTION BASIN
- 4 ACCESS RD STA 1+60.23
END ACCESS ROAD
CONSTRUCTION AT
BOTTOM OF DETENTION BASIN

- NOTES:**
1. ALL STATIONS BASELINE
CONSTRUCTION
DETENTION BASIN - TOP
UNLESS OTHERWISE STATED.
 2. DETENTION BASIN TO BE CONSTRUCTED
WITH 2:1 SIDE SLOPES FROM
EXISTING GROUND AT BASELINE
CONSTRUCTION TO BOTTOM OF
BASIN ELEVATION 4934.28.
BUILD 1' THICK RIPRAP ON 2:1 SLOPES.
SEE DETAIL D-D, THIS SHEET.
CONSTRUCTION ALSO INCLUDES INSTALLATION
OF 60 MIL HDPE LINER BENEATH RIPRAP
SIDE SLOPES AND BASIN BOTTOM. SEE
DETAILS, SHEET 10-22.
 3. EXCAVATION OF DETENTION BASIN
AND FINAL GRADING PAID UNDER
ITEM 203000 - UNCLASSIFIED
EXCAVATION.



**CHAINLINK FENCE
KEY LAYOUT NOTES**

- 1 STA 7+00.59, RT 59.01'
- 2 STA 7+94.41, RT 52.95'
- 3 STA 8+01.40, RT 40.00'
- 4 STA 8+17.40, RT 40.00'
- 5 STA 8+24.38, RT 52.95'
- 6 STA 11+08.02, RT 28.34'
- 7 STA 0+93.49, RT 25.37'
- 8 STA 2+30.08, RT 4.29'
- 9 STA 2+42.11, RT 16.86'
- 10 STA 4+90.85, RT 11.35'
- 11 STA 5+03.95, RT 22.91'
- 12 STA 6+76.25, RT 7.33'
- 13 STA 6+90.00, RT 39.14'



DESIGN REVIEW COMMITTEE

CITY ENGINEER APPROVAL

NO.	DESCRIPTION	DATE	BY
4			
3			
2			
1			

REVISIONS (OR CHANGE NOTICES)




BERNALILLO COUNTY
PUBLIC WORKS DIVISION
TECHNICAL SERVICES DEPARTMENT



**SUNPORT BOULEVARD EXTENSION
DETENTION BASIN
PLAN AND DETAILS**

BASELINE CONSTRUCTION DETENTION BASIN - TOP

HORIZONTAL ALIGNMENT


STATION				NORTHING				EASTING				STATION				NORTHING				EASTING				STATION				NORTHING				EASTING																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
POB				0+00.00				1473648.529				1522498.114				CURVE C-3				PT				5+29.39				1473439.933				1522879.815				PT				9+25.03				1473608.130				1522652.583				CURVE C-8																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
PC				0+65.02				1473584.083				1522489.485				PRC				2+38.30				1473498.286				1522623.337				PC				6+65.59				1473575.928				1522887.177				PC				9+28.14				1473605.447				1522651.023				PC				9+64.19				1473620.115				1522630.040																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
Tangent Direction:				S				7°37'32.8" W								PI				2+51.96				1473485.638				1522628.486				Tangent Direction:				N				3°05'55.8" E								Tangent Direction:				S				30°10'06.0" W								PI				10+05.25				1473660.228				1522621.293																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
Tangent Length:				65.02'												CC								1473509.598				1522651.123								Tangent Length:				136.19'								Tangent Length:				3.10'								CC								1473607.331				1522571.418																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
CURVE C-1																PT				2+63.93				1473481.215				1522641.405								CURVE C-5																CURVE C-7												PT				10+36.20				1473666.603				1522580.735																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
PC				0+65.02				1473584.083				1522489.485								Radius:				30.00'								PC				6+65.59				1473575.928				1522887.177								PC				9+28.14				1473605.447				1522651.023								Radius:				60.00'																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
PI				0+99.59				1473549.822				1522484.898								Delta:				48°56'54.7" Left								PI				6+94.63				1473604.928				1522888.747								PI				9+53.87				1473583.198				1522638.090								Delta:				68°45'53.4" Left																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
CC								1473578.775				1522529.132								Length:				25.63'								CC								1473577.550				1522857.221								CC								1473610.472				1522642.378								Length:				72.01'																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
PT				1+22.03				1473540.317				1522518.133								Tangent:				13.66'								PT				7+11.74				1473607.438				1522859.814								CC				9+52.14				1473608.342				1522632.607								Tangent:				41.06'																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
																				Chord:				24.86'																																Chord:				67.77'																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
																				Middle Ordinate:				2.70'																																				Middle Ordinate:				10.48'																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
																				External:				2.96'																																								External:				12.70'																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
																				Tangent Direction:				S 22°09'05.3" E																																								Tangent Direction:				N 12°18'07.1" W																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
																				Tangent Direction:				S 71°06'00.0" E																																								Tangent Direction:				N 81°04'00.5" W																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
																								PT				2+63.93				1473481.215				1522641.405																												PT				10+36.20				1473666.603				1522580.735																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
																								PC				4+73.99				1473413.173				1522840.141																												PC				10+85.02				1473674.184				1522532.507																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
																								Tangent Direction:				S 71°06'00.0" E																																				Tangent Direction:				N 81°04'00.5" W																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
																								Tangent Length:				210.06'																																				Tangent Length:				48.82'																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											





DETAIL
CURB AND GUTTER TRANSITION AT
COA TYPE "D" INLETS

(NOT TO SCALE)



NOTE:
WARP DETENTION BASIN RIPRAP LINED SLOPES
TO MATCH SIDES OF STARWAY AND PLATFORMS



4			
3			
2			
1			
NO.	DESCRIPTION	DATE	BY
REVISIONS (OR CHANGE NOTICES)			



REVISIONS (OR CHANGE NOTICES)



BERNALILLO COUNTY
PUBLIC WORKS DIVISION
TECHNICAL SERVICES DEPARTMENT


SUNPORT BOULEVARD EXTENSION

MISCELLANEOUS DRAINAGE DETAILS




SUNPORT BOULEVARD EXTENSION

HDPE LINER DETAILS (SHEET 1 OF 2)



PIPE BOOT BANDING DETAIL



NOTE:
EARTH ADJACENT TO CONCRETE COLLAR TO BE WELL COMPACTED TO PREVENT FUTURE DIFFERENTIAL SETTLEMENT. ALL CONCRETE COLLARS TO BE CHAMFERED A MINIMUM OF 1" (TYP.) AT ALL CORNERS IN CONTACT WITH LINER.

PIPE PENETRATION W/SINGLE PIPE BOOT AND CONCRETE COLLAR W/POLYLOCK ATTACHMENTS


K. W. Eades

9/14/2020


4			
3			
2			
1			
NO.	DESCRIPTION	DATE	BY

DESIGN REVIEW COMMITTEE	CITY ENGINEER APPROVAL	REVISIONS (OR CHANGE NOTICES)	
		BERNALILLO COUNTY PUBLIC WORKS DIVISION TECHNICAL SERVICES DEPARTMENT	
		SUNPORT BOULEVARD EXTENSION HDPE LINER DETAILS (SHEET 2 OF 2)	

DESIGNED BY: designer
PHONE: phone
EMAIL: email



PLAN




SECTION B-B

GENERAL NOTES:

- 1. ALL BARS SHALL BE STRUCTURAL GRADE STEEL, GRADE A36.
- 2. THE GRATE SHALL BE WELDED WITH 1/8" FILLET WELD AROUND BOTH SIDES OF CROSS BARS, 1/4". FILLET WELD BOTH SIDES OF BEARING BARS TO END BARS.
- 3. AFTER CLEANING SURFACE OF SCALE, RUST, OILS, ETC., PAINT GRATE WITH ONE SHOP COAT RED OXIDE, TWO FINISH COATS ALUMINUM PAINT (AASHTO M 69).
- 4. TOP OF CROSS BARS SHALL BE FLUSH WITH TOP OF GRATE.
- 5. GRIND WELDS FLUSH WITH BEARING BARS.
- 6. WHEN INSTALLED IN FRAME, PUSH TIGHT TO ONE SIDE, OTHER SIDE SHALL HAVE 1/2" MAX. OPENING. SPACERS WELDED TO FRAME MAY BE USED IF REQUIRED TO KEEP 1/2" SPACE OR LESS.

CONSTRUCTION NOTES:

- A. BEARING BARS, (13) 1/2" X 3 1/2" X 39".
- B. END BARS, (2) 1/2" X 3" X 25".
- C. CROSS BARS, (9) 1/2" DIA. X 24".



SECTION A-A

REVISIONS	CITY OF ALBUQUERQUE	
	DRAINAGE STORM INLET ALBUQUERQUE GRATE DWG. 2220-MODIFIED FEB. 2014	

FOR INFORMATION ONLY

4			
3			
2			
1			
NO.	DESCRIPTION	DATE	BY

DESIGN REVIEW COMMITTEE	CITY ENGINEER APPROVAL


REVISIONS (OR CHANGE NOTICES)




BERNALILLO COUNTY
PUBLIC WORKS DIVISION
TECHNICAL SERVICES DEPARTMENT

SUNPORT BOULEVARD EXTENSION
COA DRAINAGE STORM INLET
ALBUQUERQUE GRATE

DESIGNED BY: designer
PHONE: phone
EMAIL: email



PLAN VIEW B-B
NOT TO SCALE



ELEVATION A-A
NOT TO SCALE

SITE SPECIFIC DATA REQUIREMENTS			
STRUCTURE ID		P-33A	
WATER QUALITY FLOW RATE (cfs [L/s])		5.0	
PEAK FLOW RATE (cfs [L/s])		33.5	
RETURN PERIOD OF PEAK FLOW (yrs)		100	
RIM ELEVATION		4848.9	
PIPE DATA:	INVERT	MATERIAL	DIAMETER
INLET PIPE 1	4941.47		24" (*)
INLET PIPE 2	NONE		
OUTLET PIPE	4941.42		24" (*)
NOTES / SPECIAL REQUIREMENTS: (*) = 24" STORM DRAIN CULVERT PIPE			

GENERAL NOTES:

- STRUCTURE SHALL MEET AASHTO HS20 LOAD RATING, ASSUMING EARTH COVER OF 0' TO 2' [610]. AND GROUNDWATER ELEVATION AT, OR BELOW, THE OUTLET PIPE INVERT ELEVATION. ENGINEER OF RECORD TO CONFIRM ACTUAL GROUNDWATER ELEVATION. CASTINGS SHALL MEET AASHTO M306.
- STRUCTURE SHALL BE PRECAST CONCRETE CONFORMING TO ASTM C478 AND AASHTO LOAD FACTOR DESIGN METHOD.
- ALTERNATE UNITS ARE SHOWN IN MILLIMETERS [mm].

INSTALLATION NOTES

- ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE SPECIFIED BY ENGINEER OF RECORD.
- CONTRACTOR TO PROVIDE EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE CASCADE SEPARATOR MANHOLE STRUCTURE.
- CONTRACTOR TO INSTALL JOINT SEALANT BETWEEN ALL STRUCTURE SECTIONS AND ASSEMBLE STRUCTURE.
- CONTRACTOR TO PROVIDE, INSTALL, AND GROUT INLET AND OUTLET PIPE(S). MATCH PIPE INVERTS WITH ELEVATIONS SHOWN. ALL PIPE CENTERLINES TO MATCH PIPE OPENING CENTERLINES.
- CONTRACTOR TO TAKE APPROPRIATE MEASURES TO ASSURE UNIT IS WATER TIGHT, HOLDING WATER TO FLOWLINE INVERT MINIMUM. IT IS SUGGESTED THAT ALL JOINTS BELOW PIPE INVERTS ARE GROUTED.

FOR INFORMATION ONLY

4			
3			
2			
1			
NO.	DESCRIPTION	DATE	BY

REVISIONS (OR CHANGE NOTICES)




BERNALILLO COUNTY
PUBLIC WORKS DIVISION
TECHNICAL SERVICES DEPARTMENT


SUNPORT BOULEVARD EXTENSION
6' DIAMETER SPECIAL MANHOLE
DETAILS

DESIGN REVIEW COMMITTEE

CITY ENGINEER APPROVAL



PLAN VIEW B-B
NOT TO SCALE



ELEVATION A-A
NOT TO SCALE

SITE SPECIFIC DATA REQUIREMENTS			
STRUCTURE ID		P16-A	
WATER QUALITY FLOW RATE (cfs [L/s])		7.4	
PEAK FLOW RATE (cfs [L/s])		26	
RETURN PERIOD OF PEAK FLOW (yrs)		100	
RIM ELEVATION		4942.2	
PIPE DATA:		INVERT	MATERIAL DIAMETER
INLET PIPE 1		4934.57	42" RCP
INLET PIPE 2		NONE	
OUTLET PIPE		4934.52	42" RCP
NOTES / SPECIAL REQUIREMENTS:			

GENERAL NOTES:

- STRUCTURE SHALL MEET AASHTO HS20 LOAD RATING, ASSUMING EARTH COVER OF 0' TO 2' [610], AND GROUNDWATER ELEVATION AT, OR BELOW, THE OUTLET PIPE INVERT ELEVATION. ENGINEER OF RECORD TO CONFIRM ACTUAL GROUNDWATER ELEVATION. CASTINGS SHALL MEET AASHTO M306.
- STRUCTURE SHALL BE PRECAST CONCRETE CONFORMING TO ASTM C478 AND AASHTO LOAD FACTOR DESIGN METHOD.
- ALTERNATE UNITS ARE SHOWN IN MILLIMETERS [mm].

INSTALLATION NOTES

- ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE SPECIFIED BY ENGINEER OF RECORD.
- CONTRACTOR TO PROVIDE EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE CASCADE SEPARATOR MANHOLE STRUCTURE.
- CONTRACTOR TO INSTALL JOINT SEALANT BETWEEN ALL STRUCTURE SECTIONS AND ASSEMBLE STRUCTURE.
- CONTRACTOR TO PROVIDE, INSTALL, AND GROUT INLET AND OUTLET PIPE(S). MATCH PIPE INVERTS WITH ELEVATIONS SHOWN. ALL PIPE CENTERLINES TO MATCH PIPE OPENING CENTERLINES.
- CONTRACTOR TO TAKE APPROPRIATE MEASURES TO ASSURE UNIT IS WATER TIGHT, HOLDING WATER TO FLOWLINE INVERT MINIMUM. IT IS SUGGESTED THAT ALL JOINTS BELOW PIPE INVERTS ARE GROUTED.

FOR INFORMATION ONLY

4			
3			
2			
1			
NO.	DESCRIPTION	DATE	BY

REVISIONS (OR CHANGE NOTICES)



BERNALILLO COUNTY
PUBLIC WORKS DIVISION
TECHNICAL SERVICES DEPARTMENT

SUNPORT BOULEVARD EXTENSION
8' DIAMETER SPECIAL MANHOLE
DETAILS

DESIGN REVIEW COMMITTEE

CITY ENGINEER APPROVAL

\\AD.CONTECH-CPI.COM\ROOT\COMMON\CAD\TREATMENT\21 CASCADE\40 STANDARD DRAWINGS\DWGCS-8-DTL.DWG
9/11/2020 1:45 PM

EMAIL: email

PHONE: phone

DESIGNED BY: designer

APPENDIX C
AHYMO DATA

*S Sunport Boulevard extension by Jonah Ruybalid NOV 19 2019

*

START TIME=0.0 HR PUNCH CODE=0

*S 100-YEAR, 24-HOUR STORM EVENT- ZONE 2

RAINFALL TYPE=2 QUARTER HR RAIN=0.00 ONE HR RAIN=1.80
SIX HR RAIN=2.24 DAILY RAIN=2.59 DT=0.05 HR

* 10-YEAR, 24-HOUR STORM EVENT, - ZONE 2

*RAINFALL TYPE=2 QUARTER HR RAIN=0.00 ONE HR RAIN=1.14
* SIX HR RAIN=1.47 DAILY RAIN=1.76 DT=0.05 HR
*

SEDIMENT BULK CODE = 1 BULK FACTOR = 1.10

*PROPOSED SITE CONDITIONS

*

COMPUTE NM HYD ID=1 HYD=XF DA=0.003794
A B C D 30 40 20 10
TP=0.13330 MASS RAIN=-1

PRINT HYD ID=1 CODE=1

*

COMPUTE NM HYD ID=2 HYD=XE1 DA=0.0.0004978
A B C D 0 0 85 15
TP=0.13330 MASS RAIN=-1

PRINT HYD ID=2 CODE=1

*

COMPUTE NM HYD ID=3 HYD=XE2 DA=0.0.0002535
A B C D 0 0 80 20
TP=0.13330 MASS RAIN=-1

PRINT HYD ID=3 CODE=1

*

*Add basins XF and XE2 basin-routing

ADD HYD ID=4 HYD=XF_XE2 ID=1 ID=3
PRINT HYD ID=4 CODE=1

*

COMPUTE NM HYD ID=5 HYD=XE3 DA=0.003694
A B C D 86 0 14 0
TP=0.13330 MASS RAIN=-1

PRINT HYD ID=5 CODE=1

*

COMPUTE NM HYD ID=6 HYD=XD3 DA=0.0017353
A B C D 0 40 50 10
TP=0.13330 MASS RAIN=-1

PRINT HYD ID=6 CODE=1

*

COMPUTE NM HYD ID=7 HYD=XD4 DA=0.00021196
A B C D 0 0 70 30
TP=0.13330 MASS RAIN=-1

PRINT HYD ID=7 CODE=1

*

*Add basins XD3 and XD4 basin-routing

```

ADD HYD          ID=8  HYD=XD3_XD4  ID=6  ID=7
PRINT HYD        ID=8  CODE=1
*
*Add basins XD3, XD4, XE2, XF basin-routing
ADD HYD          ID=9  HYD=XD3_XD4_XE2_XF  ID=4  ID=8
PRINT HYD        ID=9  CODE=1
*
COMPUTE NM HYD   ID=10  HYD=XD5  DA=0.002328
                  A B C D  0  50  50  0
                  TP=0.13330  MASS RAIN=-1
PRINT HYD        ID=10  CODE=1
*
COMPUTE NM HYD   ID=11  HYD=H3  DA=0.000283628
                  A B C D  0  0  0  100
                  TP=0.13330  MASS RAIN=-1
PRINT HYD        ID=11  CODE=1
*
COMPUTE NM HYD   ID=12  HYD=H4  DA=0.0012214
                  A B C D  0  0  0  100
                  TP=0.13330  MASS RAIN=-1
PRINT HYD        ID=12  CODE=1
*
*Add basins H3 and H4 basin-routing
ADD HYD          ID=13  HYD=H3_H4  ID=11  ID=12
PRINT HYD        ID=13  CODE=1
*
COMPUTE NM HYD   ID=14  HYD=I3  DA=0.0013089
                  A B C D  0  0  0  100
                  TP=0.13330  MASS RAIN=-1
PRINT HYD        ID=14  CODE=1
*
*Add basins I3 H3 H4 basin-routing
ADD HYD          ID=15  HYD=I3_H3_H4  ID=13  ID=14
PRINT HYD        ID=15  CODE=1
*
COMPUTE NM HYD   ID=16  HYD=I4  DA=0.000589138
                  A B C D  0  0  0  100
                  TP=0.13330  MASS RAIN=-1
PRINT HYD        ID=16  CODE=1
*
*Add basins I4 I3 H3 H4 basin-routing
ADD HYD          ID=17  HYD=WQPondInS(I4_I3_H3_H4)  ID=15  ID=16
PRINT HYD        ID=17  CODE=1
*
*Add basins I4 I3 H3 H4 XE1 basin-routing WQPondIn
ADD HYD          ID=18  HYD=I4_I3_H3_H4_XE1  ID=2  ID=17
PRINT HYD        ID=18  CODE=1
*
*Add basins XE2 and XD5 basin-routing SDC in overland
ADD HYD          ID=19  HYD=XE2_XD5  ID=5  ID=10

```

```

PRINT HYD          ID=19  CODE=1
*
* Water Quality Pond outflows over weir to south diversion channel
ROUTE RESERVOIR    ID=20  HYD=WQPondOut  INFLOW ID=18  CODE=5
      OUTFLOW(cfs)    STORAGE(ac ft)    ELEV(ft)
      0.000           0.0              5000.4
      0.010           0.0336           5001.0
      0.010           0.1012           5002.0
      1.700           0.1879           5003.0
      61.200          0.2954           5004.0
      224.200         0.5023           5005.0
      502.900         0.7324           5006.0
      912.800         0.9827           5007.0
      1000.000        10.0000           5008.0
*
*****
*
COMPUTE NM HYD      ID=1  HYD=XD1  DA=0.0015604
A B C D  0  45  40  15
TP=0.13330  MASS RAIN=-1
PRINT HYD          ID=1  CODE=1
*
COMPUTE NM HYD      ID=2  HYD=XD2  DA=0.0016502
A B C D  10  30  40  20
TP=0.13330  MASS RAIN=-1
PRINT HYD          ID=2  CODE=1
*
COMPUTE NM HYD      ID=3  HYD=M4   DA=0.0003507
A B C D  0  0  0  100
TP=0.13330  MASS RAIN=-1
PRINT HYD          ID=3  CODE=1
*
COMPUTE NM HYD      ID=4  HYD=M3   DA=0.00033327
A B C D  0  0  0  100
TP=0.13330  MASS RAIN=-1
PRINT HYD          ID=4  CODE=1
*
COMPUTE NM HYD      ID=5  HYD=XM2  DA=0.0010503
A B C D  0  0  78  22
TP=0.13330  MASS RAIN=-1
PRINT HYD          ID=5  CODE=1
*
COMPUTE NM HYD      ID=6  HYD=XM1  DA=0.0005732
A B C D  0  0  55  45
TP=0.13330  MASS RAIN=-1
PRINT HYD          ID=6  CODE=1
*
COMPUTE NM HYD      ID=7  HYD=M1   DA=0.00185513
A B C D  0  10  38  52
TP=0.13330  MASS RAIN=-1

```

```

PRINT HYD          ID=7  CODE=1
*
COMPUTE NM HYD      ID=8  HYD=M2  DA=0.00060728
                   A B C D  0  0  0  100
                   TP=0.13330  MASS RAIN=-1
PRINT HYD          ID=8  CODE=1
*
*Add basins XD1 M4 basin-routing
ADD HYD            ID=9  HYD=XD1_M4  ID=1  ID=3
PRINT HYD          ID=9  CODE=1
*
*Add basins XD2 M3 basin-routing
ADD HYD            ID=10  HYD=XD2_M3  ID=2  ID=4
PRINT HYD          ID=10  CODE=1
*
*Add basins XM2 XD2 M3 basin-routing
ADD HYD            ID=11  HYD=XM2_XD2_M3  ID=5  ID=10
PRINT HYD          ID=11  CODE=1
*
*Add basins XM2 XD2 M3 XD1 M4 basin-routing
ADD HYD            ID=12  HYD=XM2_XD2_M3_XD1_M4  ID=9  ID=11
PRINT HYD          ID=12  CODE=1
*
*Add basins M1 XM1 basin-routing
ADD HYD            ID=13  HYD=M1_XM1  ID=6  ID=7
PRINT HYD          ID=13  CODE=1
*
COMPUTE NM HYD      ID=14  HYD=N  DA=0.00367838
                   A B C D  15  0  85  0
                   TP=0.13330  MASS RAIN=-1
PRINT HYD          ID=14  CODE=1
*
*Add basins N XM2 XD2 M3 XD1 M4 basin-routing
ADD HYD            ID=15  HYD=N_XM2_XD2_M3_XD1_M4  ID=12  ID=14
PRINT HYD          ID=15  CODE=1
*
*Add basins M1 XM1 M2 basin-routing
ADD HYD            ID=16  HYD=M1_XM1_M2  ID=8  ID=13
PRINT HYD          ID=16  CODE=1
*
*Add basins M1 XM1 M2 N XM2 XD2 M3 XD1 M4 basin-routing
ADD HYD            ID=17  HYD=woodward  ID=15  ID=16
PRINT HYD          ID=17  CODE=1
*
COMPUTE NM HYD      ID=18  HYD=I1  DA=0.000621979
                   A B C D  0  0  0  100
                   TP=0.13330  MASS RAIN=-1
PRINT HYD          ID=18  CODE=1
*
COMPUTE NM HYD      ID=19  HYD=I2  DA=0.000247657

```



```

                A B C D  0  0  0  100
                TP=0.13330  MASS RAIN=-1
PRINT HYD      ID=19  CODE=1
*
*Add basins I2 I1 basin-routing
ADD HYD        ID=20  HYD=I2_I1  ID=18  ID=19
PRINT HYD      ID=20  CODE=1
*
COMPUTE NM HYD  ID=1  HYD=H2  DA=0.000540774
                A B C D  0  0  0  100
                TP=0.13330  MASS RAIN=-1
PRINT HYD      ID=1  CODE=1
*
*Add basins H2 I2 I1 basin-routing
ADD HYD        ID=2  HYD=H2_I2_I1  ID=20  ID=1
PRINT HYD      ID=2  CODE=1
*
COMPUTE NM HYD  ID=3  HYD=H1  DA=0.000254482
                A B C D  0  0  0  100
                TP=0.13330  MASS RAIN=-1
PRINT HYD      ID=3  CODE=1
*
*Add basins H1 H2 I2 I1 basin-routing
ADD HYD        ID=4  HYD=H1_H2_I2_I1  ID=2  ID=3
PRINT HYD      ID=4  CODE=1
*
COMPUTE NM HYD  ID=5  HYD=H  DA=0.000663978
                A B C D  0  0  0  100
                TP=0.13330  MASS RAIN=-1
PRINT HYD      ID=5  CODE=1
*
*Add basins H H1 H2 I2 I1 basin-routing
ADD HYD        ID=6  HYD=H_H1_H2_I2_I1  ID=4  ID=5
PRINT HYD      ID=6  CODE=1
*
COMPUTE NM HYD  ID=7  HYD=I  DA=0.000641823
                A B C D  0  0  0  100
                TP=0.13330  MASS RAIN=-1
PRINT HYD      ID=7  CODE=1
*
*Add basins I H H1 H2 I2 I1 basin-routing
ADD HYD        ID=8  HYD=I_H_H1_H2_I2_I1  ID=6  ID=7
PRINT HYD      ID=8  CODE=1
*
*Add basins DetPondInE(M1 XM1 M2 N XM2 XD2 M3 XD1 M4 I H H1 H2 I2 I1) basin-routing
ADD HYD        ID=21  HYD=DetPondInE  ID=17  ID=8
PRINT HYD      ID=21  CODE=1
*
COMPUTE NM HYD  ID=9  HYD=P  DA=0.000468872
                A B C D  0  0  0  100

```

```

TP=0.13330  MASS RAIN=-1
PRINT HYD      ID=9  CODE=1
*
COMPUTE NM HYD  ID=10  HYD=S  DA=0.000444064
A B C D  0  0  0  100
TP=0.13330  MASS RAIN=-1
PRINT HYD      ID=10  CODE=1
*
*Add basins S P basin-routing
ADD HYD        ID=11  HYD=S_P  ID=9  ID=10
PRINT HYD      ID=11  CODE=1
*
COMPUTE NM HYD  ID=12  HYD=P1  DA=0.000967237
A B C D  0  0  10  90
TP=0.13330  MASS RAIN=-1
PRINT HYD      ID=12  CODE=1
*
COMPUTE NM HYD  ID=13  HYD=S1  DA=0.000578041
A B C D  0  0  10  90
TP=0.13330  MASS RAIN=-1
PRINT HYD      ID=13  CODE=1
*
*Add basins S1 P1 basin-routing
ADD HYD        ID=14  HYD=S1_P1  ID=12  ID=13
PRINT HYD      ID=14  CODE=1
*
*Add basins S P S1 P1 basin-routing
ADD HYD        ID=15  HYD=S1_P1_S_P  ID=11  ID=14
PRINT HYD      ID=15  CODE=1
*
COMPUTE NM HYD  ID=16  HYD=T  DA=0.00126173
A B C D  0  0  0  100
TP=0.13330  MASS RAIN=-1
PRINT HYD      ID=16  CODE=1
*
*Add basins T S1 P1 S P basin-routing
ADD HYD        ID=17  HYD=T_S1_P1_S_P  ID=15  ID=16
PRINT HYD      ID=17  CODE=1
*
COMPUTE NM HYD  ID=18  HYD=Q1  DA=0.000194272
A B C D  0  0  10  90
TP=0.13330  MASS RAIN=-1
PRINT HYD      ID=18  CODE=1
*
COMPUTE NM HYD  ID=19  HYD=R1  DA=0.0003026
A B C D  0  0  10  90
TP=0.13330  MASS RAIN=-1
PRINT HYD      ID=19  CODE=1
*
*Add basins Q1 R1 basin-routing

```

```

ADD HYD          ID=20  HYD=Q1_R1  ID=18  ID=19
PRINT HYD        ID=20  CODE=1
*
COMPUTE NM HYD    ID=1  HYD=Q  DA=0.000793384
                  A B C D  0  0  8  92
                  TP=0.13330  MASS RAIN=-1
PRINT HYD        ID=1  CODE=1
*
COMPUTE NM HYD    ID=2  HYD=R  DA=0.000582811
                  A B C D  0  0  10  90
                  TP=0.13330  MASS RAIN=-1
PRINT HYD        ID=2  CODE=1
*
*Add basins Q R basin-routing
ADD HYD          ID=3  HYD=Q_R  ID=1  ID=2
PRINT HYD        ID=3  CODE=1
*
*Add basins Q R Q1 R1 basin-routing
ADD HYD          ID=4  HYD=Q_R_Q1_R1  ID=20  ID=3
PRINT HYD        ID=4  CODE=1
*
*Add basins Q R Q1 R1 T S1 P1 S P basin-routing
ADD HYD          ID=5  HYD=broadway  ID=17  ID=4
PRINT HYD        ID=5  CODE=1
*
COMPUTE NM HYD    ID=6  HYD=XC  DA=0.004401217
                  A B C D  0  0  80  20
                  TP=0.13330  MASS RAIN=-1
PRINT HYD        ID=6  CODE=1
*
*Add basins Q R Q1 R1 T S1 P1 S P XC basin-routing
ADD HYD          ID=7  HYD=broadway XC  ID=5  ID=6
PRINT HYD        ID=7  CODE=1
*
COMPUTE NM HYD    ID=8  HYD=D  DA=0.000317857
                  A B C D  0  0  0  100
                  TP=0.13330  MASS RAIN=-1
PRINT HYD        ID=8  CODE=1
*
COMPUTE NM HYD    ID=9  HYD=C  DA=0.00037726
                  A B C D  0  0  0  100
                  TP=0.13330  MASS RAIN=-1
PRINT HYD        ID=9  CODE=1
*
*Add basins D C basin-routing
ADD HYD          ID=10  HYD=D_C  ID=8  ID=9
PRINT HYD        ID=10  CODE=1
*
*Add basins D C Q R Q1 R1 T S1 P1 S P XC basin-routing
ADD HYD          ID=11  HYD=Broadway Sun  ID=7  ID=10

```

```

PRINT HYD          ID=11  CODE=1
*
COMPUTE NM HYD      ID=12  HYD=G1  DA=0.001237166
                   A B C D    0  0  0  100
                   TP=0.13330  MASS RAIN=-1
PRINT HYD          ID=12  CODE=1
*
COMPUTE NM HYD      ID=13  HYD=G  DA=0.001068715
                   A B C D    0  0  0  100
                   TP=0.13330  MASS RAIN=-1
PRINT HYD          ID=13  CODE=1
*
*Add basins G1 G basin-routing
ADD HYD             ID=14  HYD=G1_G  ID=12  ID=13
PRINT HYD           ID=14  CODE=1
*
*Add basins G1 G D C Q R Q1 R1 T S1 P1 S P XC basin-routing
ADD HYD             ID=15  HYD=DetPondInW  ID=11  ID=14
PRINT HYD           ID=15  CODE=1
*
*Add basins G1 G D C Q R Q1 R1 T S1 P1 S P XC M1 XM1 M2 N XM2 XD2 M3 XD1 M4 I H H1
H2 I2 I1 basin-routing
ADD HYD             ID=16  HYD=DetPondInSS  ID=21  ID=15
PRINT HYD           ID=16  CODE=1
*
COMPUTE NM HYD      ID=17  HYD=XJ  DA=0.007554964
                   A B C D    30  33  37  0
                   TP=0.13330  MASS RAIN=-1
PRINT HYD           ID=17  CODE=1
*
COMPUTE NM HYD      ID=18  HYD=XJ1  DA=0.0104488
                   A B C D    0  75  25  0
                   TP=0.13330  MASS RAIN=-1
PRINT HYD           ID=18  CODE=1
*
*Add basins XJ1 XJ basin-routing
ADD HYD             ID=19  HYD=XJ1_XJ  ID=17  ID=18
PRINT HYD           ID=19  CODE=1
*
*Add basins XJ1 XJ G1 G D C Q R Q1 R1 T S1 P1 S P XC M1 XM1 M2 N XM2 XD2 M3 XD1 M4 I
H H1 H2 I2 I1 basin-routing
ADD HYD             ID=20  HYD=DetPondIn  ID=16  ID=19
PRINT HYD           ID=20  CODE=1
*
* pond discharges into storm sewer that discharges into the San Jose Drain
ROUTE RESERVOIR     ID=1  HYD=DetPondOut  INFLOW ID=20  CODE=5
                   OUTFLOW(cfs) STORAGE(ac ft)  ELEV(ft)
                   0.000          0.000        4934.3
                   0.850          0.600        4935
                   2.490          1.430        4936

```


4.730	2.350	4937
6.760	3.320	4938
14.530	4.350	4939
16.130	5.450	4940
17.770	6.600	4941
18.640	7.280	4941.5

*

*

```

COMPUTE NM HYD      ID=2  HYD=XV  DA=0.003050928
                     A B C D    0  0 10 90
                     TP=0.13330  MASS RAIN=-1

```

```

PRINT HYD           ID=2  CODE=1

```

*

```

COMPUTE NM HYD      ID=3  HYD=A   DA=0.000885059
                     A B C D    0  0  2 98
                     TP=0.13330  MASS RAIN=-1

```

```

PRINT HYD           ID=3  CODE=1

```

*

```

COMPUTE NM HYD      ID=4  HYD=B   DA=0.000822449
                     A B C D    0  0  2 98
                     TP=0.13330  MASS RAIN=-1

```

```

PRINT HYD           ID=4  CODE=1

```

*

*Add basins A B basin-routing

```

ADD HYD              ID=5  HYD=A_B  ID=3  ID=4

```

```

PRINT HYD           ID=5  CODE=1

```

*

*Add basins XV DetPondOut basin-routing

```

ADD HYD              ID=6  HYD=XV_DetPondOut  ID=1  ID=2

```

```

PRINT HYD           ID=6  CODE=1

```

*

*Add basins A B XV DetPondOut basin-routing

```

ADD HYD              ID=7  HYD=XV_DetPondOut_A_B  ID=5  ID=6

```

```

PRINT HYD           ID=7  CODE=1

```

*

FINISH

AHYMO Input file ? page 1 of 9

AHYMO PROGRAM SUMMARY TABLE (AHYMO-S4) - Ver. S4.01a,
 Rel: 01a RUN DATE (MON/DAY/YR) =07/07/2020
 INPUT FILE = C:\Users\Public\AHYMOdata\AHYMO input 7-7-20_MC.txt
 USER NO.= MolzenCorSingleA36115542

TIME TO RUNOFF COMMAND (INCHES)	TO PEAK PEAK (HOURS)	CFS HYDROGRAPH PER IDENTIFICATION ACRE	FROM PAGE = ID NO. NOTATION	TO ID NO.	AREA (SQ MI)	PEAK DISCHARGE (CFS)	RUNOFF VOLUME (AC-FT)
--	-------------------------------	--	---	-----------------	-----------------	----------------------------	-----------------------------

*S Sunport Boulevard extension by Jonah Ruybalid NOV 19 2019
 START

TIME= 0.00

*S 100-YEAR, 24-HOUR STORM EVENT- ZONE 2
 RAINFALL TYPE= 2 NOAA 14

RAIN24= 2.590

SEDIMENT BULK

PK BF = 1.10

COMPUTE NM HYD	XF -	1	0.00379	6.50	0.209
1.03092 1.500	2.677 PER IMP=	10.00			
COMPUTE NM HYD	XE1 -	2	0.00005	0.12	0.004
1.35843 1.500	3.891 PER IMP=	15.00			
COMPUTE NM HYD	XE2 -	3	0.00003	0.07	0.002
1.42997 1.500	4.021 PER IMP=	20.00			
ADD HYD	XF_XE2 1&	3 4	0.00382	6.57	0.210
1.03277 1.500	2.686				
COMPUTE NM HYD	XE3 -	5	0.00369	4.73	0.143
0.72397 1.550	2.003 PER IMP=	0.00			
COMPUTE NM HYD	XD3 -	6	0.00174	3.51	0.109
1.17561 1.500	3.158 PER IMP=	10.00			
COMPUTE NM HYD	XD4 -	7	0.00021	0.52	0.018
1.57304 1.500	3.863 PER IMP=	30.00			
ADD HYD	XD3_XD4 6&	7 8	0.00195	4.03	0.126
1.21237 1.500	3.234				
ADD HYD	XD3_XD4_XE2_	4& 8 9	0.00577	10.60	0.336
1.09342 1.500	2.871				
COMPUTE NM HYD	XD5 -	10	0.00233	4.36	0.125
1.00639 1.500	2.929 PER IMP=	0.00			
COMPUTE NM HYD	H3 -	11	0.00028	0.87	0.039
2.57457 1.500	4.786 PER IMP=	100.00			
COMPUTE NM HYD	H4 -	12	0.00122	3.71	0.168
2.57457 1.500	4.747 PER IMP=	100.00			
ADD HYD	H3_H4 11&12	13	0.00151	4.58	0.207
2.57427 1.500	4.754				
COMPUTE NM HYD	I3 -	14	0.00131	3.98	0.180
2.57457 1.500	4.747 PER IMP=	100.00			
ADD HYD	I3_H3_H4 13&14	15	0.00281	8.56	0.386
2.57430 1.500	4.751				

COMPUTE NM HYD	I4	-	16	0.00059	1.80	0.081
2.57457	1.500	4.762	PER IMP= 100.00			
ADD HYD	WQPondInS(I4	15&16	17	0.00340	10.35	0.467
2.57428	1.500	4.753				
ADD HYD	I4_I3_H3_H4_	2&17	18	0.00345	10.48	0.471
2.55558	1.500	4.741				
ADD HYD	XE2_XD5	5&10	19	0.00602	9.09	0.268
0.83313	1.500	2.360				
ROUTE RESERVOIR	WQPondOut	18	20	0.00345	7.74	0.467
2.53741	1.600	3.504	AC-FT= 0.199			
COMPUTE NM HYD	XD1	-	1	0.00156	3.19	0.103
1.23551	1.500	3.194	PER IMP= 15.00			
COMPUTE NM HYD	XD2	-	2	0.00165	3.40	0.114
1.29606	1.500	3.220	PER IMP= 20.00			
COMPUTE NM HYD	M4	-	3	0.00035	1.07	0.048
2.57457	1.500	4.776	PER IMP= 100.00			
COMPUTE NM HYD	M3	-	4	0.00033	1.02	0.046
2.57457	1.500	4.776	PER IMP= 100.00			
COMPUTE NM HYD	XM2	-	5	0.00105	2.46	0.082
1.45858	1.500	3.658	PER IMP= 22.00			
COMPUTE NM HYD	XM1	-	6	0.00057	1.47	0.055
1.78766	1.500	4.004	PER IMP= 45.00			
COMPUTE NM HYD	M1	-	7	0.00186	4.74	0.184
1.85834	1.500	3.989	PER IMP= 52.00			
COMPUTE NM HYD	M2	-	8	0.00061	1.85	0.083
2.57457	1.500	4.757	PER IMP= 100.00			
ADD HYD	XD1_M4	1& 3	9	0.00191	4.26	0.151
1.48086	1.500	3.484				
ADD HYD	XD2_M3	2& 4	10	0.00198	4.42	0.160
1.51067	1.500	3.482				
ADD HYD	XM2_XD2_M3	5&10	11	0.00303	6.88	0.241
1.49237	1.500	3.543				
ADD HYD	XM2_XD2_M3_X	9&11	12	0.00494	11.14	0.392
1.48792	1.500	3.520				
ADD HYD	M1_XM1	6& 7	13	0.00243	6.20	0.238
1.84144	1.500	3.992				
COMPUTE NM HYD	N	-	14	0.00368	7.23	0.207
1.05739	1.500	3.069	PER IMP= 0.00			
ADD HYD	N_XM2_XD2_M3	12&14	15	0.00862	18.37	0.600
1.30426	1.500	3.328				
ADD HYD	M1_XM1_M2	8&13	16	0.00304	8.05	0.322
1.98804	1.500	4.145				
ADD HYD	woodward	15&16	17	0.01166	26.42	0.922
1.48230	1.500	3.541				
COMPUTE NM HYD	I1	-	18	0.00062	1.89	0.085
2.57457	1.500	4.757	PER IMP= 100.00			
COMPUTE NM HYD	I2	-	19	0.00025	0.76	0.034
2.57457	1.500	4.786	PER IMP= 100.00			
ADD HYD	I2_I1	18&19	20	0.00087	2.65	0.119
2.57402	1.500	4.765				

COMPUTE NM HYD		H2 - 1	0.00054	1.65	0.074
2.57457	1.500	4.762 PER IMP= 100.00			
ADD HYD		H2_I2_I1 20& 1 2	0.00141	4.30	0.194
2.57407	1.500	4.764			
COMPUTE NM HYD		H1 - 3	0.00025	0.78	0.035
2.57457	1.500	4.786 PER IMP= 100.00			
ADD HYD		H1_H2_I2_I1 2& 3 4	0.00166	5.08	0.229
2.57396	1.500	4.767			

↑

		FROM	TO			PEAK	RUNOFF
TIME TO		CFS	PAGE = 2				
		HYDROGRAPH	ID	ID	AREA	DISCHARGE	VOLUME
RUNOFF	PEAK	PER	NO.	NO.	(SQ MI)	(CFS)	(AC-FT)
COMMAND	IDENTIFICATION	NO.	NO.				
(INCHES)	(HOURS)	ACRE	NOTATION				
COMPUTE NM HYD		H - 5	0.00066	2.02	0.091		
2.57457	1.500	4.757 PER IMP= 100.00					
ADD HYD		H_H1_H2_I2_I 4& 5 6	0.00233	7.10	0.320		
2.57405	1.500	4.764					
COMPUTE NM HYD		I - 7	0.00064	1.95	0.088		
2.57457	1.500	4.757 PER IMP= 100.00					
ADD HYD		I_H_H1_H2_I2 6& 7 8	0.00297	9.05	0.408		
2.57410	1.500	4.763					
ADD HYD		DetPondInE 17& 8 21	0.01463	35.47	1.330		
1.70400	1.500	3.789					
COMPUTE NM HYD		P - 9	0.00047	1.43	0.064		
2.57457	1.500	4.768 PER IMP= 100.00					
COMPUTE NM HYD		S - 10	0.00044	1.36	0.061		
2.57457	1.500	4.768 PER IMP= 100.00					
ADD HYD		S_P 9&10 11	0.00091	2.79	0.125		
2.57416	1.500	4.768					
COMPUTE NM HYD		P1 - 12	0.00097	2.86	0.125		
2.43150	1.500	4.624 PER IMP= 90.00					
COMPUTE NM HYD		S1 - 13	0.00058	1.72	0.075		
2.43150	1.500	4.642 PER IMP= 90.00					
ADD HYD		S1_P1 12&13 14	0.00155	4.58	0.200		
2.43119	1.500	4.631					
ADD HYD		S1_P1_S_P 11&14 15	0.00246	7.37	0.326		
2.48428	1.500	4.682					
COMPUTE NM HYD		T - 16	0.00126	3.83	0.173		
2.57457	1.500	4.747 PER IMP= 100.00					
ADD HYD		T_S1_P1_S_P 15&16 17	0.00372	11.20	0.499		
2.51483	1.500	4.704					
COMPUTE NM HYD		Q1 - 18	0.00019	0.58	0.025		
2.43150	1.500	4.705 PER IMP= 90.00					
COMPUTE NM HYD		R1 - 19	0.00030	0.91	0.039		
2.43150	1.500	4.680 PER IMP= 90.00					
ADD HYD		Q1_R1 18&19 20	0.00050	1.49	0.064		
2.42693	1.500	4.690					

COMPUTE NM HYD	Q	-	1	0.00079	2.37	0.104
2.46011 1.500	4.661 PER IMP=	92.00				
COMPUTE NM HYD	R	-	2	0.00058	1.73	0.076
2.43150 1.500	4.642 PER IMP=	90.00				
ADD HYD	Q_R	1& 2	3	0.00138	4.10	0.180
2.44768 1.500	4.653					
ADD HYD	Q_R_Q1_R1	20& 3	4	0.00187	5.59	0.244
2.44217 1.500	4.663					
ADD HYD	broadway	17& 4	5	0.00559	16.79	0.743
2.49050 1.500	4.690					
COMPUTE NM HYD	XC	-	6	0.00440	10.16	0.336
1.42997 1.500	3.608 PER IMP=	20.00				
ADD HYD	broadway	5& 6	7	0.00999	26.95	1.079
2.02344 1.500	4.214					
COMPUTE NM HYD	D	-	8	0.00032	0.97	0.044
2.57457 1.500	4.776 PER IMP=	100.00				
COMPUTE NM HYD	C	-	9	0.00038	1.15	0.052
2.57457 1.500	4.768 PER IMP=	100.00				
ADD HYD	D_C	8& 9	10	0.00070	2.12	0.095
2.57406 1.500	4.772					
ADD HYD	Broadway	7&10	11	0.01069	29.07	1.174
2.05925 1.500	4.250					
COMPUTE NM HYD	G1	-	12	0.00124	3.76	0.170
2.57457 1.500	4.747 PER IMP=	100.00				
COMPUTE NM HYD	G	-	13	0.00107	3.25	0.147
2.57457 1.500	4.750 PER IMP=	100.00				
ADD HYD	G1_G	12&13	14	0.00231	7.01	0.317
2.57435 1.500	4.748					
ADD HYD	DetPondInW	11&14	15	0.01300	36.08	1.491
2.15065 1.500	4.338					
ADD HYD	DetPondInSS	21&15	16	0.02762	71.56	2.820
1.91411 1.500	4.047					
COMPUTE NM HYD	XJ	-	17	0.00755	12.48	0.364
0.90246 1.500	2.581 PER IMP=	0.00				
COMPUTE NM HYD	XJ1	-	18	0.01045	18.34	0.528
0.94796 1.500	2.742 PER IMP=	0.00				
ADD HYD	XJ1_XJ	17&18	19	0.01800	30.82	0.892
0.92886 1.500	2.674					
ADD HYD	DetPondIn	16&19	20	0.04563	102.37	3.712
1.52536 1.500	3.506					
ROUTE RESERVOIR	DetPondOut	20	1	0.04563	4.48	3.712
1.52535 2.300	0.154 AC-FT=	2.946				
COMPUTE NM HYD	XV	-	2	0.00305	8.99	0.396
2.43150 1.500	4.605 PER IMP=	90.00				
COMPUTE NM HYD	A	-	3	0.00089	2.68	0.120
2.54596 1.500	4.732 PER IMP=	98.00				
COMPUTE NM HYD	B	-	4	0.00082	2.49	0.112
2.54596 1.500	4.732 PER IMP=	98.00				
ADD HYD	A_B	3& 4	5	0.00171	5.17	0.232
2.54566 1.500	4.732					

ADD HYD		XV_DetPondOu	1& 2	6	0.04868	10.04	4.106
1.58161	1.550	0.322					
ADD HYD		XV_DetPondOu	5& 6	7	0.05039	15.10	4.338
1.61428	1.500	0.468					
FINISH							

AHYMO PROGRAM (AHYMO-S4)

- Version: S4.01a - Rel: 01a

RUN DATE (MON/DAY/YR) = 07/07/2020

START TIME (HR:MIN:SEC) = 17:52:22

USER NO. =

MolzenCorSingleA36115542

INPUT FILE = C:\Users\Public\AHYMOdata\AHYMO input 7-7-20_MC.txt

*S Sunport Boulevard extension by Jonah Ruybalid NOV 19 2019

*

START TIME=0.0 HR PUNCH CODE=0

*S 100-YEAR, 24-HOUR STORM EVENT- ZONE 2

RAINFALL TYPE=2 QUARTER HR RAIN=0.00 ONE HR RAIN=1.80

SIX HR RAIN=2.24 DAILY RAIN=2.59 DT=0.05 HR

24-HOUR RAINFALL DIST. - BASED ON NOAA ATLAS 14 FOR CONVECTIVE

AREAS (NM & AZ) - D1

DT = 0.050000 HOURS END TIME = 24.000002 HOURS

0.0000	0.0029	0.0060	0.0092	0.0127	0.0163	0.0204
0.0262	0.0352	0.0450	0.0551	0.0661	0.0773	0.0888
0.1007	0.1128	0.1263	0.1404	0.1556	0.1780	0.2040
0.2389	0.2784	0.3272	0.3923	0.4656	0.5921	0.7888
1.1258	1.3627	1.5495	1.6433	1.7256	1.7847	1.8318
1.8728	1.9028	1.9303	1.9531	1.9702	1.9844	1.9972
2.0092	2.0197	2.0297	2.0395	2.0488	2.0565	2.0610
2.0653	2.0696	2.0735	2.0775	2.0813	2.0851	2.0889
2.0924	2.0959	2.0993	2.1026	2.1060	2.1091	2.1122
2.1153	2.1184	2.1214	2.1242	2.1271	2.1299	2.1326
2.1354	2.1380	2.1407	2.1433	2.1459	2.1485	2.1510
2.1535	2.1560	2.1584	2.1608	2.1632	2.1656	2.1679
2.1702	2.1725	2.1747	2.1770	2.1792	2.1814	2.1835
2.1857	2.1878	2.1899	2.1920	2.1940	2.1961	2.1981
2.2001	2.2021	2.2040	2.2060	2.2079	2.2098	2.2117
2.2136	2.2155	2.2173	2.2191	2.2210	2.2228	2.2245
2.2263	2.2281	2.2298	2.2316	2.2333	2.2350	2.2367
2.2383	2.2400	2.2417	2.2433	2.2450	2.2466	2.2483
2.2499	2.2516	2.2532	2.2548	2.2565	2.2581	2.2597
2.2613	2.2629	2.2646	2.2662	2.2678	2.2694	2.2710
2.2726	2.2741	2.2757	2.2773	2.2789	2.2805	2.2820
2.2836	2.2852	2.2867	2.2883	2.2898	2.2914	2.2929
2.2945	2.2960	2.2975	2.2991	2.3006	2.3021	2.3036
2.3051	2.3066	2.3081	2.3096	2.3111	2.3126	2.3141
2.3156	2.3171	2.3186	2.3200	2.3215	2.3230	2.3244
2.3259	2.3274	2.3288	2.3303	2.3317	2.3331	2.3346
2.3360	2.3374	2.3389	2.3403	2.3417	2.3431	2.3445
2.3459	2.3473	2.3487	2.3501	2.3515	2.3529	2.3543
2.3557	2.3570	2.3584	2.3598	2.3611	2.3625	2.3639
2.3652	2.3666	2.3679	2.3692	2.3706	2.3719	2.3732
2.3746	2.3759	2.3772	2.3785	2.3798	2.3811	2.3824
2.3837	2.3850	2.3863	2.3876	2.3889	2.3902	2.3914

2.3927	2.3940	2.3952	2.3965	2.3978	2.3990	2.4003
2.4015	2.4027	2.4040	2.4052	2.4064	2.4077	2.4089
2.4101	2.4113	2.4125	2.4137	2.4149	2.4161	2.4173
2.4185	2.4197	2.4209	2.4221	2.4232	2.4244	2.4256
2.4267	2.4279	2.4290	2.4302	2.4313	2.4325	2.4336
2.4348	2.4359	2.4370	2.4381	2.4393	2.4404	2.4415
2.4426	2.4437	2.4448	2.4459	2.4470	2.4481	2.4492
2.4503	2.4513	2.4524	2.4535	2.4545	2.4556	2.4567
2.4577	2.4588	2.4598	2.4609	2.4619	2.4629	2.4640
2.4650	2.4660	2.4670	2.4680	2.4691	2.4701	2.4711
2.4721	2.4731	2.4740	2.4750	2.4760	2.4770	2.4780
2.4789	2.4799	2.4809	2.4818	2.4828	2.4838	2.4847
2.4856	2.4866	2.4875	2.4885	2.4894	2.4903	2.4912
2.4922	2.4931	2.4940	2.4949	2.4958	2.4967	2.4976
2.4985	2.4994	2.5002	2.5011	2.5020	2.5029	2.5037
2.5046	2.5055	2.5063	2.5072	2.5080	2.5088	2.5097
2.5105	2.5114	2.5122	2.5130	2.5138	2.5146	2.5155
2.5163	2.5171	2.5179	2.5187	2.5195	2.5202	2.5210
2.5218	2.5226	2.5234	2.5241	2.5249	2.5257	2.5264
2.5272	2.5279	2.5287	2.5294	2.5301	2.5309	2.5316
2.5323	2.5331	2.5338	2.5345	2.5352	2.5359	2.5366
2.5373	2.5380	2.5387	2.5394	2.5401	2.5408	2.5414
2.5421	2.5428	2.5434	2.5441	2.5447	2.5454	2.5460
2.5467	2.5473	2.5480	2.5486	2.5492	2.5499	2.5505
2.5511	2.5517	2.5523	2.5529	2.5535	2.5541	2.5547
2.5553	2.5559	2.5565	2.5570	2.5576	2.5582	2.5588
2.5593	2.5599	2.5604	2.5610	2.5615	2.5621	2.5626
2.5631	2.5637	2.5642	2.5647	2.5652	2.5658	2.5663
2.5668	2.5673	2.5678	2.5683	2.5688	2.5692	2.5697
2.5702	2.5707	2.5712	2.5716	2.5721	2.5725	2.5730
2.5735	2.5739	2.5743	2.5748	2.5752	2.5757	2.5761
2.5765	2.5769	2.5773	2.5778	2.5782	2.5786	2.5790
2.5794	2.5798	2.5802	2.5805	2.5809	2.5813	2.5817
2.5820	2.5824	2.5828	2.5831	2.5835	2.5838	2.5842
2.5845	2.5849	2.5852	2.5855	2.5858	2.5862	2.5865
2.5868	2.5871	2.5874	2.5877	2.5880	2.5883	2.5886
2.5889	2.5892	2.5895	2.5897	2.5900		

* 10-YEAR, 24-HOUR STORM EVENT, - ZONE 2

*RAINFALL TYPE=2 QUARTER HR RAIN=0.00 ONE HR RAIN=1.14

* SIX HR RAIN=1.47 DAILY RAIN=1.76 DT=0.05 HR

*

↑

 SEDIMENT BULK CODE = 1 BULK FACTOR = 1.10

↑

 *PROPOSED SITE CONDITIONS

*

COMPUTE NM HYD ID=1 HYD=XF DA=0.003794

A B C D 30 40 20 10
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428
UNIT PEAK = 1.4979 CFS UNIT VOLUME = 0.9928 B = 526.28
P60 = 1.8000
AREA = 0.000379 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

K = 0.137266HR TP = 0.133300HR K/TP RATIO = 1.029753 SHAPE
CONSTANT, N = 3.427819
UNIT PEAK = 8.0698 CFS UNIT VOLUME = 0.9988 B = 315.03
P60 = 1.8000
AREA = 0.003415 SQ MI IA = 0.51667 INCHES INF = 1.29667
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=1 CODE=1

HYDROGRAPH FROM AREA XF

RUNOFF VOLUME = 1.03092 INCHES = 0.2086 ACRE-FEET
PEAK DISCHARGE RATE = 6.50 CFS AT 1.500 HOURS BASIN AREA =
0.0038 SQ. MI.

*

COMPUTE NM HYD ID=2 HYD=XE1 DA=0.0.0004978
A B C D 0 0 85 15
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428
UNIT PEAK = 0.29480E-01CFS UNIT VOLUME = 0.8994 B = 526.28
P60 = 1.8000
AREA = 0.000007 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

K = 0.105077HR TP = 0.133300HR K/TP RATIO = 0.788276 SHAPE
 CONSTANT, N = 4.552748
 UNIT PEAK = 0.12395 CFS UNIT VOLUME = 0.9079 B = 390.48
 P60 = 1.8000
 AREA = 0.000042 SQ MI IA = 0.35000 INCHES INF = 0.83000
 INCHES PER HOUR
 RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
 0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=2 CODE=1

HYDROGRAPH FROM AREA XE1

RUNOFF VOLUME = 1.35843 INCHES = 0.0036 ACRE-FEET
 PEAK DISCHARGE RATE = 0.12 CFS AT 1.500 HOURS BASIN AREA =
 0.0000 SQ. MI.

*

COMPUTE NM HYD ID=3 HYD=XE2 DA=0.0.0002535
 A B C D 0 0 80 20
 TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
 CONSTANT, N = 7.106428
 UNIT PEAK = 0.20017E-01CFS UNIT VOLUME = 0.8994 B = 526.28
 P60 = 1.8000
 AREA = 0.000005 SQ MI IA = 0.10000 INCHES INF = 0.04000
 INCHES PER HOUR
 RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
 0.050000

K = 0.105077HR TP = 0.133300HR K/TP RATIO = 0.788276 SHAPE
 CONSTANT, N = 4.552748
 UNIT PEAK = 0.59407E-01CFS UNIT VOLUME = 0.8918 B = 390.48
 P60 = 1.8000
 AREA = 0.000020 SQ MI IA = 0.35000 INCHES INF = 0.83000
 INCHES PER HOUR
 RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
 0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=3 CODE=1

HYDROGRAPH FROM AREA XE2

RUNOFF VOLUME = 1.42997 INCHES = 0.0019 ACRE-FEET
PEAK DISCHARGE RATE = 0.07 CFS AT 1.500 HOURS BASIN AREA =
0.0000 SQ. MI.

*

*Add basins XF and XE2 basin-routing

ADD HYD ID=4 HYD=XF_XE2 ID=1 ID=3

PRINT HYD ID=4 CODE=1

HYDROGRAPH FROM AREA XF_XE2

RUNOFF VOLUME = 1.03277 INCHES = 0.2104 ACRE-FEET
PEAK DISCHARGE RATE = 6.57 CFS AT 1.500 HOURS BASIN AREA =
0.0038 SQ. MI.

*

COMPUTE NM HYD ID=5 HYD=XE3 DA=0.003694
A B C D 86 0 14 0
TP=0.13330 MASS RAIN=-1

K = 0.156997HR TP = 0.133300HR K/TP RATIO = 1.177768 SHAPE
CONSTANT, N = 3.012561

UNIT PEAK = 7.8383 CFS UNIT VOLUME = 0.9972 B = 282.85
P60 = 1.8000

AREA = 0.003694 SQ MI IA = 0.60800 INCHES INF = 1.55240
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=5 CODE=1

HYDROGRAPH FROM AREA XE3

RUNOFF VOLUME = 0.72397 INCHES = 0.1426 ACRE-FEET

PEAK DISCHARGE RATE = 4.73 CFS AT 1.550 HOURS BASIN AREA =
0.0037 SQ. MI.

*

COMPUTE NM HYD ID=6 HYD=XD3 DA=0.0017353
A B C D 0 40 50 10
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428
UNIT PEAK = 0.68511 CFS UNIT VOLUME = 0.9832 B = 526.28
P60 = 1.8000
AREA = 0.000174 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

K = 0.117142HR TP = 0.133300HR K/TP RATIO = 0.878787 SHAPE
CONSTANT, N = 4.039515
UNIT PEAK = 4.1920 CFS UNIT VOLUME = 0.9983 B = 357.80
P60 = 1.8000
AREA = 0.001562 SQ MI IA = 0.41667 INCHES INF = 1.01667
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=6 CODE=1

HYDROGRAPH FROM AREA XD3

RUNOFF VOLUME = 1.17561 INCHES = 0.1088 ACRE-FEET
PEAK DISCHARGE RATE = 3.51 CFS AT 1.500 HOURS BASIN AREA =
0.0017 SQ. MI.

*

COMPUTE NM HYD ID=7 HYD=XD4 DA=0.00021196
A B C D 0 0 70 30
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428

UNIT PEAK = 0.25105 CFS UNIT VOLUME = 0.9593 B = 526.28
P60 = 1.8000
AREA = 0.000064 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

K = 0.105077HR TP = 0.133300HR K/TP RATIO = 0.788276 SHAPE
CONSTANT, N = 4.552748
UNIT PEAK = 0.43463 CFS UNIT VOLUME = 0.9753 B = 390.48
P60 = 1.8000
AREA = 0.000148 SQ MI IA = 0.35000 INCHES INF = 0.83000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=7 CODE=1

HYDROGRAPH FROM AREA XD4

RUNOFF VOLUME = 1.57304 INCHES = 0.0178 ACRE-FEET
PEAK DISCHARGE RATE = 0.52 CFS AT 1.500 HOURS BASIN AREA =
0.0002 SQ. MI.

*

*Add basins XD3 and XD4 basin-routing
ADD HYD ID=8 HYD=XD3_XD4 ID=6 ID=7
PRINT HYD ID=8 CODE=1

HYDROGRAPH FROM AREA XD3_XD4

RUNOFF VOLUME = 1.21237 INCHES = 0.1259 ACRE-FEET
PEAK DISCHARGE RATE = 4.03 CFS AT 1.500 HOURS BASIN AREA =
0.0019 SQ. MI.

*

*Add basins XD3, XD4, XE2, XF basin-routing
ADD HYD ID=9 HYD=XD3_XD4_XE2_XF ID=4 ID=8
PRINT HYD ID=9 CODE=1

HYDROGRAPH FROM AREA XD3_XD4_XE2_XF

RUNOFF VOLUME = 1.09342 INCHES = 0.3363 ACRE-FEET
 PEAK DISCHARGE RATE = 10.60 CFS AT 1.500 HOURS BASIN AREA =
 0.0058 SQ. MI.

*

COMPUTE NM HYD ID=10 HYD=XD5 DA=0.002328
 A B C D 0 50 50 0
 TP=0.13330 MASS RAIN=-1

K = 0.118650HR TP = 0.133300HR K/TP RATIO = 0.890100 SHAPE
 CONSTANT, N = 3.984395
 UNIT PEAK = 6.1847 CFS UNIT VOLUME = 0.9990 B = 354.13
 P60 = 1.8000
 AREA = 0.002328 SQ MI IA = 0.42500 INCHES INF = 1.04000
 INCHES PER HOUR
 RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
 0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=10 CODE=1

HYDROGRAPH FROM AREA XD5

RUNOFF VOLUME = 1.00639 INCHES = 0.1250 ACRE-FEET
 PEAK DISCHARGE RATE = 4.36 CFS AT 1.500 HOURS BASIN AREA =
 0.0023 SQ. MI.

*

COMPUTE NM HYD ID=11 HYD=H3 DA=0.000283628
 A B C D 0 0 0 100
 TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
 CONSTANT, N = 7.106428
 UNIT PEAK = 1.1198 CFS UNIT VOLUME = 0.9891 B = 526.28
 P60 = 1.8000
 AREA = 0.000284 SQ MI IA = 0.10000 INCHES INF = 0.04000
 INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=11 CODE=1

HYDROGRAPH FROM AREA H3

RUNOFF VOLUME = 2.57457 INCHES = 0.0389 ACRE-FEET
PEAK DISCHARGE RATE = 0.87 CFS AT 1.500 HOURS BASIN AREA =
0.0003 SQ. MI.

*

COMPUTE NM HYD ID=12 HYD=H4 DA=0.0012214
A B C D 0 0 0 100
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428

UNIT PEAK = 4.8222 CFS UNIT VOLUME = 0.9971 B = 526.28
P60 = 1.8000

AREA = 0.001221 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=12 CODE=1

HYDROGRAPH FROM AREA H4

RUNOFF VOLUME = 2.57457 INCHES = 0.1677 ACRE-FEET
PEAK DISCHARGE RATE = 3.71 CFS AT 1.500 HOURS BASIN AREA =
0.0012 SQ. MI.

*

*Add basins H3 and H4 basin-routing

ADD HYD ID=13 HYD=H3_H4 ID=11 ID=12

PRINT HYD ID=13 CODE=1

HYDROGRAPH FROM AREA H3_H4

RUNOFF VOLUME = 2.57427 INCHES = 0.2066 ACRE-FEET
 PEAK DISCHARGE RATE = 4.58 CFS AT 1.500 HOURS BASIN AREA =
 0.0015 SQ. MI.

*

COMPUTE NM HYD ID=14 HYD=I3 DA=0.0013089
 A B C D 0 0 0 100
 TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
 CONSTANT, N = 7.106428

UNIT PEAK = 5.1676 CFS UNIT VOLUME = 0.9971 B = 526.28
 P60 = 1.8000

AREA = 0.001309 SQ MI IA = 0.10000 INCHES INF = 0.04000
 INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
 0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=14 CODE=1

HYDROGRAPH FROM AREA I3

RUNOFF VOLUME = 2.57457 INCHES = 0.1797 ACRE-FEET
 PEAK DISCHARGE RATE = 3.98 CFS AT 1.500 HOURS BASIN AREA =
 0.0013 SQ. MI.

*

*Add basins I3 H3 H4 basin-routing

ADD HYD ID=15 HYD=I3_H3_H4 ID=13 ID=14

PRINT HYD ID=15 CODE=1

HYDROGRAPH FROM AREA I3_H3_H4

RUNOFF VOLUME = 2.57430 INCHES = 0.3863 ACRE-FEET
 PEAK DISCHARGE RATE = 8.56 CFS AT 1.500 HOURS BASIN AREA =
 0.0028 SQ. MI.

*

COMPUTE NM HYD ID=16 HYD=I4 DA=0.000589138
A B C D 0 0 0 100
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428
UNIT PEAK = 2.3259 CFS UNIT VOLUME = 0.9941 B = 526.28
P60 = 1.8000
AREA = 0.000589 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=16 CODE=1

HYDROGRAPH FROM AREA I4

RUNOFF VOLUME = 2.57457 INCHES = 0.0809 ACRE-FEET
PEAK DISCHARGE RATE = 1.80 CFS AT 1.500 HOURS BASIN AREA =
0.0006 SQ. MI.

*

*Add basins I4 I3 H3 H4 basin-routing

ADD HYD ID=17 HYD=WQPondInS(I4_I3_H3_H4) ID=15 ID=16
PRINT HYD ID=17 CODE=1

HYDROGRAPH FROM AREA

WQPondInS(I4_I3_H3_H4

RUNOFF VOLUME = 2.57428 INCHES = 0.4672 ACRE-FEET
PEAK DISCHARGE RATE = 10.35 CFS AT 1.500 HOURS BASIN AREA =
0.0034 SQ. MI.

*

*Add basins I4 I3 H3 H4 XE1 basin-routing WQPondIn

ADD HYD ID=18 HYD=I4_I3_H3_H4_XE1 ID=2 ID=17
PRINT HYD ID=18 CODE=1

HYDROGRAPH FROM AREA I4_I3_H3_H4_XE1

RUNOFF VOLUME = 2.55558 INCHES = 0.4706 ACRE-FEET
 PEAK DISCHARGE RATE = 10.48 CFS AT 1.500 HOURS BASIN AREA =
 0.0035 SQ. MI.

*

*Add basins XE2 and XD5 basin-routing SDC in overland

ADD HYD ID=19 HYD=XE2_XD5 ID=5 ID=10

PRINT HYD ID=19 CODE=1

HYDROGRAPH FROM AREA XE2_XD5

RUNOFF VOLUME = 0.83313 INCHES = 0.2676 ACRE-FEET
 PEAK DISCHARGE RATE = 9.09 CFS AT 1.500 HOURS BASIN AREA =
 0.0060 SQ. MI.

*

* Water Quality Pond outflows over weir to south diversion channel

ROUTE RESERVOIR	ID=20	HYD=WQPondOut	INFLOW ID=18	CODE=5
	OUTFLOW(cfs)	STORAGE(ac ft)	ELEV(ft)	
	0.000	0.0	5000.4	
	0.010	0.0336	5001.0	
	0.010	0.1012	5002.0	
	1.700	0.1879	5003.0	
	61.200	0.2954	5004.0	
	224.200	0.5023	5005.0	
	502.900	0.7324	5006.0	
	912.800	0.9827	5007.0	
	1000.000	10.0000	5008.0	

* * * * *

TIME (HRS)	INFLOW (CFS)	ELEV (FEET)	VOLUME (AC-FT)	OUTFLOW (CFS)
0.00	0.00	5000.40	0.000	0.00
0.25	0.00	5000.40	0.000	0.00
0.50	0.00	5000.40	0.000	0.00
0.75	0.02	5000.40	0.000	0.00
1.00	0.64	5000.53	0.007	0.00

1.25	2.10	5000.99	0.033	0.01
1.50	10.48	5002.49	0.144	0.84
1.75	3.85	5003.04	0.193	4.27
2.00	1.54	5003.00	0.188	1.70
2.25	0.67	5002.86	0.176	1.46
2.50	0.28	5002.67	0.159	1.14
2.75	0.12	5002.48	0.143	0.82
3.00	0.08	5002.34	0.130	0.58
3.25	0.06	5002.24	0.122	0.41
3.50	0.05	5002.17	0.116	0.29
3.75	0.05	5002.12	0.112	0.21
4.00	0.05	5002.09	0.109	0.16
4.25	0.05	5002.07	0.107	0.13
4.50	0.06	5002.05	0.106	0.10
4.75	0.06	5002.05	0.105	0.09
5.00	0.06	5002.04	0.105	0.08
5.25	0.07	5002.04	0.104	0.07
5.50	0.07	5002.04	0.104	0.07
5.75	0.07	5002.04	0.104	0.07
6.00	0.08	5002.04	0.104	0.07
6.25	0.08	5002.04	0.105	0.08
6.50	0.08	5002.04	0.105	0.08
6.75	0.08	5002.04	0.105	0.08
7.00	0.08	5002.04	0.105	0.08
7.25	0.08	5002.04	0.105	0.08
7.50	0.08	5002.04	0.105	0.08
7.75	0.08	5002.04	0.105	0.08
8.00	0.07	5002.04	0.105	0.08
8.25	0.07	5002.04	0.105	0.07
8.50	0.07	5002.04	0.104	0.07
8.75	0.07	5002.04	0.104	0.07
9.00	0.07	5002.04	0.104	0.07
9.25	0.07	5002.04	0.104	0.07
9.50	0.07	5002.04	0.104	0.07
9.75	0.07	5002.04	0.104	0.07
10.00	0.07	5002.03	0.104	0.07
10.25	0.07	5002.03	0.104	0.07
10.50	0.06	5002.03	0.104	0.07
10.75	0.06	5002.03	0.104	0.07
11.00	0.06	5002.03	0.104	0.06
11.25	0.06	5002.03	0.104	0.06
11.50	0.06	5002.03	0.104	0.06
11.75	0.06	5002.03	0.104	0.06
12.00	0.06	5002.03	0.104	0.06
12.25	0.06	5002.03	0.104	0.06
12.50	0.06	5002.03	0.104	0.06
12.75	0.06	5002.03	0.104	0.06
13.00	0.06	5002.03	0.104	0.06
13.25	0.05	5002.03	0.104	0.06
13.50	0.05	5002.03	0.104	0.06

13.75	0.05	5002.03	0.103	0.05
TIME (HRS)	INFLOW (CFS)	ELEV (FEET)	VOLUME (AC-FT)	OUTFLOW (CFS)
14.00	0.05	5002.03	0.103	0.05
14.25	0.05	5002.03	0.103	0.05
14.50	0.05	5002.02	0.103	0.05
14.75	0.05	5002.02	0.103	0.05
15.00	0.05	5002.02	0.103	0.05
15.25	0.05	5002.02	0.103	0.05
15.50	0.05	5002.02	0.103	0.05
15.75	0.04	5002.02	0.103	0.05
16.00	0.04	5002.02	0.103	0.05
16.25	0.04	5002.02	0.103	0.05
16.50	0.04	5002.02	0.103	0.04
16.75	0.04	5002.02	0.103	0.04
17.00	0.04	5002.02	0.103	0.04
17.25	0.04	5002.02	0.103	0.04
17.50	0.04	5002.02	0.103	0.04
17.75	0.04	5002.02	0.103	0.04
18.00	0.04	5002.02	0.103	0.04
18.25	0.04	5002.02	0.103	0.04
18.50	0.03	5002.02	0.103	0.04
18.75	0.03	5002.02	0.103	0.04
19.00	0.03	5002.01	0.102	0.03
19.25	0.03	5002.01	0.102	0.03
19.50	0.03	5002.01	0.102	0.03
19.75	0.03	5002.01	0.102	0.03
20.00	0.03	5002.01	0.102	0.03
20.25	0.03	5002.01	0.102	0.03
20.50	0.03	5002.01	0.102	0.03
20.75	0.03	5002.01	0.102	0.03
21.00	0.03	5002.01	0.102	0.03
21.25	0.02	5002.01	0.102	0.03
21.50	0.02	5002.01	0.102	0.03
21.75	0.02	5002.01	0.102	0.02
22.00	0.02	5002.01	0.102	0.02
22.25	0.02	5002.01	0.102	0.02
22.50	0.02	5002.01	0.102	0.02
22.75	0.02	5002.01	0.102	0.02
23.00	0.02	5002.01	0.102	0.02
23.25	0.02	5002.01	0.102	0.02
23.50	0.02	5002.00	0.102	0.02
23.75	0.01	5002.00	0.102	0.02
24.00	0.01	5002.00	0.102	0.02
24.25	0.00	5002.00	0.101	0.01
24.50	0.00	5002.00	0.101	0.01
24.75	0.00	5002.00	0.101	0.01
25.00	0.00	5002.00	0.101	0.01

25.25	0.00	5002.00	0.101	0.01
25.50	0.00	5002.00	0.101	0.01
25.75	0.00	5002.00	0.101	0.01
26.00	0.00	5002.00	0.101	0.01
26.25	0.00	5002.00	0.101	0.01
26.50	0.00	5002.00	0.101	0.01
26.75	0.00	5002.00	0.101	0.01
27.00	0.00	5002.00	0.101	0.01
27.25	0.00	5002.00	0.101	0.01
27.50	0.00	5002.00	0.101	0.01
27.75	0.00	5002.00	0.101	0.01

TIME (HRS)	INFLOW (CFS)	ELEV (FEET)	VOLUME (AC-FT)	OUTFLOW (CFS)
---------------	-----------------	----------------	-------------------	------------------

28.00	0.00	5002.00	0.101	0.01
28.25	0.00	5002.00	0.101	0.01
28.50	0.00	5002.00	0.101	0.01
28.75	0.00	5002.00	0.101	0.01
29.00	0.00	5002.00	0.101	0.01
29.25	0.00	5002.00	0.101	0.01
29.50	0.00	5002.00	0.101	0.01
29.75	0.00	5002.00	0.101	0.01
30.00	0.00	5002.00	0.101	0.01
30.25	0.00	5002.00	0.101	0.01
30.50	0.00	5002.00	0.101	0.01
30.75	0.00	5002.00	0.101	0.01
31.00	0.00	5002.00	0.101	0.01
31.25	0.00	5002.00	0.101	0.01
31.50	0.00	5002.00	0.101	0.01
31.75	0.00	5002.00	0.101	0.01
32.00	0.00	5002.00	0.101	0.01
32.25	0.00	5002.00	0.101	0.01
32.50	0.00	5002.00	0.101	0.01
32.75	0.00	5002.00	0.101	0.01
33.00	0.00	5002.00	0.101	0.01
33.25	0.00	5002.00	0.101	0.01
33.50	0.00	5002.00	0.101	0.01
33.75	0.00	5002.00	0.101	0.01
34.00	0.00	5002.00	0.101	0.01
34.25	0.00	5002.00	0.101	0.01
34.50	0.00	5002.00	0.101	0.01
34.75	0.00	5002.00	0.101	0.01
35.00	0.00	5002.00	0.101	0.01
35.25	0.00	5002.00	0.101	0.01
35.50	0.00	5002.00	0.101	0.01
35.75	0.00	5002.00	0.101	0.01
36.00	0.00	5002.00	0.101	0.01
36.25	0.00	5002.00	0.101	0.01
36.50	0.00	5002.00	0.101	0.01

36.75	0.00	5002.00	0.101	0.01
37.00	0.00	5002.00	0.101	0.01
37.25	0.00	5002.00	0.101	0.01
37.50	0.00	5002.00	0.101	0.01
37.75	0.00	5002.00	0.101	0.01
38.00	0.00	5002.00	0.101	0.01
38.25	0.00	5002.00	0.101	0.01
38.50	0.00	5002.00	0.101	0.01
38.75	0.00	5002.00	0.101	0.01
39.00	0.00	5002.00	0.101	0.01
39.25	0.00	5002.00	0.101	0.01
39.50	0.00	5002.00	0.101	0.01
39.75	0.00	5002.00	0.101	0.01
40.00	0.00	5002.00	0.101	0.01
40.25	0.00	5002.00	0.101	0.01
40.50	0.00	5002.00	0.101	0.01
40.75	0.00	5002.00	0.101	0.01
41.00	0.00	5002.00	0.101	0.01
41.25	0.00	5002.00	0.101	0.01
41.50	0.00	5002.00	0.101	0.01
41.75	0.00	5002.00	0.101	0.01

TIME (HRS)	INFLOW (CFS)	ELEV (FEET)	VOLUME (AC-FT)	OUTFLOW (CFS)
42.00	0.00	5002.00	0.101	0.01
42.25	0.00	5002.00	0.101	0.01
42.50	0.00	5002.00	0.101	0.01
42.75	0.00	5002.00	0.101	0.01
43.00	0.00	5002.00	0.101	0.01
43.25	0.00	5002.00	0.101	0.01
43.50	0.00	5002.00	0.101	0.01
43.75	0.00	5002.00	0.101	0.01
44.00	0.00	5002.00	0.101	0.01
44.25	0.00	5002.00	0.101	0.01
44.50	0.00	5002.00	0.101	0.01
44.75	0.00	5002.00	0.101	0.01
45.00	0.00	5002.00	0.101	0.01
45.25	0.00	5002.00	0.101	0.01
45.50	0.00	5002.00	0.101	0.01
45.75	0.00	5002.00	0.101	0.01
46.00	0.00	5002.00	0.101	0.01
46.25	0.00	5002.00	0.101	0.01
46.50	0.00	5002.00	0.101	0.01
46.75	0.00	5002.00	0.101	0.01
47.00	0.00	5002.00	0.101	0.01
47.25	0.00	5002.00	0.101	0.01
47.50	0.00	5002.00	0.101	0.01
47.75	0.00	5002.00	0.101	0.01
48.00	0.00	5002.00	0.101	0.01

48.25	0.00	5002.00	0.101	0.01
48.50	0.00	5002.00	0.101	0.01
48.75	0.00	5002.00	0.101	0.01
49.00	0.00	5002.00	0.101	0.01
49.25	0.00	5002.00	0.101	0.01
49.50	0.00	5002.00	0.101	0.01
49.75	0.00	5002.00	0.101	0.01
50.00	0.00	5002.00	0.101	0.01
50.25	0.00	5002.00	0.101	0.01
50.50	0.00	5002.00	0.101	0.01
50.75	0.00	5002.00	0.101	0.01
51.00	0.00	5002.00	0.101	0.01
51.25	0.00	5002.00	0.101	0.01
51.50	0.00	5002.00	0.101	0.01
51.75	0.00	5002.00	0.101	0.01
52.00	0.00	5002.00	0.101	0.01
52.25	0.00	5002.00	0.101	0.01
52.50	0.00	5002.00	0.101	0.01
52.75	0.00	5002.00	0.101	0.01
53.00	0.00	5002.00	0.101	0.01
53.25	0.00	5002.00	0.101	0.01
53.50	0.00	5002.00	0.101	0.01
53.75	0.00	5002.00	0.101	0.01
54.00	0.00	5002.00	0.101	0.01
54.25	0.00	5002.00	0.101	0.01
54.50	0.00	5002.00	0.101	0.01
54.75	0.00	5002.00	0.101	0.01
55.00	0.00	5002.00	0.101	0.01
55.25	0.00	5002.00	0.101	0.01
55.50	0.00	5002.00	0.101	0.01
55.75	0.00	5002.00	0.101	0.01

TIME (HRS)	INFLOW (CFS)	ELEV (FEET)	VOLUME (AC-FT)	OUTFLOW (CFS)
---------------	-----------------	----------------	-------------------	------------------

56.00	0.00	5002.00	0.101	0.01
56.25	0.00	5002.00	0.101	0.01
56.50	0.00	5002.00	0.101	0.01
56.75	0.00	5002.00	0.101	0.01
57.00	0.00	5002.00	0.101	0.01
57.25	0.00	5002.00	0.101	0.01
57.50	0.00	5002.00	0.101	0.01
57.75	0.00	5002.00	0.101	0.01
58.00	0.00	5002.00	0.101	0.01
58.25	0.00	5002.00	0.101	0.01
58.50	0.00	5002.00	0.101	0.01
58.75	0.00	5002.00	0.101	0.01
59.00	0.00	5002.00	0.101	0.01
59.25	0.00	5002.00	0.101	0.01
59.50	0.00	5002.00	0.101	0.01

59.75	0.00	5002.00	0.101	0.01
60.00	0.00	5002.00	0.101	0.01
60.25	0.00	5002.00	0.101	0.01
60.50	0.00	5002.00	0.101	0.01
60.75	0.00	5002.00	0.101	0.01
61.00	0.00	5002.00	0.101	0.01
61.25	0.00	5002.00	0.101	0.01
61.50	0.00	5002.00	0.101	0.01
61.75	0.00	5002.00	0.101	0.01
62.00	0.00	5002.00	0.101	0.01
62.25	0.00	5002.00	0.101	0.01
62.50	0.00	5002.00	0.101	0.01
62.75	0.00	5002.00	0.101	0.01
63.00	0.00	5002.00	0.101	0.01
63.25	0.00	5002.00	0.101	0.01
63.50	0.00	5002.00	0.101	0.01
63.75	0.00	5002.00	0.101	0.01
64.00	0.00	5002.00	0.101	0.01
64.25	0.00	5002.00	0.101	0.01
64.50	0.00	5002.00	0.101	0.01
64.75	0.00	5002.00	0.101	0.01
65.00	0.00	5002.00	0.101	0.01
65.25	0.00	5002.00	0.101	0.01
65.50	0.00	5002.00	0.101	0.01
65.75	0.00	5002.00	0.101	0.01
66.00	0.00	5002.00	0.101	0.01
66.25	0.00	5002.00	0.101	0.01
66.50	0.00	5002.00	0.101	0.01
66.75	0.00	5002.00	0.101	0.01
67.00	0.00	5002.00	0.101	0.01
67.25	0.00	5002.00	0.101	0.01
67.50	0.00	5002.00	0.101	0.01
67.75	0.00	5002.00	0.101	0.01
68.00	0.00	5002.00	0.101	0.01
68.25	0.00	5002.00	0.101	0.01
68.50	0.00	5002.00	0.101	0.01
68.75	0.00	5002.00	0.101	0.01
69.00	0.00	5002.00	0.101	0.01
69.25	0.00	5002.00	0.101	0.01
69.50	0.00	5002.00	0.101	0.01
69.75	0.00	5002.00	0.101	0.01

TIME (HRS)	INFLOW (CFS)	ELEV (FEET)	VOLUME (AC-FT)	OUTFLOW (CFS)
---------------	-----------------	----------------	-------------------	------------------

70.00	0.00	5002.00	0.101	0.01
70.25	0.00	5002.00	0.101	0.01
70.50	0.00	5002.00	0.101	0.01
70.75	0.00	5002.00	0.101	0.01
71.00	0.00	5002.00	0.101	0.01

71.25	0.00	5002.00	0.101	0.01
71.50	0.00	5002.00	0.101	0.01
71.75	0.00	5002.00	0.101	0.01
72.00	0.00	5002.00	0.101	0.01
72.25	0.00	5002.00	0.101	0.01
72.50	0.00	5002.00	0.101	0.01
72.75	0.00	5002.00	0.101	0.01
73.00	0.00	5002.00	0.101	0.01
73.25	0.00	5002.00	0.101	0.01
73.50	0.00	5002.00	0.101	0.01
73.75	0.00	5002.00	0.101	0.01
74.00	0.00	5002.00	0.101	0.01
74.25	0.00	5002.00	0.101	0.01
74.50	0.00	5002.00	0.101	0.01
74.75	0.00	5002.00	0.101	0.01
75.00	0.00	5002.00	0.101	0.01
75.25	0.00	5002.00	0.101	0.01
75.50	0.00	5002.00	0.101	0.01
75.75	0.00	5002.00	0.101	0.01
76.00	0.00	5002.00	0.101	0.01
76.25	0.00	5002.00	0.101	0.01
76.50	0.00	5002.00	0.101	0.01
76.75	0.00	5002.00	0.101	0.01
77.00	0.00	5002.00	0.101	0.01
77.25	0.00	5002.00	0.101	0.01
77.50	0.00	5002.00	0.101	0.01
77.75	0.00	5002.00	0.101	0.01
78.00	0.00	5002.00	0.101	0.01
78.25	0.00	5002.00	0.101	0.01
78.50	0.00	5002.00	0.101	0.01
78.75	0.00	5002.00	0.101	0.01
79.00	0.00	5002.00	0.101	0.01
79.25	0.00	5002.00	0.101	0.01
79.50	0.00	5002.00	0.101	0.01
79.75	0.00	5002.00	0.101	0.01
80.00	0.00	5002.00	0.101	0.01
80.25	0.00	5002.00	0.101	0.01
80.50	0.00	5002.00	0.101	0.01
80.75	0.00	5002.00	0.101	0.01
81.00	0.00	5002.00	0.101	0.01
81.25	0.00	5002.00	0.101	0.01
81.50	0.00	5002.00	0.101	0.01
81.75	0.00	5002.00	0.101	0.01
82.00	0.00	5002.00	0.101	0.01
82.25	0.00	5002.00	0.101	0.01
82.50	0.00	5002.00	0.101	0.01
82.75	0.00	5002.00	0.101	0.01
83.00	0.00	5002.00	0.101	0.01
83.25	0.00	5002.00	0.101	0.01
83.50	0.00	5002.00	0.101	0.01

83.75	0.00	5002.00	0.101	0.01
-------	------	---------	-------	------

TIME (HRS)	INFLOW (CFS)	ELEV (FEET)	VOLUME (AC-FT)	OUTFLOW (CFS)
---------------	-----------------	----------------	-------------------	------------------

84.00	0.00	5002.00	0.101	0.01
84.25	0.00	5002.00	0.101	0.01
84.50	0.00	5002.00	0.101	0.01
84.75	0.00	5002.00	0.101	0.01
85.00	0.00	5002.00	0.101	0.01
85.25	0.00	5002.00	0.101	0.01
85.50	0.00	5002.00	0.101	0.01
85.75	0.00	5002.00	0.101	0.01
86.00	0.00	5002.00	0.101	0.01
86.25	0.00	5002.00	0.101	0.01
86.50	0.00	5002.00	0.101	0.01
86.75	0.00	5002.00	0.101	0.01
87.00	0.00	5002.00	0.101	0.01
87.25	0.00	5002.00	0.101	0.01
87.50	0.00	5002.00	0.101	0.01
87.75	0.00	5002.00	0.101	0.01
88.00	0.00	5002.00	0.101	0.01
88.25	0.00	5002.00	0.101	0.01
88.50	0.00	5002.00	0.101	0.01
88.75	0.00	5002.00	0.101	0.01
89.00	0.00	5002.00	0.101	0.01
89.25	0.00	5002.00	0.101	0.01
89.50	0.00	5002.00	0.101	0.01
89.75	0.00	5002.00	0.101	0.01
90.00	0.00	5002.00	0.101	0.01
90.25	0.00	5002.00	0.101	0.01
90.50	0.00	5002.00	0.101	0.01
90.75	0.00	5002.00	0.101	0.01
91.00	0.00	5002.00	0.101	0.01
91.25	0.00	5002.00	0.101	0.01
91.50	0.00	5002.00	0.101	0.01
91.75	0.00	5002.00	0.101	0.01
92.00	0.00	5002.00	0.101	0.01
92.25	0.00	5002.00	0.101	0.01
92.50	0.00	5002.00	0.101	0.01
92.75	0.00	5002.00	0.101	0.01
93.00	0.00	5002.00	0.101	0.01
93.25	0.00	5002.00	0.101	0.01
93.50	0.00	5002.00	0.101	0.01
93.75	0.00	5002.00	0.101	0.01
94.00	0.00	5002.00	0.101	0.01
94.25	0.00	5002.00	0.101	0.01
94.50	0.00	5002.00	0.101	0.01
94.75	0.00	5002.00	0.101	0.01
95.00	0.00	5002.00	0.101	0.01

95.25	0.00	5002.00	0.101	0.01
95.50	0.00	5002.00	0.101	0.01
95.75	0.00	5002.00	0.101	0.01
96.00	0.00	5002.00	0.101	0.01
96.25	0.00	5002.00	0.101	0.01
96.50	0.00	5002.00	0.101	0.01
96.75	0.00	5002.00	0.101	0.01
97.00	0.00	5002.00	0.101	0.01
97.25	0.00	5002.00	0.101	0.01
97.50	0.00	5002.00	0.101	0.01
97.75	0.00	5002.00	0.101	0.01

TIME (HRS)	INFLOW (CFS)	ELEV (FEET)	VOLUME (AC-FT)	OUTFLOW (CFS)
98.00	0.00	5002.00	0.101	0.01
98.25	0.00	5002.00	0.101	0.01
98.50	0.00	5002.00	0.101	0.01
98.75	0.00	5002.00	0.101	0.01
99.00	0.00	5002.00	0.101	0.01
99.25	0.00	5002.00	0.101	0.01
99.50	0.00	5002.00	0.101	0.01
99.75	0.00	5002.00	0.101	0.01
100.00	0.00	5002.00	0.101	0.01
100.25	0.00	5002.00	0.101	0.01
100.50	0.00	5002.00	0.101	0.01
100.75	0.00	5002.00	0.101	0.01
101.00	0.00	5002.00	0.101	0.01
101.25	0.00	5002.00	0.101	0.01
101.50	0.00	5002.00	0.101	0.01
101.75	0.00	5002.00	0.101	0.01
102.00	0.00	5002.00	0.101	0.01
102.25	0.00	5002.00	0.101	0.01
102.50	0.00	5002.00	0.101	0.01
102.75	0.00	5002.00	0.101	0.01
103.00	0.00	5002.00	0.101	0.01
103.25	0.00	5002.00	0.101	0.01
103.50	0.00	5002.00	0.101	0.01
103.75	0.00	5002.00	0.101	0.01
104.00	0.00	5002.00	0.101	0.01
104.25	0.00	5002.00	0.101	0.01
104.50	0.00	5002.00	0.101	0.01
104.75	0.00	5002.00	0.101	0.01
105.00	0.00	5002.00	0.101	0.01
105.25	0.00	5002.00	0.101	0.01
105.50	0.00	5002.00	0.101	0.01
105.75	0.00	5002.00	0.101	0.01
106.00	0.00	5002.00	0.101	0.01
106.25	0.00	5001.00	0.034	0.01
106.50	0.00	5001.00	0.033	0.01

106.75	0.00	5000.99	0.033	0.01
107.00	0.00	5000.99	0.033	0.01
107.25	0.00	5000.98	0.033	0.01
107.50	0.00	5000.98	0.033	0.01
107.75	0.00	5000.98	0.032	0.01
108.00	0.00	5000.97	0.032	0.01
108.25	0.00	5000.97	0.032	0.01
108.50	0.00	5000.97	0.032	0.01
108.75	0.00	5000.96	0.032	0.01
109.00	0.00	5000.96	0.031	0.01
109.25	0.00	5000.96	0.031	0.01
109.50	0.00	5000.95	0.031	0.01
109.75	0.00	5000.95	0.031	0.01
110.00	0.00	5000.95	0.031	0.01
110.25	0.00	5000.94	0.030	0.01
110.50	0.00	5000.94	0.030	0.01
110.75	0.00	5000.94	0.030	0.01
111.00	0.00	5000.93	0.030	0.01
111.25	0.00	5000.93	0.030	0.01
111.50	0.00	5000.93	0.029	0.01
111.75	0.00	5000.92	0.029	0.01

TIME (HRS)	INFLOW (CFS)	ELEV (FEET)	VOLUME (AC-FT)	OUTFLOW (CFS)
112.00	0.00	5000.92	0.029	0.01
112.25	0.00	5000.92	0.029	0.01
112.50	0.00	5000.91	0.029	0.01
112.75	0.00	5000.91	0.029	0.01
113.00	0.00	5000.91	0.028	0.01
113.25	0.00	5000.90	0.028	0.01
113.50	0.00	5000.90	0.028	0.01
113.75	0.00	5000.90	0.028	0.01
114.00	0.00	5000.90	0.028	0.01
114.25	0.00	5000.89	0.028	0.01
114.50	0.00	5000.89	0.027	0.01
114.75	0.00	5000.89	0.027	0.01
115.00	0.00	5000.88	0.027	0.01
115.25	0.00	5000.88	0.027	0.01
115.50	0.00	5000.88	0.027	0.01
115.75	0.00	5000.87	0.027	0.01
116.00	0.00	5000.87	0.026	0.01
116.25	0.00	5000.87	0.026	0.01
116.50	0.00	5000.87	0.026	0.01
116.75	0.00	5000.86	0.026	0.01
117.00	0.00	5000.86	0.026	0.01
117.25	0.00	5000.86	0.026	0.01
117.50	0.00	5000.85	0.025	0.01
117.75	0.00	5000.85	0.025	0.01
118.00	0.00	5000.85	0.025	0.01

118.25	0.00	5000.85	0.025	0.01
118.50	0.00	5000.84	0.025	0.01
118.75	0.00	5000.84	0.025	0.01
119.00	0.00	5000.84	0.025	0.01
119.25	0.00	5000.84	0.024	0.01
119.50	0.00	5000.83	0.024	0.01
119.75	0.00	5000.83	0.024	0.01
120.00	0.00	5000.83	0.024	0.01
120.25	0.00	5000.82	0.024	0.01
120.50	0.00	5000.82	0.024	0.01
120.75	0.00	5000.82	0.023	0.01
121.00	0.00	5000.82	0.023	0.01
121.25	0.00	5000.81	0.023	0.01
121.50	0.00	5000.81	0.023	0.01
121.75	0.00	5000.81	0.023	0.01
122.00	0.00	5000.81	0.023	0.01
122.25	0.00	5000.80	0.023	0.01
122.50	0.00	5000.80	0.023	0.01
122.75	0.00	5000.80	0.022	0.01
123.00	0.00	5000.80	0.022	0.01
123.25	0.00	5000.79	0.022	0.01
123.50	0.00	5000.79	0.022	0.01
123.75	0.00	5000.79	0.022	0.01
124.00	0.00	5000.79	0.022	0.01
124.25	0.00	5000.78	0.022	0.01
124.50	0.00	5000.78	0.021	0.01
124.75	0.00	5000.78	0.021	0.01
125.00	0.00	5000.78	0.021	0.01
125.25	0.00	5000.78	0.021	0.01
125.50	0.00	5000.77	0.021	0.01
125.75	0.00	5000.77	0.021	0.01

TIME (HRS)	INFLOW (CFS)	ELEV (FEET)	VOLUME (AC-FT)	OUTFLOW (CFS)
126.00	0.00	5000.77	0.021	0.01
126.25	0.00	5000.77	0.021	0.01
126.50	0.00	5000.76	0.020	0.01
126.75	0.00	5000.76	0.020	0.01
127.00	0.00	5000.76	0.020	0.01
127.25	0.00	5000.76	0.020	0.01
127.50	0.00	5000.76	0.020	0.01
127.75	0.00	5000.75	0.020	0.01
128.00	0.00	5000.75	0.020	0.01
128.25	0.00	5000.75	0.020	0.01
128.50	0.00	5000.75	0.019	0.01
128.75	0.00	5000.74	0.019	0.01
129.00	0.00	5000.74	0.019	0.01
129.25	0.00	5000.74	0.019	0.01
129.50	0.00	5000.74	0.019	0.01

129.75	0.00	5000.74	0.019	0.01
130.00	0.00	5000.73	0.019	0.01
130.25	0.00	5000.73	0.019	0.01
130.50	0.00	5000.73	0.018	0.01
130.75	0.00	5000.73	0.018	0.01
131.00	0.00	5000.73	0.018	0.01
131.25	0.00	5000.72	0.018	0.01
131.50	0.00	5000.72	0.018	0.01
131.75	0.00	5000.72	0.018	0.01
132.00	0.00	5000.72	0.018	0.01
132.25	0.00	5000.72	0.018	0.01
132.50	0.00	5000.71	0.018	0.01
132.75	0.00	5000.71	0.017	0.01
133.00	0.00	5000.71	0.017	0.01
133.25	0.00	5000.71	0.017	0.01
133.50	0.00	5000.71	0.017	0.01
133.75	0.00	5000.70	0.017	0.01
134.00	0.00	5000.70	0.017	0.01
134.25	0.00	5000.70	0.017	0.01
134.50	0.00	5000.70	0.017	0.00

PEAK DISCHARGE = 7.743 CFS - PEAK OCCURS AT HOUR 1.60
 MAXIMUM WATER SURFACE ELEVATION = 5003.102
 MAXIMUM STORAGE = 0.1988 AC-FT INCREMENTAL TIME= 0.050000HRS

*

*

COMPUTE NM HYD ID=1 HYD=XD1 DA=0.0015604
 A B C D 0 45 40 15
 TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
 CONSTANT, N = 7.106428

UNIT PEAK = 0.92408 CFS UNIT VOLUME = 0.9865 B = 526.28
 P60 = 1.8000

AREA = 0.000234 SQ MI IA = 0.10000 INCHES INF = 0.04000
 INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
 0.050000

K = 0.119449HR TP = 0.133300HR K/TP RATIO = 0.896090 SHAPE
 CONSTANT, N = 3.955991

UNIT PEAK = 3.5047 CFS UNIT VOLUME = 0.9976 B = 352.23
 P60 = 1.8000

AREA = 0.001326 SQ MI IA = 0.42941 INCHES INF = 1.05235
 INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
 0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=1 CODE=1

HYDROGRAPH FROM AREA XD1

RUNOFF VOLUME = 1.23551 INCHES = 0.1028 ACRE-FEET
PEAK DISCHARGE RATE = 3.19 CFS AT 1.500 HOURS BASIN AREA =
0.0016 SQ. MI.

*

COMPUTE NM HYD ID=2 HYD=XD2 DA=0.0016502
A B C D 10 30 40 20
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428
UNIT PEAK = 1.3030 CFS UNIT VOLUME = 0.9911 B = 526.28
P60 = 1.8000
AREA = 0.000330 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

K = 0.122804HR TP = 0.133300HR K/TP RATIO = 0.921257 SHAPE
CONSTANT, N = 3.841709
UNIT PEAK = 3.4116 CFS UNIT VOLUME = 0.9974 B = 344.48
P60 = 1.8000
AREA = 0.001320 SQ MI IA = 0.44375 INCHES INF = 1.09250
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=2 CODE=1

HYDROGRAPH FROM AREA XD2

RUNOFF VOLUME = 1.29606 INCHES = 0.1141 ACRE-FEET
PEAK DISCHARGE RATE = 3.40 CFS AT 1.500 HOURS BASIN AREA =
0.0017 SQ. MI.

*

COMPUTE NM HYD ID=3 HYD=M4 DA=0.0003507
A B C D 0 0 0 100
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428
UNIT PEAK = 1.3846 CFS UNIT VOLUME = 0.9911 B = 526.28
P60 = 1.8000
AREA = 0.000351 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=3 CODE=1

HYDROGRAPH FROM AREA M4

RUNOFF VOLUME = 2.57457 INCHES = 0.0482 ACRE-FEET
PEAK DISCHARGE RATE = 1.07 CFS AT 1.500 HOURS BASIN AREA =
0.0004 SQ. MI.

*

COMPUTE NM HYD ID=4 HYD=M3 DA=0.00033327
A B C D 0 0 0 100
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428
UNIT PEAK = 1.3158 CFS UNIT VOLUME = 0.9911 B = 526.28
P60 = 1.8000
AREA = 0.000333 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=4 CODE=1

HYDROGRAPH FROM AREA M3

RUNOFF VOLUME = 2.57457 INCHES = 0.0458 ACRE-FEET
PEAK DISCHARGE RATE = 1.02 CFS AT 1.500 HOURS BASIN AREA =
0.0003 SQ. MI.

*

COMPUTE NM HYD ID=5 HYD=XM2 DA=0.0010503
A B C D 0 0 78 22
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428
UNIT PEAK = 0.91226 CFS UNIT VOLUME = 0.9865 B = 526.28
P60 = 1.8000
AREA = 0.000231 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

K = 0.105077HR TP = 0.133300HR K/TP RATIO = 0.788276 SHAPE
CONSTANT, N = 4.552748
UNIT PEAK = 2.3998 CFS UNIT VOLUME = 0.9962 B = 390.48
P60 = 1.8000
AREA = 0.000819 SQ MI IA = 0.35000 INCHES INF = 0.83000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=5 CODE=1

HYDROGRAPH FROM AREA XM2

RUNOFF VOLUME = 1.45858 INCHES = 0.0817 ACRE-FEET
PEAK DISCHARGE RATE = 2.46 CFS AT 1.500 HOURS BASIN AREA =
0.0011 SQ. MI.

*

COMPUTE NM HYD ID=6 HYD=XM1 DA=0.0005732
A B C D 0 0 55 45
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
 CONSTANT, N = 7.106428
 UNIT PEAK = 1.0184 CFS UNIT VOLUME = 0.9891 B = 526.28
 P60 = 1.8000
 AREA = 0.000258 SQ MI IA = 0.10000 INCHES INF = 0.04000
 INCHES PER HOUR
 RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
 0.050000

K = 0.105077HR TP = 0.133300HR K/TP RATIO = 0.788276 SHAPE
 CONSTANT, N = 4.552748
 UNIT PEAK = 0.92350 CFS UNIT VOLUME = 0.9877 B = 390.48
 P60 = 1.8000
 AREA = 0.000315 SQ MI IA = 0.35000 INCHES INF = 0.83000
 INCHES PER HOUR
 RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
 0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=6 CODE=1

HYDROGRAPH FROM AREA XM1

RUNOFF VOLUME = 1.78766 INCHES = 0.0546 ACRE-FEET
 PEAK DISCHARGE RATE = 1.47 CFS AT 1.500 HOURS BASIN AREA =
 0.0006 SQ. MI.

*

COMPUTE NM HYD ID=7 HYD=M1 DA=0.00185513
 A B C D 0 10 38 52
 TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
 CONSTANT, N = 7.106428
 UNIT PEAK = 3.8086 CFS UNIT VOLUME = 0.9966 B = 526.28
 P60 = 1.8000
 AREA = 0.000965 SQ MI IA = 0.10000 INCHES INF = 0.04000
 INCHES PER HOUR
 RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
 0.050000

K = 0.110733HR TP = 0.133300HR K/TP RATIO = 0.830703 SHAPE

CONSTANT, N = 4.294546

UNIT PEAK = 2.5007 CFS UNIT VOLUME = 0.9969 B = 374.35

P60 = 1.8000

AREA = 0.000890 SQ MI IA = 0.38125 INCHES INF = 0.91750
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=7 CODE=1

HYDROGRAPH FROM AREA M1

RUNOFF VOLUME = 1.85834 INCHES = 0.1839 ACRE-FEET
PEAK DISCHARGE RATE = 4.74 CFS AT 1.500 HOURS BASIN AREA =
0.0019 SQ. MI.

*

COMPUTE NM HYD ID=8 HYD=M2 DA=0.00060728
A B C D 0 0 0 100
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428

UNIT PEAK = 2.3976 CFS UNIT VOLUME = 0.9951 B = 526.28

P60 = 1.8000

AREA = 0.000607 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=8 CODE=1

HYDROGRAPH FROM AREA M2

RUNOFF VOLUME = 2.57457 INCHES = 0.0834 ACRE-FEET
PEAK DISCHARGE RATE = 1.85 CFS AT 1.500 HOURS BASIN AREA =
0.0006 SQ. MI.

*

*Add basins XD1 M4 basin-routing

ADD HYD ID=9 HYD=XD1_M4 ID=1 ID=3

PRINT HYD ID=9 CODE=1

HYDROGRAPH FROM AREA XD1_M4

RUNOFF VOLUME = 1.48086 INCHES = 0.1509 ACRE-FEET
PEAK DISCHARGE RATE = 4.26 CFS AT 1.500 HOURS BASIN AREA =
0.0019 SQ. MI.

*

*Add basins XD2 M3 basin-routing

ADD HYD ID=10 HYD=XD2_M3 ID=2 ID=4

PRINT HYD ID=10 CODE=1

HYDROGRAPH FROM AREA XD2_M3

RUNOFF VOLUME = 1.51067 INCHES = 0.1598 ACRE-FEET
PEAK DISCHARGE RATE = 4.42 CFS AT 1.500 HOURS BASIN AREA =
0.0020 SQ. MI.

*

*Add basins XM2 XD2 M3 basin-routing

ADD HYD ID=11 HYD=XM2_XD2_M3 ID=5 ID=10

PRINT HYD ID=11 CODE=1

HYDROGRAPH FROM AREA XM2_XD2_M3

RUNOFF VOLUME = 1.49237 INCHES = 0.2415 ACRE-FEET
PEAK DISCHARGE RATE = 6.88 CFS AT 1.500 HOURS BASIN AREA =
0.0030 SQ. MI.

*

*Add basins XM2 XD2 M3 XD1 M4 basin-routing

ADD HYD ID=12 HYD=XM2_XD2_M3_XD1_M4 ID=9 ID=11

PRINT HYD ID=12 CODE=1

HYDROGRAPH FROM AREA XM2_XD2_M3_XD1_M4

RUNOFF VOLUME = 1.48792 INCHES = 0.3924 ACRE-FEET
 PEAK DISCHARGE RATE = 11.14 CFS AT 1.500 HOURS BASIN AREA =
 0.0049 SQ. MI.

*

*Add basins M1 XM1 basin-routing

ADD HYD ID=13 HYD=M1_XM1 ID=6 ID=7

PRINT HYD ID=13 CODE=1

HYDROGRAPH FROM AREA M1_XM1

RUNOFF VOLUME = 1.84144 INCHES = 0.2385 ACRE-FEET
 PEAK DISCHARGE RATE = 6.20 CFS AT 1.500 HOURS BASIN AREA =
 0.0024 SQ. MI.

*

COMPUTE NM HYD ID=14 HYD=N DA=0.00367838

A B C D 15 0 85 0

TP=0.13330 MASS RAIN=-1

K = 0.114133HR TP = 0.133300HR K/TP RATIO = 0.856211 SHAPE
 CONSTANT, N = 4.154749

UNIT PEAK = 10.082 CFS UNIT VOLUME = 1.000 B = 365.36

P60 = 1.8000

AREA = 0.003678 SQ MI IA = 0.39500 INCHES INF = 0.95600
 INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
 0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=14 CODE=1

HYDROGRAPH FROM AREA N

RUNOFF VOLUME = 1.05739 INCHES = 0.2074 ACRE-FEET
 PEAK DISCHARGE RATE = 7.23 CFS AT 1.500 HOURS BASIN AREA =
 0.0037 SQ. MI.

*

*Add basins N XM2 XD2 M3 XD1 M4 basin-routing

ADD HYD ID=15 HYD=N_XM2_XD2_M3_XD1_M4 ID=12 ID=14

PRINT HYD ID=15 CODE=1

HYDROGRAPH FROM AREA

N_XM2_XD2_M3_XD1_M4

RUNOFF VOLUME = 1.30426 INCHES = 0.5998 ACRE-FEET

PEAK DISCHARGE RATE = 18.37 CFS AT 1.500 HOURS BASIN AREA =
0.0086 SQ. MI.

*

*Add basins M1 XM1 M2 basin-routing

ADD HYD ID=16 HYD=M1_XM1_M2 ID=8 ID=13

PRINT HYD ID=16 CODE=1

HYDROGRAPH FROM AREA M1_XM1_M2

RUNOFF VOLUME = 1.98804 INCHES = 0.3219 ACRE-FEET

PEAK DISCHARGE RATE = 8.05 CFS AT 1.500 HOURS BASIN AREA =
0.0030 SQ. MI.

*

*Add basins M1 XM1 M2 N XM2 XD2 M3 XD1 M4 basin-routing

ADD HYD ID=17 HYD=woodward ID=15 ID=16

PRINT HYD ID=17 CODE=1

HYDROGRAPH FROM AREA woodward

RUNOFF VOLUME = 1.48230 INCHES = 0.9217 ACRE-FEET

PEAK DISCHARGE RATE = 26.42 CFS AT 1.500 HOURS BASIN AREA =
0.0117 SQ. MI.

*

COMPUTE NM HYD ID=18 HYD=I1 DA=0.000621979

A B C D 0 0 0 100
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428

UNIT PEAK = 2.4556 CFS UNIT VOLUME = 0.9951 B = 526.28
P60 = 1.8000

AREA = 0.000622 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=18 CODE=1

HYDROGRAPH FROM AREA I1

RUNOFF VOLUME = 2.57457 INCHES = 0.0854 ACRE-FEET
PEAK DISCHARGE RATE = 1.89 CFS AT 1.500 HOURS BASIN AREA =
0.0006 SQ. MI.

*

COMPUTE NM HYD ID=19 HYD=I2 DA=0.000247657
A B C D 0 0 0 100
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428

UNIT PEAK = 0.97776 CFS UNIT VOLUME = 0.9891 B = 526.28
P60 = 1.8000

AREA = 0.000248 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=19 CODE=1

HYDROGRAPH FROM AREA I2

RUNOFF VOLUME = 2.57457 INCHES = 0.0340 ACRE-FEET
PEAK DISCHARGE RATE = 0.76 CFS AT 1.500 HOURS BASIN AREA =

0.0002 SQ. MI.

*

*Add basins I2 I1 basin-routing

ADD HYD ID=20 HYD=I2_I1 ID=18 ID=19

PRINT HYD ID=20 CODE=1

HYDROGRAPH FROM AREA I2_I1

RUNOFF VOLUME = 2.57402 INCHES = 0.1194 ACRE-FEET

PEAK DISCHARGE RATE = 2.65 CFS AT 1.500 HOURS BASIN AREA =
0.0009 SQ. MI.

*

COMPUTE NM HYD ID=1 HYD=H2 DA=0.000540774

A B C D 0 0 0 100

TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428

UNIT PEAK = 2.1350 CFS UNIT VOLUME = 0.9941 B = 526.28
P60 = 1.8000

AREA = 0.000541 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=1 CODE=1

HYDROGRAPH FROM AREA H2

RUNOFF VOLUME = 2.57457 INCHES = 0.0743 ACRE-FEET

PEAK DISCHARGE RATE = 1.65 CFS AT 1.500 HOURS BASIN AREA =
0.0005 SQ. MI.

*

*Add basins H2 I2 I1 basin-routing

ADD HYD ID=2 HYD=H2_I2_I1 ID=20 ID=1

PRINT HYD ID=2 CODE=1

HYDROGRAPH FROM AREA H2_I2_I1

RUNOFF VOLUME = 2.57407 INCHES = 0.1936 ACRE-FEET
PEAK DISCHARGE RATE = 4.30 CFS AT 1.500 HOURS BASIN AREA =
0.0014 SQ. MI.

*

COMPUTE NM HYD ID=3 HYD=H1 DA=0.000254482
A B C D 0 0 0 100
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428

UNIT PEAK = 1.0047 CFS UNIT VOLUME = 0.9891 B = 526.28
P60 = 1.8000

AREA = 0.000254 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=3 CODE=1

HYDROGRAPH FROM AREA H1

RUNOFF VOLUME = 2.57457 INCHES = 0.0349 ACRE-FEET
PEAK DISCHARGE RATE = 0.78 CFS AT 1.500 HOURS BASIN AREA =
0.0003 SQ. MI.

*

*Add basins H1 H2 I2 I1 basin-routing

ADD HYD ID=4 HYD=H1_H2_I2_I1 ID=2 ID=3

PRINT HYD ID=4 CODE=1

HYDROGRAPH FROM AREA H1_H2_I2_I1

RUNOFF VOLUME = 2.57396 INCHES = 0.2286 ACRE-FEET

PEAK DISCHARGE RATE = 5.08 CFS AT 1.500 HOURS BASIN AREA = 0.0017 SQ. MI.

*

COMPUTE NM HYD ID=5 HYD=H DA=0.000663978
A B C D 0 0 0 100
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428

UNIT PEAK = 2.6214 CFS UNIT VOLUME = 0.9951 B = 526.28
P60 = 1.8000

AREA = 0.000664 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = 0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=5 CODE=1

HYDROGRAPH FROM AREA H

RUNOFF VOLUME = 2.57457 INCHES = 0.0912 ACRE-FEET
PEAK DISCHARGE RATE = 2.02 CFS AT 1.500 HOURS BASIN AREA = 0.0007 SQ. MI.

*

*Add basins H H1 H2 I2 I1 basin-routing
ADD HYD ID=6 HYD=H_H1_H2_I2_I1 ID=4 ID=5
PRINT HYD ID=6 CODE=1

HYDROGRAPH FROM AREA H_H1_H2_I2_I1

RUNOFF VOLUME = 2.57405 INCHES = 0.3197 ACRE-FEET
PEAK DISCHARGE RATE = 7.10 CFS AT 1.500 HOURS BASIN AREA = 0.0023 SQ. MI.

*

COMPUTE NM HYD ID=7 HYD=I DA=0.000641823

A B C D 0 0 0 100
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428

UNIT PEAK = 2.5340 CFS UNIT VOLUME = 0.9951 B = 526.28
P60 = 1.8000

AREA = 0.000642 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=7 CODE=1

HYDROGRAPH FROM AREA I

RUNOFF VOLUME = 2.57457 INCHES = 0.0881 ACRE-FEET
PEAK DISCHARGE RATE = 1.95 CFS AT 1.500 HOURS BASIN AREA =
0.0006 SQ. MI.

*

*Add basins I H H1 H2 I2 I1 basin-routing

ADD HYD ID=8 HYD=I_H_H1_H2_I2_I1 ID=6 ID=7

PRINT HYD ID=8 CODE=1

HYDROGRAPH FROM AREA I_H_H1_H2_I2_I1

RUNOFF VOLUME = 2.57410 INCHES = 0.4078 ACRE-FEET
PEAK DISCHARGE RATE = 9.05 CFS AT 1.500 HOURS BASIN AREA =
0.0030 SQ. MI.

*

*Add basins DetPondInE(M1 XM1 M2 N XM2 XD2 M3 XD1 M4 I H H1 H2 I2 I1) basin-rout

ADD HYD ID=21 HYD=DetPondInE ID=17 ID=8

PRINT HYD ID=21 CODE=1

HYDROGRAPH FROM AREA DetPondInE

RUNOFF VOLUME = 1.70400 INCHES = 1.3295 ACRE-FEET
PEAK DISCHARGE RATE = 35.47 CFS AT 1.500 HOURS BASIN AREA =
0.0146 SQ. MI.

*

COMPUTE NM HYD ID=9 HYD=P DA=0.000468872
A B C D 0 0 0 100
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428

UNIT PEAK = 1.8511 CFS UNIT VOLUME = 0.9928 B = 526.28
P60 = 1.8000

AREA = 0.000469 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=9 CODE=1

HYDROGRAPH FROM AREA P

RUNOFF VOLUME = 2.57457 INCHES = 0.0644 ACRE-FEET
PEAK DISCHARGE RATE = 1.43 CFS AT 1.500 HOURS BASIN AREA =
0.0005 SQ. MI.

*

COMPUTE NM HYD ID=10 HYD=S DA=0.000444064
A B C D 0 0 0 100
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428

UNIT PEAK = 1.7532 CFS UNIT VOLUME = 0.9928 B = 526.28
P60 = 1.8000

AREA = 0.000444 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=10 CODE=1

HYDROGRAPH FROM AREA S

RUNOFF VOLUME = 2.57457 INCHES = 0.0610 ACRE-FEET
PEAK DISCHARGE RATE = 1.36 CFS AT 1.500 HOURS BASIN AREA =
0.0004 SQ. MI.

*

*Add basins S P basin-routing

ADD HYD ID=11 HYD=S_P ID=9 ID=10

PRINT HYD ID=11 CODE=1

HYDROGRAPH FROM AREA S_P

RUNOFF VOLUME = 2.57416 INCHES = 0.1253 ACRE-FEET
PEAK DISCHARGE RATE = 2.79 CFS AT 1.500 HOURS BASIN AREA =
0.0009 SQ. MI.

*

COMPUTE NM HYD ID=12 HYD=P1 DA=0.000967237

A B C D 0 0 10 90

TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428

UNIT PEAK = 3.4368 CFS UNIT VOLUME = 0.9959 B = 526.28
P60 = 1.8000

AREA = 0.000871 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

K = 0.105077HR TP = 0.133300HR K/TP RATIO = 0.788276 SHAPE
CONSTANT, N = 4.552748

UNIT PEAK = 0.28334 CFS UNIT VOLUME = 0.9592 B = 390.48
P60 = 1.8000

AREA = 0.000097 SQ MI IA = 0.35000 INCHES INF = 0.83000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=12 CODE=1

HYDROGRAPH FROM AREA P1

RUNOFF VOLUME = 2.43150 INCHES = 0.1254 ACRE-FEET
PEAK DISCHARGE RATE = 2.86 CFS AT 1.500 HOURS BASIN AREA =
0.0010 SQ. MI.

*

COMPUTE NM HYD ID=13 HYD=S1 DA=0.000578041
A B C D 0 0 10 90
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428
UNIT PEAK = 2.0539 CFS UNIT VOLUME = 0.9941 B = 526.28
P60 = 1.8000
AREA = 0.000520 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

K = 0.105077HR TP = 0.133300HR K/TP RATIO = 0.788276 SHAPE
CONSTANT, N = 4.552748
UNIT PEAK = 0.16933 CFS UNIT VOLUME = 0.9334 B = 390.48
P60 = 1.8000
AREA = 0.000058 SQ MI IA = 0.35000 INCHES INF = 0.83000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=13 CODE=1

HYDROGRAPH FROM AREA S1

RUNOFF VOLUME = 2.43150 INCHES = 0.0750 ACRE-FEET
PEAK DISCHARGE RATE = 1.72 CFS AT 1.500 HOURS BASIN AREA =
0.0006 SQ. MI.

*

*Add basins S1 P1 basin-routing

ADD HYD ID=14 HYD=S1_P1 ID=12 ID=13

PRINT HYD ID=14 CODE=1

HYDROGRAPH FROM AREA S1_P1

RUNOFF VOLUME = 2.43119 INCHES = 0.2004 ACRE-FEET
PEAK DISCHARGE RATE = 4.58 CFS AT 1.500 HOURS BASIN AREA =
0.0015 SQ. MI.

*

*Add basins S P S1 P1 basin-routing

ADD HYD ID=15 HYD=S1_P1_S_P ID=11 ID=14

PRINT HYD ID=15 CODE=1

HYDROGRAPH FROM AREA S1_P1_S_P

RUNOFF VOLUME = 2.48428 INCHES = 0.3257 ACRE-FEET
PEAK DISCHARGE RATE = 7.37 CFS AT 1.500 HOURS BASIN AREA =
0.0025 SQ. MI.

*

COMPUTE NM HYD ID=16 HYD=T DA=0.00126173

A B C D 0 0 0 100

TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428

UNIT PEAK = 4.9814 CFS UNIT VOLUME = 0.9971 B = 526.28

P60 = 1.8000

AREA = 0.001262 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=16 CODE=1

HYDROGRAPH FROM AREA T

RUNOFF VOLUME = 2.57457 INCHES = 0.1732 ACRE-FEET
 PEAK DISCHARGE RATE = 3.83 CFS AT 1.500 HOURS BASIN AREA =
 0.0013 SQ. MI.

*

*Add basins T S1 P1 S P basin-routing

ADD HYD ID=17 HYD=T_S1_P1_S_P ID=15 ID=16

PRINT HYD ID=17 CODE=1

HYDROGRAPH FROM AREA T_S1_P1_S_P

RUNOFF VOLUME = 2.51483 INCHES = 0.4989 ACRE-FEET
 PEAK DISCHARGE RATE = 11.20 CFS AT 1.500 HOURS BASIN AREA =
 0.0037 SQ. MI.

*

COMPUTE NM HYD ID=18 HYD=Q1 DA=0.000194272

A B C D 0 0 10 90

TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
 CONSTANT, N = 7.106428

UNIT PEAK = 0.69030 CFS UNIT VOLUME = 0.9832 B = 526.28
 P60 = 1.8000

AREA = 0.000175 SQ MI IA = 0.10000 INCHES INF = 0.04000
 INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
 0.050000

K = 0.105077HR TP = 0.133300HR K/TP RATIO = 0.788276 SHAPE
 CONSTANT, N = 4.552748

UNIT PEAK = 0.56909E-01CFS UNIT VOLUME = 0.8918 B = 390.48
 P60 = 1.8000

AREA = 0.000019 SQ MI IA = 0.35000 INCHES INF = 0.83000
 INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
 0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=18 CODE=1

HYDROGRAPH FROM AREA Q1

RUNOFF VOLUME = 2.43150 INCHES = 0.0252 ACRE-FEET
PEAK DISCHARGE RATE = 0.58 CFS AT 1.500 HOURS BASIN AREA =
0.0002 SQ. MI.

*

COMPUTE NM HYD ID=19 HYD=R1 DA=0.0003026
A B C D 0 0 10 90
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428
UNIT PEAK = 1.0752 CFS UNIT VOLUME = 0.9891 B = 526.28
P60 = 1.8000
AREA = 0.000272 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

K = 0.105077HR TP = 0.133300HR K/TP RATIO = 0.788276 SHAPE
CONSTANT, N = 4.552748
UNIT PEAK = 0.88642E-01CFS UNIT VOLUME = 0.8918 B = 390.48
P60 = 1.8000
AREA = 0.000030 SQ MI IA = 0.35000 INCHES INF = 0.83000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=19 CODE=1

HYDROGRAPH FROM AREA R1

RUNOFF VOLUME = 2.43150 INCHES = 0.0392 ACRE-FEET
PEAK DISCHARGE RATE = 0.91 CFS AT 1.500 HOURS BASIN AREA =
0.0003 SQ. MI.

*

*Add basins Q1 R1 basin-routing

ADD HYD ID=20 HYD=Q1_R1 ID=18 ID=19

PRINT HYD ID=20 CODE=1

HYDROGRAPH FROM AREA Q1_R1

RUNOFF VOLUME = 2.42693 INCHES = 0.0643 ACRE-FEET
PEAK DISCHARGE RATE = 1.49 CFS AT 1.500 HOURS BASIN AREA =
0.0005 SQ. MI.

*

COMPUTE NM HYD ID=1 HYD=Q DA=0.000793384

A B C D 0 0 8 92

TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428

UNIT PEAK = 2.8817 CFS UNIT VOLUME = 0.9951 B = 526.28
P60 = 1.8000

AREA = 0.000730 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

K = 0.105077HR TP = 0.133300HR K/TP RATIO = 0.788276 SHAPE
CONSTANT, N = 4.552748

UNIT PEAK = 0.18593 CFS UNIT VOLUME = 0.9334 B = 390.48
P60 = 1.8000

AREA = 0.000063 SQ MI IA = 0.35000 INCHES INF = 0.83000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=1 CODE=1

HYDROGRAPH FROM AREA Q

RUNOFF VOLUME = 2.46011 INCHES = 0.1041 ACRE-FEET

PEAK DISCHARGE RATE = 2.37 CFS AT 1.500 HOURS BASIN AREA =
0.0008 SQ. MI.

*

COMPUTE NM HYD ID=2 HYD=R DA=0.000582811
A B C D 0 0 10 90
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428
UNIT PEAK = 2.0709 CFS UNIT VOLUME = 0.9941 B = 526.28
P60 = 1.8000
AREA = 0.000525 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

K = 0.105077HR TP = 0.133300HR K/TP RATIO = 0.788276 SHAPE
CONSTANT, N = 4.552748
UNIT PEAK = 0.17073 CFS UNIT VOLUME = 0.9334 B = 390.48
P60 = 1.8000
AREA = 0.000058 SQ MI IA = 0.35000 INCHES INF = 0.83000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=2 CODE=1

HYDROGRAPH FROM AREA R

RUNOFF VOLUME = 2.43150 INCHES = 0.0756 ACRE-FEET
PEAK DISCHARGE RATE = 1.73 CFS AT 1.500 HOURS BASIN AREA =
0.0006 SQ. MI.

*

*Add basins Q R basin-routing
ADD HYD ID=3 HYD=Q_R ID=1 ID=2
PRINT HYD ID=3 CODE=1

HYDROGRAPH FROM AREA Q_R

RUNOFF VOLUME = 2.44768 INCHES = 0.1797 ACRE-FEET
PEAK DISCHARGE RATE = 4.10 CFS AT 1.500 HOURS BASIN AREA =
0.0014 SQ. MI.

*

*Add basins Q R Q1 R1 basin-routing

ADD HYD ID=4 HYD=Q_R_Q1_R1 ID=20 ID=3

PRINT HYD ID=4 CODE=1

HYDROGRAPH FROM AREA Q_R_Q1_R1

RUNOFF VOLUME = 2.44217 INCHES = 0.2440 ACRE-FEET
PEAK DISCHARGE RATE = 5.59 CFS AT 1.500 HOURS BASIN AREA =
0.0019 SQ. MI.

*

*Add basins Q R Q1 R1 T S1 P1 S P basin-routing

ADD HYD ID=5 HYD=broadway ID=17 ID=4

PRINT HYD ID=5 CODE=1

HYDROGRAPH FROM AREA highway

RUNOFF VOLUME = 2.49050 INCHES = 0.7429 ACRE-FEET
PEAK DISCHARGE RATE = 16.79 CFS AT 1.500 HOURS BASIN AREA =
0.0056 SQ. MI.

*

COMPUTE NM HYD ID=6 HYD=XC DA=0.004401217

A B C D 0 0 80 20

TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428

UNIT PEAK = 3.4752 CFS UNIT VOLUME = 0.9959 B = 526.28
P60 = 1.8000

AREA = 0.000880 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =

0.050000

K = 0.105077HR TP = 0.133300HR K/TP RATIO = 0.788276 SHAPE
CONSTANT, N = 4.552748
UNIT PEAK = 10.314 CFS UNIT VOLUME = 1.001 B = 390.48
P60 = 1.8000
AREA = 0.003521 SQ MI IA = 0.35000 INCHES INF = 0.83000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=6 CODE=1

HYDROGRAPH FROM AREA XC

RUNOFF VOLUME = 1.42997 INCHES = 0.3357 ACRE-FEET
PEAK DISCHARGE RATE = 10.16 CFS AT 1.500 HOURS BASIN AREA =
0.0044 SQ. MI.

*

*Add basins Q R Q1 R1 T S1 P1 S P XC basin-routing
ADD HYD ID=7 HYD=broadway XC ID=5 ID=6
PRINT HYD ID=7 CODE=1

HYDROGRAPH FROM AREA roadway

RUNOFF VOLUME = 2.02344 INCHES = 1.0785 ACRE-FEET
PEAK DISCHARGE RATE = 26.95 CFS AT 1.500 HOURS BASIN AREA =
0.0100 SQ. MI.

*

COMPUTE NM HYD ID=8 HYD=D DA=0.000317857
A B C D 0 0 0 100
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428
UNIT PEAK = 1.2549 CFS UNIT VOLUME = 0.9911 B = 526.28
P60 = 1.8000

AREA = 0.000318 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=8 CODE=1

HYDROGRAPH FROM AREA D

RUNOFF VOLUME = 2.57457 INCHES = 0.0436 ACRE-FEET
PEAK DISCHARGE RATE = 0.97 CFS AT 1.500 HOURS BASIN AREA =
0.0003 SQ. MI.

*

COMPUTE NM HYD ID=9 HYD=C DA=0.00037726
A B C D 0 0 0 100
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428
UNIT PEAK = 1.4894 CFS UNIT VOLUME = 0.9928 B = 526.28
P60 = 1.8000
AREA = 0.000377 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=9 CODE=1

HYDROGRAPH FROM AREA C

RUNOFF VOLUME = 2.57457 INCHES = 0.0518 ACRE-FEET
PEAK DISCHARGE RATE = 1.15 CFS AT 1.500 HOURS BASIN AREA =
0.0004 SQ. MI.

*

*Add basins D C basin-routing
ADD HYD ID=10 HYD=D_C ID=8 ID=9

PRINT HYD ID=10 CODE=1

HYDROGRAPH FROM AREA D_C

RUNOFF VOLUME = 2.57406 INCHES = 0.0954 ACRE-FEET
PEAK DISCHARGE RATE = 2.12 CFS AT 1.500 HOURS BASIN AREA =
0.0007 SQ. MI.

*

*Add basins D C Q R Q1 R1 T S1 P1 S P XC basin-routing
ADD HYD ID=11 HYD=Broadway Sun ID=7 ID=10
PRINT HYD ID=11 CODE=1

HYDROGRAPH FROM AREA Broadway

RUNOFF VOLUME = 2.05925 INCHES = 1.1740 ACRE-FEET
PEAK DISCHARGE RATE = 29.07 CFS AT 1.500 HOURS BASIN AREA =
0.0107 SQ. MI.

*

COMPUTE NM HYD ID=12 HYD=G1 DA=0.001237166
A B C D 0 0 0 100
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428
UNIT PEAK = 4.8844 CFS UNIT VOLUME = 0.9971 B = 526.28
P60 = 1.8000

AREA = 0.001237 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=12 CODE=1

HYDROGRAPH FROM AREA G1

RUNOFF VOLUME = 2.57457 INCHES = 0.1699 ACRE-FEET

PEAK DISCHARGE RATE = 3.76 CFS AT 1.500 HOURS BASIN AREA =
0.0012 SQ. MI.

*

COMPUTE NM HYD ID=13 HYD=G DA=0.001068715
A B C D 0 0 0 100
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428

UNIT PEAK = 4.2193 CFS UNIT VOLUME = 0.9966 B = 526.28
P60 = 1.8000

AREA = 0.001069 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=13 CODE=1

HYDROGRAPH FROM AREA G

RUNOFF VOLUME = 2.57457 INCHES = 0.1467 ACRE-FEET
PEAK DISCHARGE RATE = 3.25 CFS AT 1.500 HOURS BASIN AREA =
0.0011 SQ. MI.

*

*Add basins G1 G basin-routing

ADD HYD ID=14 HYD=G1_G ID=12 ID=13

PRINT HYD ID=14 CODE=1

HYDROGRAPH FROM AREA G1_G

RUNOFF VOLUME = 2.57435 INCHES = 0.3166 ACRE-FEET
PEAK DISCHARGE RATE = 7.01 CFS AT 1.500 HOURS BASIN AREA =
0.0023 SQ. MI.

*

*Add basins G1 G D C Q R Q1 R1 T S1 P1 S P XC basin-routing

ADD HYD ID=15 HYD=DetPondInW ID=11 ID=14
PRINT HYD ID=15 CODE=1

HYDROGRAPH FROM AREA DetPondInW

RUNOFF VOLUME = 2.15065 INCHES = 1.4906 ACRE-FEET
PEAK DISCHARGE RATE = 36.08 CFS AT 1.500 HOURS BASIN AREA =
0.0130 SQ. MI.

*

*Add basins G1 G D C Q R Q1 R1 T S1 P1 S P XC M1 XM1 M2 N XM2 XD2 M3 XD1 M4 I H
ADD HYD ID=16 HYD=DetPondInSS ID=21 ID=15
PRINT HYD ID=16 CODE=1

HYDROGRAPH FROM AREA DetPondInSS

RUNOFF VOLUME = 1.91411 INCHES = 2.8201 ACRE-FEET
PEAK DISCHARGE RATE = 71.56 CFS AT 1.500 HOURS BASIN AREA =
0.0276 SQ. MI.

*

COMPUTE NM HYD ID=17 HYD=XJ DA=0.007554964
A B C D 30 33 37 0
TP=0.13330 MASS RAIN=-1

K = 0.132147HR TP = 0.133300HR K/TP RATIO = 0.991350 SHAPE
CONSTANT, N = 3.561352

UNIT PEAK = 18.408 CFS UNIT VOLUME = 1.000 B = 324.79
P60 = 1.8000

AREA = 0.007555 SQ MI IA = 0.48950 INCHES INF = 1.22060
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=17 CODE=1

HYDROGRAPH FROM AREA XJ

RUNOFF VOLUME = 0.90246 INCHES = 0.3636 ACRE-FEET
PEAK DISCHARGE RATE = 12.48 CFS AT 1.500 HOURS BASIN AREA =
0.0076 SQ. MI.

*

COMPUTE NM HYD ID=18 HYD=XJ1 DA=0.0104488
A B C D 0 75 25 0
TP=0.13330 MASS RAIN=-1

K = 0.125437HR TP = 0.133300HR K/TP RATIO = 0.941013 SHAPE
CONSTANT, N = 3.757359
UNIT PEAK = 26.546 CFS UNIT VOLUME = 1.001 B = 338.66
P60 = 1.8000
AREA = 0.010449 SQ MI IA = 0.46250 INCHES INF = 1.14500
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=18 CODE=1

HYDROGRAPH FROM AREA XJ1

RUNOFF VOLUME = 0.94796 INCHES = 0.5283 ACRE-FEET
PEAK DISCHARGE RATE = 18.34 CFS AT 1.500 HOURS BASIN AREA =
0.0104 SQ. MI.

*

*Add basins XJ1 XJ basin-routing
ADD HYD ID=19 HYD=XJ1_XJ ID=17 ID=18
PRINT HYD ID=19 CODE=1

HYDROGRAPH FROM AREA XJ1_XJ

RUNOFF VOLUME = 0.92886 INCHES = 0.8919 ACRE-FEET
PEAK DISCHARGE RATE = 30.82 CFS AT 1.500 HOURS BASIN AREA =
0.0180 SQ. MI.

*

*Add basins XJ1 XJ G1 G D C Q R Q1 R1 T S1 P1 S P XC M1 XM1 M2 N XM2 XD2 M3 XD1
 ADD HYD ID=20 HYD=DetPondIn ID=16 ID=19
 PRINT HYD ID=20 CODE=1

HYDROGRAPH FROM AREA DetPondIn

RUNOFF VOLUME = 1.52536 INCHES = 3.7120 ACRE-FEET
 PEAK DISCHARGE RATE = 102.37 CFS AT 1.500 HOURS BASIN AREA =
 0.0456 SQ. MI.

*

* pond discharges into storm sewer that discharges into the San Jose Drain
 ROUTE RESERVOIR ID=1 HYD=DetPondOut INFLOW ID=20 CODE=5

OUTFLOW(cfs)	STORAGE(ac ft)	ELEV(ft)
0.000	0.000	4934.3
0.430	0.600	4935
1.243	1.430	4936
3.550	2.350	4937
5.068	3.320	4938
14.530	4.350	4939
16.130	5.450	4940
17.770	6.600	4941
18.640	7.280	4941.5

* * * * *

TIME (HRS)	INFLOW (CFS)	ELEV (FEET)	VOLUME (AC-FT)	OUTFLOW (CFS)
0.00	0.00	4934.30	0.000	0.00
0.25	0.00	4934.30	0.000	0.00
0.50	0.00	4934.30	0.000	0.00
0.75	0.11	4934.30	0.000	0.00
1.00	2.91	4934.34	0.032	0.02
1.25	10.02	4934.47	0.150	0.11
1.50	102.37	4935.63	1.120	0.94
1.75	34.38	4937.20	2.545	3.86
2.00	11.61	4937.54	2.872	4.37
2.25	5.31	4937.61	2.944	4.48
2.50	2.35	4937.60	2.930	4.46
2.75	1.12	4937.54	2.872	4.37
3.00	0.63	4937.46	2.801	4.26
3.25	0.41	4937.39	2.725	4.14
3.50	0.30	4937.31	2.648	4.02
3.75	0.27	4937.23	2.572	3.90
4.00	0.25	4937.15	2.498	3.78

4.25	0.25	4937.08	2.426	3.67
4.50	0.26	4937.01	2.356	3.56
4.75	0.27	4936.93	2.290	3.40
5.00	0.28	4936.87	2.227	3.24
5.25	0.30	4936.80	2.168	3.09
5.50	0.32	4936.74	2.112	2.95
5.75	0.34	4936.68	2.059	2.82
6.00	0.35	4936.63	2.009	2.69
6.25	0.36	4936.58	1.962	2.58
6.50	0.36	4936.53	1.917	2.46
6.75	0.35	4936.48	1.875	2.36
7.00	0.35	4936.44	1.834	2.26
7.25	0.35	4936.40	1.796	2.16
7.50	0.34	4936.36	1.759	2.07
7.75	0.34	4936.32	1.725	1.98
8.00	0.33	4936.28	1.692	1.90
8.25	0.33	4936.25	1.660	1.82
8.50	0.33	4936.22	1.630	1.74
8.75	0.32	4936.19	1.601	1.67
9.00	0.32	4936.16	1.574	1.60
9.25	0.32	4936.13	1.548	1.54
9.50	0.31	4936.10	1.523	1.48
9.75	0.31	4936.08	1.500	1.42
10.00	0.30	4936.05	1.477	1.36
10.25	0.30	4936.03	1.456	1.31
10.50	0.29	4936.01	1.436	1.26
10.75	0.29	4935.98	1.416	1.23
11.00	0.28	4935.96	1.397	1.21
11.25	0.28	4935.94	1.378	1.19
11.50	0.28	4935.91	1.359	1.17
11.75	0.27	4935.89	1.341	1.16
12.00	0.27	4935.87	1.323	1.14
12.25	0.26	4935.85	1.305	1.12
12.50	0.26	4935.83	1.287	1.10
12.75	0.25	4935.81	1.270	1.09
13.00	0.25	4935.79	1.253	1.07
13.25	0.25	4935.77	1.236	1.05
13.50	0.24	4935.75	1.219	1.04
13.75	0.24	4935.73	1.203	1.02

TIME (HRS)	INFLOW (CFS)	ELEV (FEET)	VOLUME (AC-FT)	OUTFLOW (CFS)
---------------	-----------------	----------------	-------------------	------------------

14.00	0.24	4935.71	1.187	1.00
14.25	0.23	4935.69	1.171	0.99
14.50	0.22	4935.67	1.156	0.97
14.75	0.22	4935.65	1.140	0.96
15.00	0.22	4935.63	1.125	0.94
15.25	0.21	4935.61	1.110	0.93
15.50	0.21	4935.60	1.095	0.92

15.75	0.20	4935.58	1.081	0.90
16.00	0.20	4935.56	1.067	0.89
16.25	0.19	4935.54	1.052	0.87
16.50	0.19	4935.53	1.039	0.86
16.75	0.18	4935.51	1.025	0.85
17.00	0.18	4935.50	1.011	0.83
17.25	0.18	4935.48	0.998	0.82
17.50	0.17	4935.46	0.985	0.81
17.75	0.17	4935.45	0.972	0.79
18.00	0.17	4935.43	0.959	0.78
18.25	0.16	4935.42	0.946	0.77
18.50	0.15	4935.40	0.934	0.76
18.75	0.15	4935.39	0.921	0.74
19.00	0.15	4935.37	0.909	0.73
19.25	0.14	4935.36	0.897	0.72
19.50	0.14	4935.34	0.885	0.71
19.75	0.13	4935.33	0.874	0.70
20.00	0.13	4935.32	0.862	0.69
20.25	0.13	4935.30	0.851	0.68
20.50	0.12	4935.29	0.839	0.66
20.75	0.12	4935.27	0.828	0.65
21.00	0.12	4935.26	0.817	0.64
21.25	0.11	4935.25	0.806	0.63
21.50	0.11	4935.24	0.796	0.62
21.75	0.10	4935.22	0.785	0.61
22.00	0.10	4935.21	0.775	0.60
22.25	0.09	4935.20	0.764	0.59
22.50	0.09	4935.19	0.754	0.58
22.75	0.08	4935.17	0.744	0.57
23.00	0.08	4935.16	0.734	0.56
23.25	0.07	4935.15	0.724	0.55
23.50	0.07	4935.14	0.714	0.54
23.75	0.06	4935.13	0.704	0.53
24.00	0.06	4935.11	0.695	0.52
24.25	0.00	4935.10	0.685	0.51
24.50	0.00	4935.09	0.674	0.50
24.75	0.00	4935.08	0.664	0.49
25.00	0.00	4935.06	0.654	0.48
25.25	0.00	4935.05	0.644	0.47
25.50	0.00	4935.04	0.634	0.46
25.75	0.00	4935.03	0.625	0.45
26.00	0.00	4935.02	0.615	0.45
26.25	0.00	4935.01	0.606	0.44
26.50	0.00	4935.00	0.597	0.43
26.75	0.00	4934.99	0.589	0.42
27.00	0.00	4934.98	0.580	0.42
27.25	0.00	4934.97	0.571	0.41
27.50	0.00	4934.96	0.563	0.40
27.75	0.00	4934.95	0.555	0.40

TIME (HRS)	INFLOW (CFS)	ELEV (FEET)	VOLUME (AC-FT)	OUTFLOW (CFS)
28.00	0.00	4934.94	0.547	0.39
28.25	0.00	4934.93	0.539	0.39
28.50	0.00	4934.92	0.531	0.38
28.75	0.00	4934.91	0.523	0.37
29.00	0.00	4934.90	0.515	0.37
29.25	0.00	4934.89	0.508	0.36
29.50	0.00	4934.88	0.500	0.36
29.75	0.00	4934.88	0.493	0.35
30.00	0.00	4934.87	0.486	0.35
30.25	0.00	4934.86	0.478	0.34
30.50	0.00	4934.85	0.471	0.34
30.75	0.00	4934.84	0.464	0.33
31.00	0.00	4934.83	0.458	0.33
31.25	0.00	4934.83	0.451	0.32
31.50	0.00	4934.82	0.444	0.32
31.75	0.00	4934.81	0.438	0.31
32.00	0.00	4934.80	0.431	0.31
32.25	0.00	4934.80	0.425	0.30
32.50	0.00	4934.79	0.419	0.30
32.75	0.00	4934.78	0.413	0.30
33.00	0.00	4934.77	0.406	0.29
33.25	0.00	4934.77	0.401	0.29
33.50	0.00	4934.76	0.395	0.28
33.75	0.00	4934.75	0.389	0.28
34.00	0.00	4934.75	0.383	0.27
34.25	0.00	4934.74	0.377	0.27
34.50	0.00	4934.73	0.372	0.27
34.75	0.00	4934.73	0.366	0.26
35.00	0.00	4934.72	0.361	0.26
35.25	0.00	4934.71	0.356	0.25
35.50	0.00	4934.71	0.351	0.25
35.75	0.00	4934.70	0.345	0.25
36.00	0.00	4934.70	0.340	0.24
36.25	0.00	4934.69	0.335	0.24
36.50	0.00	4934.69	0.330	0.24
36.75	0.00	4934.68	0.326	0.23
37.00	0.00	4934.67	0.321	0.23
37.25	0.00	4934.67	0.316	0.23
37.50	0.00	4934.66	0.311	0.22
37.75	0.00	4934.66	0.307	0.22
38.00	0.00	4934.65	0.302	0.22
38.25	0.00	4934.65	0.298	0.21
38.50	0.00	4934.64	0.293	0.21
38.75	0.00	4934.64	0.289	0.21
39.00	0.00	4934.63	0.285	0.20
39.25	0.00	4934.63	0.281	0.20
39.50	0.00	4934.62	0.277	0.20

39.75	0.00	4934.62	0.273	0.20
40.00	0.00	4934.61	0.269	0.19
40.25	0.00	4934.61	0.265	0.19
40.50	0.00	4934.60	0.261	0.19
40.75	0.00	4934.60	0.257	0.18
41.00	0.00	4934.60	0.253	0.18
41.25	0.00	4934.59	0.249	0.18
41.50	0.00	4934.59	0.246	0.18
41.75	0.00	4934.58	0.242	0.17

TIME (HRS)	INFLOW (CFS)	ELEV (FEET)	VOLUME (AC-FT)	OUTFLOW (CFS)
---------------	-----------------	----------------	-------------------	------------------

42.00	0.00	4934.58	0.239	0.17
42.25	0.00	4934.57	0.235	0.17
42.50	0.00	4934.57	0.232	0.17
42.75	0.00	4934.57	0.228	0.16
43.00	0.00	4934.56	0.225	0.16
43.25	0.00	4934.56	0.222	0.16
43.50	0.00	4934.55	0.218	0.16
43.75	0.00	4934.55	0.215	0.15
44.00	0.00	4934.55	0.212	0.15
44.25	0.00	4934.54	0.209	0.15
44.50	0.00	4934.54	0.206	0.15
44.75	0.00	4934.54	0.203	0.15
45.00	0.00	4934.53	0.200	0.14
45.25	0.00	4934.53	0.197	0.14
45.50	0.00	4934.53	0.194	0.14
45.75	0.00	4934.52	0.191	0.14
46.00	0.00	4934.52	0.188	0.13
46.25	0.00	4934.52	0.185	0.13
46.50	0.00	4934.51	0.183	0.13
46.75	0.00	4934.51	0.180	0.13
47.00	0.00	4934.51	0.177	0.13
47.25	0.00	4934.50	0.175	0.13
47.50	0.00	4934.50	0.172	0.12
47.75	0.00	4934.50	0.170	0.12
48.00	0.00	4934.50	0.167	0.12
48.25	0.00	4934.49	0.165	0.12
48.50	0.00	4934.49	0.162	0.12
48.75	0.00	4934.49	0.160	0.11
49.00	0.00	4934.48	0.158	0.11
49.25	0.00	4934.48	0.155	0.11
49.50	0.00	4934.48	0.153	0.11
49.75	0.00	4934.48	0.151	0.11
50.00	0.00	4934.47	0.149	0.11
50.25	0.00	4934.47	0.146	0.10
50.50	0.00	4934.47	0.144	0.10
50.75	0.00	4934.47	0.142	0.10
51.00	0.00	4934.46	0.140	0.10

51.25	0.00	4934.46	0.138	0.10
51.50	0.00	4934.46	0.136	0.10
51.75	0.00	4934.46	0.134	0.10
52.00	0.00	4934.45	0.132	0.09
52.25	0.00	4934.45	0.130	0.09
52.50	0.00	4934.45	0.128	0.09
52.75	0.00	4934.45	0.126	0.09
53.00	0.00	4934.44	0.124	0.09
53.25	0.00	4934.44	0.123	0.09
53.50	0.00	4934.44	0.121	0.09
53.75	0.00	4934.44	0.119	0.09
54.00	0.00	4934.44	0.117	0.08
54.25	0.00	4934.43	0.115	0.08
54.50	0.00	4934.43	0.114	0.08
54.75	0.00	4934.43	0.112	0.08
55.00	0.00	4934.43	0.110	0.08
55.25	0.00	4934.43	0.109	0.08
55.50	0.00	4934.42	0.107	0.08
55.75	0.00	4934.42	0.106	0.08

TIME (HRS)	INFLOW (CFS)	ELEV (FEET)	VOLUME (AC-FT)	OUTFLOW (CFS)
---------------	-----------------	----------------	-------------------	------------------

56.00	0.00	4934.42	0.104	0.07
56.25	0.00	4934.42	0.103	0.07
56.50	0.00	4934.42	0.101	0.07
56.75	0.00	4934.42	0.100	0.07
57.00	0.00	4934.41	0.098	0.07
57.25	0.00	4934.41	0.097	0.07
57.50	0.00	4934.41	0.095	0.07
57.75	0.00	4934.41	0.094	0.07
58.00	0.00	4934.41	0.092	0.07
58.25	0.00	4934.41	0.091	0.07
58.50	0.00	4934.40	0.090	0.06
58.75	0.00	4934.40	0.088	0.06
59.00	0.00	4934.40	0.087	0.06
59.25	0.00	4934.40	0.086	0.06
59.50	0.00	4934.40	0.085	0.06
59.75	0.00	4934.40	0.083	0.06
60.00	0.00	4934.40	0.082	0.06
60.25	0.00	4934.39	0.081	0.06
60.50	0.00	4934.39	0.080	0.06
60.75	0.00	4934.39	0.079	0.06
61.00	0.00	4934.39	0.077	0.06
61.25	0.00	4934.39	0.076	0.05
61.50	0.00	4934.39	0.075	0.05
61.75	0.00	4934.39	0.074	0.05
62.00	0.00	4934.38	0.073	0.05
62.25	0.00	4934.38	0.072	0.05
62.50	0.00	4934.38	0.071	0.05

62.75	0.00	4934.38	0.070	0.05
63.00	0.00	4934.38	0.069	0.05
63.25	0.00	4934.38	0.068	0.05
63.50	0.00	4934.38	0.067	0.05
63.75	0.00	4934.38	0.066	0.05
64.00	0.00	4934.38	0.065	0.05
64.25	0.00	4934.37	0.064	0.05
64.50	0.00	4934.37	0.063	0.05
64.75	0.00	4934.37	0.062	0.04
65.00	0.00	4934.37	0.061	0.04
65.25	0.00	4934.37	0.060	0.04
65.50	0.00	4934.37	0.059	0.04
65.75	0.00	4934.37	0.058	0.04
66.00	0.00	4934.37	0.058	0.04
66.25	0.00	4934.37	0.057	0.04
66.50	0.00	4934.37	0.056	0.04
66.75	0.00	4934.36	0.055	0.04
67.00	0.00	4934.36	0.054	0.04
67.25	0.00	4934.36	0.053	0.04
67.50	0.00	4934.36	0.053	0.04
67.75	0.00	4934.36	0.052	0.04
68.00	0.00	4934.36	0.051	0.04
68.25	0.00	4934.36	0.050	0.04
68.50	0.00	4934.36	0.050	0.04
68.75	0.00	4934.36	0.049	0.04
69.00	0.00	4934.36	0.048	0.03
69.25	0.00	4934.36	0.047	0.03
69.50	0.00	4934.35	0.047	0.03
69.75	0.00	4934.35	0.046	0.03

TIME (HRS)	INFLOW (CFS)	ELEV (FEET)	VOLUME (AC-FT)	OUTFLOW (CFS)
---------------	-----------------	----------------	-------------------	------------------

70.00	0.00	4934.35	0.045	0.03
70.25	0.00	4934.35	0.045	0.03
70.50	0.00	4934.35	0.044	0.03
70.75	0.00	4934.35	0.043	0.03
71.00	0.00	4934.35	0.043	0.03
71.25	0.00	4934.35	0.042	0.03
71.50	0.00	4934.35	0.042	0.03
71.75	0.00	4934.35	0.041	0.03
72.00	0.00	4934.35	0.040	0.03
72.25	0.00	4934.35	0.040	0.03
72.50	0.00	4934.35	0.039	0.03
72.75	0.00	4934.34	0.039	0.03
73.00	0.00	4934.34	0.038	0.03
73.25	0.00	4934.34	0.037	0.03
73.50	0.00	4934.34	0.037	0.03
73.75	0.00	4934.34	0.036	0.03
74.00	0.00	4934.34	0.036	0.03

74.25	0.00	4934.34	0.035	0.03
74.50	0.00	4934.34	0.035	0.02
74.75	0.00	4934.34	0.034	0.02
75.00	0.00	4934.34	0.034	0.02
75.25	0.00	4934.34	0.033	0.02
75.50	0.00	4934.34	0.033	0.02
75.75	0.00	4934.34	0.032	0.02
76.00	0.00	4934.34	0.032	0.02
76.25	0.00	4934.34	0.031	0.02
76.50	0.00	4934.34	0.031	0.02
76.75	0.00	4934.34	0.030	0.02
77.00	0.00	4934.33	0.030	0.02
77.25	0.00	4934.33	0.030	0.02
77.50	0.00	4934.33	0.029	0.02
77.75	0.00	4934.33	0.029	0.02
78.00	0.00	4934.33	0.028	0.02
78.25	0.00	4934.33	0.028	0.02
78.50	0.00	4934.33	0.027	0.02
78.75	0.00	4934.33	0.027	0.02
79.00	0.00	4934.33	0.027	0.02
79.25	0.00	4934.33	0.026	0.02
79.50	0.00	4934.33	0.026	0.02
79.75	0.00	4934.33	0.025	0.02
80.00	0.00	4934.33	0.025	0.02
80.25	0.00	4934.33	0.025	0.02
80.50	0.00	4934.33	0.024	0.02
80.75	0.00	4934.33	0.024	0.02
81.00	0.00	4934.33	0.024	0.02
81.25	0.00	4934.33	0.023	0.02
81.50	0.00	4934.33	0.023	0.02
81.75	0.00	4934.33	0.023	0.02
82.00	0.00	4934.33	0.022	0.02
82.25	0.00	4934.33	0.022	0.02
82.50	0.00	4934.33	0.022	0.02
82.75	0.00	4934.32	0.021	0.02
83.00	0.00	4934.32	0.021	0.02
83.25	0.00	4934.32	0.021	0.01
83.50	0.00	4934.32	0.020	0.01
83.75	0.00	4934.32	0.020	0.01

TIME (HRS)	INFLOW (CFS)	ELEV (FEET)	VOLUME (AC-FT)	OUTFLOW (CFS)
---------------	-----------------	----------------	-------------------	------------------

84.00	0.00	4934.32	0.020	0.01
84.25	0.00	4934.32	0.020	0.01
84.50	0.00	4934.32	0.019	0.01
84.75	0.00	4934.32	0.019	0.01
85.00	0.00	4934.32	0.019	0.01
85.25	0.00	4934.32	0.018	0.01
85.50	0.00	4934.32	0.018	0.01

85.75	0.00	4934.32	0.018	0.01
86.00	0.00	4934.32	0.018	0.01
86.25	0.00	4934.32	0.017	0.01
86.50	0.00	4934.32	0.017	0.01
86.75	0.00	4934.32	0.017	0.01
87.00	0.00	4934.32	0.017	0.01
87.25	0.00	4934.32	0.016	0.01
87.50	0.00	4934.32	0.016	0.01
87.75	0.00	4934.32	0.016	0.01
88.00	0.00	4934.32	0.016	0.01
88.25	0.00	4934.32	0.015	0.01
88.50	0.00	4934.32	0.015	0.01
88.75	0.00	4934.32	0.015	0.01
89.00	0.00	4934.32	0.015	0.01
89.25	0.00	4934.32	0.015	0.01
89.50	0.00	4934.32	0.014	0.01
89.75	0.00	4934.32	0.014	0.01
90.00	0.00	4934.32	0.014	0.01
90.25	0.00	4934.32	0.014	0.01
90.50	0.00	4934.32	0.013	0.01
90.75	0.00	4934.32	0.013	0.01
91.00	0.00	4934.31	0.013	0.01
91.25	0.00	4934.31	0.013	0.01
91.50	0.00	4934.31	0.013	0.01
91.75	0.00	4934.31	0.013	0.01
92.00	0.00	4934.31	0.012	0.01
92.25	0.00	4934.31	0.012	0.01
92.50	0.00	4934.31	0.012	0.01
92.75	0.00	4934.31	0.012	0.01
93.00	0.00	4934.31	0.012	0.01
93.25	0.00	4934.31	0.011	0.01
93.50	0.00	4934.31	0.011	0.01
93.75	0.00	4934.31	0.011	0.01
94.00	0.00	4934.31	0.011	0.01
94.25	0.00	4934.31	0.011	0.01
94.50	0.00	4934.31	0.011	0.01
94.75	0.00	4934.31	0.010	0.01
95.00	0.00	4934.31	0.010	0.01
95.25	0.00	4934.31	0.010	0.01
95.50	0.00	4934.31	0.010	0.01
95.75	0.00	4934.31	0.010	0.01
96.00	0.00	4934.31	0.010	0.01
96.25	0.00	4934.31	0.010	0.01
96.50	0.00	4934.31	0.009	0.01
96.75	0.00	4934.31	0.009	0.01
97.00	0.00	4934.31	0.009	0.01
97.25	0.00	4934.31	0.009	0.01
97.50	0.00	4934.31	0.009	0.01
97.75	0.00	4934.31	0.009	0.01

TIME (HRS)	INFLOW (CFS)	ELEV (FEET)	VOLUME (AC-FT)	OUTFLOW (CFS)
98.00	0.00	4934.31	0.009	0.01
98.25	0.00	4934.31	0.009	0.01
98.50	0.00	4934.31	0.008	0.01
98.75	0.00	4934.31	0.008	0.01
99.00	0.00	4934.31	0.008	0.01
99.25	0.00	4934.31	0.008	0.01
99.50	0.00	4934.31	0.008	0.01
99.75	0.00	4934.31	0.008	0.01
100.00	0.00	4934.31	0.008	0.01
100.25	0.00	4934.31	0.008	0.01
100.50	0.00	4934.31	0.007	0.01
100.75	0.00	4934.31	0.007	0.01
101.00	0.00	4934.31	0.007	0.01
101.25	0.00	4934.31	0.007	0.01
101.50	0.00	4934.31	0.007	0.01
101.75	0.00	4934.31	0.007	0.00

PEAK DISCHARGE = 4.483 CFS - PEAK OCCURS AT HOUR 2.30
 MAXIMUM WATER SURFACE ELEVATION = 4937.615
 MAXIMUM STORAGE = 2.9463 AC-FT INCREMENTAL TIME= 0.050000HRS

*

*

COMPUTE NM HYD ID=2 HYD=XV DA=0.003050928
 A B C D 0 0 10 90
 TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
 CONSTANT, N = 7.106428

UNIT PEAK = 10.841 CFS UNIT VOLUME = 0.9981 B = 526.28
 P60 = 1.8000
 AREA = 0.002746 SQ MI IA = 0.10000 INCHES INF = 0.04000
 INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
 0.050000

K = 0.105077HR TP = 0.133300HR K/TP RATIO = 0.788276 SHAPE
 CONSTANT, N = 4.552748

UNIT PEAK = 0.89372 CFS UNIT VOLUME = 0.9877 B = 390.48
 P60 = 1.8000
 AREA = 0.000305 SQ MI IA = 0.35000 INCHES INF = 0.83000
 INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
 0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD

ID=2 CODE=1

HYDROGRAPH FROM AREA XV

RUNOFF VOLUME = 2.43150 INCHES = 0.3956 ACRE-FEET
PEAK DISCHARGE RATE = 8.99 CFS AT 1.500 HOURS BASIN AREA =
0.0031 SQ. MI.

*

COMPUTE NM HYD ID=3 HYD=A DA=0.000885059
A B C D 0 0 2 98
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428

UNIT PEAK = 3.4244 CFS UNIT VOLUME = 0.9959 B = 526.28
P60 = 1.8000

AREA = 0.000867 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

K = 0.105077HR TP = 0.133300HR K/TP RATIO = 0.788276 SHAPE
CONSTANT, N = 4.552748

UNIT PEAK = 0.51853E-01CFS UNIT VOLUME = 0.8918 B = 390.48
P60 = 1.8000

AREA = 0.000018 SQ MI IA = 0.35000 INCHES INF = 0.83000
INCHES PER HOUR

RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD

ID=3 CODE=1

HYDROGRAPH FROM AREA A

RUNOFF VOLUME = 2.54596 INCHES = 0.1202 ACRE-FEET
PEAK DISCHARGE RATE = 2.68 CFS AT 1.500 HOURS BASIN AREA =
0.0009 SQ. MI.

*

COMPUTE NM HYD ID=4 HYD=B DA=0.000822449
A B C D 0 0 2 98
TP=0.13330 MASS RAIN=-1

K = 0.072649HR TP = 0.133300HR K/TP RATIO = 0.545000 SHAPE
CONSTANT, N = 7.106428
UNIT PEAK = 3.1821 CFS UNIT VOLUME = 0.9959 B = 526.28
P60 = 1.8000
AREA = 0.000806 SQ MI IA = 0.10000 INCHES INF = 0.04000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

K = 0.105077HR TP = 0.133300HR K/TP RATIO = 0.788276 SHAPE
CONSTANT, N = 4.552748
UNIT PEAK = 0.48185E-01CFS UNIT VOLUME = 0.8918 B = 390.48
P60 = 1.8000
AREA = 0.000016 SQ MI IA = 0.35000 INCHES INF = 0.83000
INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT =
0.050000

BULKING FACTOR APPLIED TO HYDROGRAPH. FACTOR = 1.10000 AT PEAK FLOW.

PRINT HYD ID=4 CODE=1

HYDROGRAPH FROM AREA B

RUNOFF VOLUME = 2.54596 INCHES = 0.1117 ACRE-FEET
PEAK DISCHARGE RATE = 2.49 CFS AT 1.500 HOURS BASIN AREA =
0.0008 SQ. MI.

*

*Add basins A B basin-routing
ADD HYD ID=5 HYD=A_B ID=3 ID=4
PRINT HYD ID=5 CODE=1

HYDROGRAPH FROM AREA A_B

RUNOFF VOLUME = 2.54566 INCHES = 0.2318 ACRE-FEET
PEAK DISCHARGE RATE = 5.17 CFS AT 1.500 HOURS BASIN AREA =

0.0017 SQ. MI.

*

*Add basins XV DetPondOut basin-routing

ADD HYD ID=6 HYD=XV_DetPondOut ID=1 ID=2

PRINT HYD ID=6 CODE=1

HYDROGRAPH FROM AREA XV_DetPondOut

RUNOFF VOLUME = 1.58161 INCHES = 4.1062 ACRE-FEET

PEAK DISCHARGE RATE = 10.04 CFS AT 1.550 HOURS BASIN AREA =

0.0487 SQ. MI.

*

*Add basins A B XV DetPondOut basin-routing

ADD HYD ID=7 HYD=XV_DetPondOut_A_B ID=5 ID=6

PRINT HYD ID=7 CODE=1

HYDROGRAPH FROM AREA XV_DetPondOut_A_B

RUNOFF VOLUME = 1.61428 INCHES = 4.3380 ACRE-FEET

PEAK DISCHARGE RATE = 15.10 CFS AT 1.500 HOURS BASIN AREA =

0.0504 SQ. MI.

*

FINISH

NORMAL PROGRAM FINISH

END TIME (HR:MIN:SEC) = 17:52:22

APPENDIX D
HYDROLOGY WORKSHEETS

APPENDIX D

HYDROLOGY WORKSHEETS

- Summary of Hydrology and Hydraulic Calculations
- Pond Elevation-Storage-Discharge Tables
- Hydraulic Grade Line Graphical Results
- Drop Inlet Spread Calculations

SUMMARY OF HYDROLOGY AND HYDRAULIC CALCULATIONS

Hydrology

The computer program Arid Lands Hydrology Model (AHYMO) was utilized to calculate storm water runoff volumes and flow rates for the 100-year 24-hour event, consistent with the preliminary drainage report (PDR). The AHYMO model varies from the AHYMO model from the PDR due to an increase in the number of sub basins as a result of roadway geometry and placement of drop inlets. The AHYMO model was also revised to utilize NOAA Atlas 14 precipitation values instead of NOAA Atlas 2 precipitation values.

Hydraulics

This project utilizes both New Mexico Department of Transportation (NMDOT) and City of Albuquerque (COA) standard drawings. The portion of this project which utilizes NMDOT items is east of Broadway Boulevard consisting of Sunport Boulevard while the portion utilizing COA items consists of Broadway Boulevard and Woodward Road.

Drop Inlet Calculations

The computer program Hydraflow Express is an extension of AutoCAD Civil 3D and was utilized to determine inlet capacities. A number of inputs specific to the type of drop inlet were input into the program to determine inlet capacities including but not limited to the inlet type, sag or grade location, length, throat height, grate width, local depression, and cross slopes.

Sunport Boulevard generally consists of slopes between 4% and 7%. Spread did not appear to be an issue with the utilization of the single Type I inlets, as the spread did not appear to approach one driving lane in width. Drop inlets on grade within Sunport Boulevard were utilized to prevent large discharge values down at the intersection of Sunport/Broadway where a sag condition occurs.

Woodward Road and Broadway Boulevard have minimal longitudinal slope. The storm sewer lines as part of this project generally have a slope of 0.1% with minimal cover to allow for discharge to the detention pond southeast of the Broadway/Sunport intersection. Due to the shallow slopes and backwater effects from the pond once it is full, velocities are expected to be minimal during high precipitation events. Therefore, COA Type D drop inlets are proposed for this portion of the project. The thought is that drop inlets which utilize the grate opening as well as the curb opening may allow for larger debris to enter the storm sewer system in this area that most likely would not have the velocities to effectively remove that debris.

The results of these computations can be found within Appendix D including a graphical representation of the spread and a tabular results showing the efficiency of the inlet for discharge in increments of 0.25 cfs. It should be noted that spread is limited to less than one driving lane throughout the project.

Storm Sewer Calculations

The computer program Autodesk Storm and Sanitary Analysis 2018 (SSA) was utilized to model flows within the storm sewer system. It was determined that the storm sewer system within Broadway Boulevard discharging into the detention pond would require modeling of backwater effects and surcharging due to the system configuration. SSA was determined to have the ability to model what was necessary for this type of system.

In order to run the program effectively to model the necessary components of the system, many program components were created with a number of inputs. These components included junctions, conveyance links (pipes), and outfalls. Below is a brief summary of each of these components:

- Junctions were utilized where manholes or drop inlets exist throughout the system. The AHYMO discharge values were input at the junctions to represent the 100-year discharge values from sub-basins that would be entering the storm drain system at those locations.

- Conveyance links were created to connect the Junctions as they do within the plans. Input information including pipe sizes, materials, and invert elevations were assigned to each conveyance link. Junctions (manholes) were utilized as shown on the plans.
- Outfalls were utilized to represent discharge locations within the system including the San Jose Drain, Detention Pond, Water Quality Pond, and South Diversion Channel. The maximum water surface elevation reached for the detention pond within AHYMO was utilized as a control elevation for the hydraulic calculations. The 10-year water surface elevation for the San Jose Drain at the discharge location was also used as a control elevation for hydraulic calculations.

The AHYMO discharges were utilized in the inlet calculations and are shown on the design plans. The Hydraulic Grade Lines (HGL) calculated within the SSA model are shown on the design plans with the AHYMO discharges.


The results of the analysis including HGL and drop inlet graphical results and tabular results can be found within this Appendix.

Detention Pond (Southeast of Broadway/Sunport intersection)												
Elevation (ft)	Area (sf)	Area (ac)	Depth (ft)	Storage (cf)	Storage (ac-ft)	Q(cfs) Row 1	Q(cfs) Row 2	Q(cfs) Row 3	Q(cfs) Row 4	Q (cfs) 18" pipe	Q (cfs) grate	Q(cfs)
4934.28	33,900	0.78	0.0	0	0.00	0	0	0.0	0.0	0.0	0.0	0.00
4935	36,180	0.83	0.7	25,229	0.58	0.849477734	0.00	0.0	0.0	0.0	0.0	0.85
4936	38,830	0.89	1.7	62,442	1.43	1.380452492	1.00	0.1	0.0	0.0	0.0	2.49
4937	41,462	0.95	2.7	102,253	2.35	1.766925204	1.49	1.1	0.3	0.0	0.0	4.73
4938	44,061	1.01	3.7	144,658	3.32	2.06459535	1.83	1.6	1.3	0.0	0.0	6.76
4939	46,679	1.07	4.7	189,675	4.35					14.5	22.1	14.53
4940	49,282	1.13	5.7	237,293	5.45					16.1	62.5	16.13
4941	51,870	1.19	6.7	287,502	6.60					17.8	114.8	17.77
4941.5	53,000	1.22	7.2	317,090	7.28					18.6	144.7	18.64


Water Quality Basin							
Elevation (ft)	Area (sf)	Depth (ft)	Storage(cf)	Storage (ac-ft)	Q (cfs) 3-6" PVC reverse slope pipes	Q(cfs) spillway	Q(cfs) Total
5000.38	2,125.7	0	0	0.0	0.00	0	0.0
5001	2,600.7	0.62	1,465	0.0	0.00	0	0.0
5002	3,437.4	1.62	4,408	0.1	0.00	0	0.0
5003	4,330.7	2.62	8,184	0.2	1.72	0	1.7
5004	5,280.6	3.62	12,869	0.3	3.32	58	61.2
5005	10,643.0	4.62	21,882	0.5	4.36	220	224.2
5006	11,318.0	5.62	31,902	0.7	5.20	498	502.9
5007	11,992.6	6.62	42,805	1.0	5.93	907	912.8


Structure	Invert Elevation (ft)	Rim Elevation (ft)	Max. HGL Elevation (ft)	Max. EGL Elevation (ft)
P-1	4935.56	4939.27	4936.22	4936.25
P-2	4933.50	4938.95	4934.72	4934.77
P-3	4935.10	4938.64	4935.93	4935.94
P-4	4936.86	4940.07	4937.58	4937.61
P-5	4936.43	4939.95	4937.54	4937.59
P-6	4938.64	4941.85	4939.63	4939.68
P-7	4938.21	4941.73	4939.53	4939.63
P-8	4936.15	4939.69	4937.84	4938.00
P-9	4936.06	4939.85	4937.76	4937.82
P-10	4936.15	4939.69	4937.77	4937.78
P-11	4935.71	4939.27	4938.65	4938.83
P-12	4935.02	4939.16	4937.71	4937.94
P-13	4935.12	4938.73	4937.76	4937.87
P-13A	4936.00	4940.00	4937.81	4937.82
P-14	4934.86	4940.15	4937.58	4943.59
P-15	4934.69	4941.20	4937.44	4938.58
P-16	4934.51	4942.29	4937.34	4937.67
P-17A	4934.29	4941.50	4935.45	4935.89
P-18	4934.19	4943.82	4935.43	4936.85
P-19	4933.90	4941.18	4935.39	4936.58
P-19A	4933.83	4940.29	4935.34	4937.32
P-20	4933.80	4940.17	4935.34	4935.77
P-21	4936.02	4939.56	4939.56	4939.83
P-22	4935.67	4939.66	4938.08	4938.34
P-23	4936.01	4939.55	4938.08	4938.10
P-24	4935.26	4938.97	4938.97	4939.22
P-25	4935.13	4939.21	4937.69	4937.86
P-26	4935.55	4938.99	4937.70	4938.88
P-27	4993.88	4997.44	4994.08	4995.04
P-28	4992.82	4996.61	4993.30	4994.54
P-29	4992.26	4995.87	4993.19	4997.21
P-30	4992.03	4995.66	4992.46	4993.62
P-31	4969.11	4973.16	4969.65	4977.51
P-32	4965.60	4970.65	4966.57	4966.44
P-33	4954.75	4968.45	4955.92	4955.93
P-34	5025.32	5029.32	5026.11	5025.99
P-35	5025.12	5029.28	5026.09	5025.96
P-36	5024.72	5028.13	5025.14	5025.21
P-37	5024.77	5028.38	5025.39	5025.36
P-38	5009.22	5018.18	5010.58	5010.59
P-39	4999.89	5004.94	5002.46	5002.47
P-40	4998.82	5004.45	5001.87	5001.87
P-41	5018.59	5032.59	5020.14	5020.14
P-41A	5009.63	5017.68	5013.15	5013.15
P-45	4960.61	4965.00	4965.00	4967.50
P-45A	4963.68	4967.52	4964.78	4964.99
P-45B	4963.46	4967.34	4964.60	4964.67
P-47	4982.48	4987.48	4982.97	4983.04
P-48	4978.35	4984.38	4982.94	4983.11


Storm Drain						
Storm Drain	Upstream Structure	Downstream Structure	Average Slope %	Diameter (in)	Q, Peak Discharge, AHYMO (cfs)	Velocity (ft/s)
SD-1	P-1	P-2	0.5000	18	2.5	1.4
SD-2	P-3	P-2	0.5000	18	3.2	1.8
SD-3	P-19	P-19A	0.1000	18	1.5	0.8
SD-3A	P-19A	P-20	0.1300	18	1.5	1.5
SD-4	P-18	P-19	0.1000	18	1.5	1.8
SD-5	P-14	P-15	0.1000	42	16.8	1.7
SD-6	P-4	P-5	0.5100	24	1.0	2.5
SD-7	P-5	P-15	0.4200	24	2.1	3.2
SD-8	P-15	P-16	0.1000	42	18.9	2.0
SD-9	P-25	P-14	0.1200	36	5.6	0.8
SD-10	P-6	P-7	0.5000	24	3.8	3.4
SD-11	P-7	P-16	0.5000	24	7.0	3.8
SD-12	P-16	P-17DetPondwest	0.5300	42	25.9	2.7
SD-13	P-17A	P-18	0.1100	18	1.5	0.8
SD-14	P-33	P-46DetPondEast	8.0000	24	33.5	19.7
SD-15	P-45	P-33	0.5200	24	26.4	8.6
SD-15A	P-45A	P-45B	0.5000	24	6.4	4.6
SD-15B	P-45B	P-45C	0.8300	24	8.3	5.3
SD-16	P-32	P-33	6.4300	24	9.1	9.6
SD-17	P-31	P-32	6.0200	24	7.1	8.7
SD-18	P-30	P-31	7.3700	24	5.1	11.3
SD-19	P-29	P-30	2.4000	24	4.3	5.3
SD-20	P-28	P-29	1.2700	24	2.7	4.2
SD-21	P-27	P-28	3.3700	24	0.8	4.1
SD-21A	P-34	P-35	0.4800	24	0.9	1.3
SD-22	P-35	P-36	0.5100	24	4.6	4.0
SD-23	P-37	P-36	0.5000	24	1.8	3.3
SD-24	P-36	WQPOut	34.7400	18	6.4	8.7
SD-25	P-40	P-40A	0.5500	42	62.6	7.9
SD-26	P-39	P-40	1.1300	42	62.6	9.1
SD-27	P-38	P-39	4.4800	36	56.0	16.3
SD-28	P-41A	P-38	0.5000	36	55.5	8.8
SD-28A	P-41	P-41A	7.9000	36	52.0	22.6
SD-29	P-8	P-9	0.1000	18	1.4	0.8
SD-30	P-10	P-9	0.6000	18	1.4	0.8
SD-31	P-9	P-12	0.2000	30	2.8	0.6
SD-31A	P-11	P-12	0.5100	24	1.7	0.5
SD-31B	P-13	P-12	0.1200	24	6.7	2.1
SD-32	P-12	P-14	0.1000	36	11.2	1.6
SD-33	P-24	P-25	0.1100	24	2.4	0.8
SD-34	P-26	P-25	12.3300	18	1.7	1.0
SD-35	P-22	P-25	0.1400	36	1.5	0.2
SD-36	P-23	P-22	0.3300	18	0.9	0.5
SD-37	P-21	P-22	0.5100	18	0.6	0.3
SD-38	P-47	P-48	6.1200	24	6.88	12.7
SD-39	P-48	P-49	0.2100	24	11.14	3.6
SD-40	P-13A	P-13	6.1800	18	3.83	2.2
Existing	P-20	P-2	0.1400	30	10.4	2.1
toSanJoseDrain	P-2	San Jose Drain	0.6800	30	16.1	3.3





SUNPORT BOULEVARD EXTENSION
DRAINAGE BASIN MAP
DECEMBER 2019


















































































































































Inlet Report

COA Single Storm Inlet Type D Grate (Sag)

Grate Inlet

Location	= Sag
Curb Length (ft)	= -0-
Throat Height (in)	= -0-
Grate Area (sqft)	= 3.72
Grate Width (ft)	= 2.08
Grate Length (ft)	= 3.33

Gutter

Slope, Sw (ft/ft)	= 0.063
Slope, Sx (ft/ft)	= 0.020
Local Depr (in)	= 2.75
Gutter Width (ft)	= 2.00
Gutter Slope (%)	= -0-
Gutter n-value	= -0-


Calculations

Compute by:	Q vs Depth
Max Depth (in)	= 7

Highlighted

Q Total (cfs)	= 5.75
Q Capt (cfs)	= 5.75
Q Bypass (cfs)	= -0-
Depth at Inlet (in)	= 7.05
Efficiency (%)	= 100
Gutter Spread (ft)	= 13.63
Gutter Vel (ft/s)	= -0-
Bypass Spread (ft)	= -0-
Bypass Depth (in)	= -0-

All dimensions in feet



Q		Inlet		Gutter	
Total	Captured	Depth	Efficiency	Depth	Spread
(cfs)	(cfs)	(in)	(%)	(in)	(ft)
0.25	0.25	1.20	100	-1.55	0.56
0.50	0.50	1.90	100	-0.85	0.89
0.75	0.75	2.49	100	-0.26	1.17
1.00	1.00	3.01	100	0.26	1.41
1.25	1.25	3.50	100	0.75	1.64
1.50	1.50	3.95	100	1.20	1.85
1.75	1.75	4.38	100	1.63	2.48
2.00	2.00	4.61	100	1.86	3.44
2.25	2.25	4.80	100	2.05	4.26
2.50	2.50	4.99	100	2.24	5.04
2.75	2.75	5.17	100	2.42	5.80
3.00	3.00	5.35	100	2.60	6.54
3.25	3.25	5.52	100	2.77	7.25
3.50	3.50	5.69	100	2.94	7.95
3.75	3.75	5.85	100	3.10	8.63
4.00	4.00	6.01	100	3.26	9.30
4.25	4.25	6.17	100	3.42	9.95
4.50	4.50	6.32	100	3.57	10.59
4.75	4.75	6.47	100	3.72	11.22
5.00	5.00	6.62	100	3.87	11.84
5.25	5.25	6.77	100	4.02	12.44
5.50	5.50	6.91	100	4.16	13.04
5.75	5.75	7.05	100	4.30	13.63

Inlet Report

COA Double Storm Inlet Type D Grate (Sag)

Grate Inlet

Location	= Sag
Curb Length (ft)	= -0-
Throat Height (in)	= -0-
Grate Area (sqft)	= 7.44
Grate Width (ft)	= 2.08
Grate Length (ft)	= 6.66

Gutter

Slope, Sw (ft/ft)	= 0.063
Slope, Sx (ft/ft)	= 0.020
Local Depr (in)	= 2.75
Gutter Width (ft)	= 2.00
Gutter Slope (%)	= -0-
Gutter n-value	= -0-


Calculations

Compute by:	Q vs Depth
Max Depth (in)	= 8

Highlighted

Q Total (cfs)	= 8.50
Q Capt (cfs)	= 8.50
Q Bypass (cfs)	= -0-
Depth at Inlet (in)	= 7.13
Efficiency (%)	= 100
Gutter Spread (ft)	= 13.94
Gutter Vel (ft/s)	= -0-
Bypass Spread (ft)	= -0-
Bypass Depth (in)	= -0-

All dimensions in feet



Q		Inlet		Gutter	
Total	Captured	Depth	Efficiency	Depth	Spread
(cfs)	(cfs)	(in)	(%)	(in)	(ft)
0.25	0.25	0.94	100	-1.81	0.44
0.50	0.50	1.49	100	-1.26	0.70
0.75	0.75	1.95	100	-0.80	0.91
1.00	1.00	2.36	100	-0.39	1.11
1.25	1.25	2.74	100	-0.01	1.28
1.50	1.50	3.09	100	0.34	1.45
1.75	1.75	3.43	100	0.68	1.61
2.00	2.00	3.74	100	0.99	1.76
2.25	2.25	4.05	100	1.30	1.90
2.50	2.50	4.34	100	1.59	2.34
2.75	2.75	4.53	100	1.78	3.12
3.00	3.00	4.67	100	1.92	3.70
3.25	3.25	4.80	100	2.05	4.26
3.50	3.50	4.93	100	2.18	4.80
3.75	3.75	5.06	100	2.31	5.34
4.00	4.00	5.19	100	2.44	5.86
4.25	4.25	5.31	100	2.56	6.37
4.50	4.50	5.43	100	2.68	6.87
4.75	4.75	5.55	100	2.80	7.36
5.00	5.00	5.66	100	2.91	7.84
5.25	5.25	5.78	100	3.03	8.32
5.50	5.50	5.89	100	3.14	8.79
5.75	5.75	6.00	100	3.25	9.25
6.00	6.00	6.11	100	3.36	9.70
6.25	6.25	6.22	100	3.47	10.15
6.50	6.50	6.32	100	3.57	10.59
6.75	6.75	6.43	100	3.68	11.03
7.00	7.00	6.53	100	3.78	11.46
7.25	7.25	6.63	100	3.88	11.88
7.50	7.50	6.73	100	3.98	12.30
7.75	7.75	6.83	100	4.08	12.72
8.00	8.00	6.93	100	4.18	13.13
8.25	8.25	7.03	100	4.28	13.54
8.50	8.50	7.13	100	4.38	13.94
8.75	8.75	7.22	100	4.47	14.34
9.00	9.00	7.32	100	4.57	14.74
9.25	9.25	7.41	100	4.66	15.13
9.50	9.50	7.51	100	4.76	15.52
9.75	9.75	7.60	100	4.85	15.90
10.00	10.00	7.69	100	4.94	16.28
10.25	10.25	7.78	100	5.03	16.66
10.50	10.50	7.87	100	5.12	17.04
10.75	10.75	7.96	100	5.21	17.41
11.00	11.00	8.05	100	5.30	17.78

Inlet Report

COA Triple Storm Inlet Type D Grate (Sag)

Grate Inlet

Location	= Sag
Curb Length (ft)	= -0-
Throat Height (in)	= -0-
Grate Area (sqft)	= 11.16
Grate Width (ft)	= 2.08
Grate Length (ft)	= 9.99

Gutter

Slope, Sw (ft/ft)	= 0.063
Slope, Sx (ft/ft)	= 0.020
Local Depr (in)	= 2.75
Gutter Width (ft)	= 2.00
Gutter Slope (%)	= -0-
Gutter n-value	= -0-


Calculations

Compute by:	Q vs Depth
Max Depth (in)	= 8

Highlighted

Q Total (cfs)	= 11.00
Q Capt (cfs)	= 11.00
Q Bypass (cfs)	= -0-
Depth at Inlet (in)	= 7.09
Efficiency (%)	= 100
Gutter Spread (ft)	= 13.80
Gutter Vel (ft/s)	= -0-
Bypass Spread (ft)	= -0-
Bypass Depth (in)	= -0-

All dimensions in feet



Q		Inlet		Gutter	
Total	Captured	Depth	Efficiency	Depth	Spread
(cfs)	(cfs)	(in)	(%)	(in)	(ft)
0.25	0.25	0.78	100	-1.97	0.37
0.50	0.50	1.24	100	-1.51	0.58
0.75	0.75	1.63	100	-1.12	0.76
1.00	1.00	1.97	100	-0.78	0.93
1.25	1.25	2.29	100	-0.46	1.07
1.50	1.50	2.58	100	-0.17	1.21
1.75	1.75	2.86	100	0.11	1.34
2.00	2.00	3.13	100	0.38	1.47
2.25	2.25	3.39	100	0.64	1.59
2.50	2.50	3.63	100	0.88	1.70
2.75	2.75	3.87	100	1.12	1.82
3.00	3.00	4.10	100	1.35	1.93
3.25	3.25	4.33	100	1.58	2.27
3.50	3.50	4.49	100	1.74	2.95
3.75	3.75	4.60	100	1.85	3.39
4.00	4.00	4.70	100	1.95	3.83
4.25	4.25	4.80	100	2.05	4.26
4.50	4.50	4.90	100	2.15	4.68
4.75	4.75	5.00	100	2.25	5.09
5.00	5.00	5.10	100	2.35	5.49
5.25	5.25	5.20	100	2.45	5.89
5.50	5.50	5.29	100	2.54	6.28
5.75	5.75	5.38	100	2.63	6.66
6.00	6.00	5.47	100	2.72	7.04
6.25	6.25	5.56	100	2.81	7.42
6.50	6.50	5.65	100	2.90	7.79
6.75	6.75	5.74	100	2.99	8.15
7.00	7.00	5.82	100	3.07	8.51
7.25	7.25	5.91	100	3.16	8.87
7.50	7.50	5.99	100	3.24	9.22
7.75	7.75	6.08	100	3.33	9.57
8.00	8.00	6.16	100	3.41	9.91
8.25	8.25	6.24	100	3.49	10.25
8.50	8.50	6.32	100	3.57	10.59
8.75	8.75	6.40	100	3.65	10.92
9.00	9.00	6.48	100	3.73	11.25
9.25	9.25	6.56	100	3.81	11.58
9.50	9.50	6.64	100	3.89	11.91
9.75	9.75	6.72	100	3.97	12.23
10.00	10.00	6.79	100	4.04	12.55
10.25	10.25	6.87	100	4.12	12.86
10.50	10.50	6.94	100	4.19	13.18
10.75	10.75	7.02	100	4.27	13.49
11.00	11.00	7.09	100	4.34	13.80
11.25	11.25	7.17	100	4.42	14.11
11.50	11.50	7.24	100	4.49	14.41
11.75	11.75	7.31	100	4.56	14.71
12.00	12.00	7.38	100	4.63	15.01
12.25	12.25	7.46	100	4.71	15.31

Q		Inlet		Gutter	
Total	Captured	Depth	Efficiency	Depth	Spread
(cfs)	(cfs)	(in)	(%)	(in)	(ft)
12.50	12.50	7.53	100	4.78	15.61
12.75	12.75	7.60	100	4.85	15.90
13.00	13.00	7.67	100	4.92	16.19
13.25	13.25	7.74	100	4.99	16.48
13.50	13.50	7.81	100	5.06	16.77
13.75	13.75	7.88	100	5.13	17.06
14.00	14.00	7.94	100	5.19	17.34
14.25	14.25	8.01	100	5.26	17.63

Gutter	Bypass		
Velocity	Q	Spread	Depth
(ft/s)	(cfs)	(ft)	(in)
n/a	n/a	n/a	n/a
n/a	n/a	n/a	n/a
n/a	n/a	n/a	n/a
n/a	n/a	n/a	n/a
n/a	n/a	n/a	n/a
n/a	n/a	n/a	n/a
n/a	n/a	n/a	n/a
n/a	n/a	n/a	n/a

Q			Inlet		Gutter		Bypass		
Total	Captured	Depth	Efficiency	Depth	Spread	Velocity	Q	Spread	Depth
(cfs)	(cfs)	(in)	(%)	(in)	(ft)	(ft/s)	(cfs)	(ft)	(in)
0.25	0.25	3.64	100	1.33	1.10	4.11	0.00	0.00	0.00
0.50	0.50	4.03	100	1.72	1.42	4.90	0.00	0.00	0.00
0.75	0.75	4.32	100	2.01	1.66	5.42	0.00	0.00	0.00
1.00	1.00	4.54	100	2.23	1.84	5.83	0.00	0.00	0.00
1.25	1.20	4.74	96	2.43	2.03	6.16	0.05	0.61	0.74
1.50	1.40	4.91	94	2.60	2.73	6.34	0.10	0.77	0.93
1.75	1.60	5.05	91	2.74	3.33	6.41	0.15	0.90	1.10
2.00	1.79	5.18	89	2.87	3.85	6.45	0.21	1.03	1.25
2.25	1.97	5.29	87	2.98	4.31	6.47	0.28	1.15	1.39
2.50	2.14	5.39	85	3.08	4.72	6.49	0.36	1.26	1.53
2.75	2.30	5.48	83	3.17	5.10	6.52	0.45	1.37	1.66
3.00	2.45	5.56	82	3.25	5.44	6.55	0.55	1.48	1.79
3.25	2.59	5.64	80	3.33	5.76	6.58	0.66	1.58	1.91
3.50	2.73	5.71	78	3.40	6.06	6.61	0.77	1.67	2.02
3.75	2.87	5.78	76	3.47	6.34	6.65	0.88	1.76	2.13
4.00	3.00	5.84	75	3.53	6.61	6.69	1.00	1.84	2.24
4.25	3.13	5.90	74	3.59	6.86	6.73	1.12	1.93	2.34
4.50	3.25	5.96	72	3.65	7.09	6.77	1.25	2.03	2.43
4.75	3.37	6.01	71	3.70	7.32	6.81	1.38	2.41	2.52

Inlet Report

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Thursday, Nov 14 2019

NMDOT Type 1-B On Grade 7.36% slope

Combination Inlet

Location	=	On grade
Curb Length (ft)	=	5.58
Throat Height (in)	=	5.06
Grate Area (sqft)	=	-0-
Grate Width (ft)	=	1.38
Grate Length (ft)	=	4.50

Gutter

Slope, Sw (ft/ft)	= 0.101
Slope, Sx (ft/ft)	= 0.020
Local Depr (in)	= 2.31
Gutter Width (ft)	= 2.00
Gutter Slope (%)	= 7.36
Gutter n-value	= 0.017


Calculations

Compute by: Q vs Depth
Max Depth (in) = 6

Highlighted

Q Total (cfs)	= 4.75
Q Capt (cfs)	= 3.37
Q Bypass (cfs)	= 1.38
Depth at Inlet (in)	= 6.01
Efficiency (%)	= 71
Gutter Spread (ft)	= 7.32
Gutter Vel (ft/s)	= 6.81
Bypass Spread (ft)	= 2.41
Bypass Depth (in)	= 2.52

All dimensions in feet



Q		Inlet		Gutter	
Total	Captured	Depth	Efficiency	Depth	Spread
(cfs)	(cfs)	(in)	(%)	(in)	(ft)
0.25	0.25	3.73	100	1.42	1.17
0.50	0.50	4.15	100	1.84	1.52
0.75	0.74	4.45	98	2.14	1.77
1.00	0.96	4.70	96	2.39	1.97
1.25	1.18	4.90	94	2.59	2.71
1.50	1.39	5.07	93	2.76	3.42
1.75	1.59	5.22	91	2.91	4.02
2.00	1.79	5.34	90	3.03	4.55
2.25	1.99	5.46	88	3.15	5.01
2.50	2.17	5.56	87	3.25	5.42
2.75	2.36	5.65	86	3.34	5.80
3.00	2.54	5.73	85	3.42	6.16
3.25	2.71	5.81	84	3.50	6.48
3.50	2.89	5.88	82	3.57	6.79
3.75	3.06	5.95	82	3.64	7.07
4.00	3.23	6.02	81	3.71	7.35
4.25	3.39	6.08	80	3.77	7.61
4.50	3.55	6.14	79	3.83	7.85
4.75	3.71	6.19	78	3.88	8.09
5.00	3.87	6.25	77	3.94	8.32
5.25	4.03	6.30	77	3.99	8.53
5.50	4.19	6.35	76	4.04	8.74
5.75	4.34	6.40	75	4.09	8.95
6.00	4.49	6.45	75	4.14	9.14
6.25	4.64	6.49	74	4.18	9.33
6.50	4.79	6.54	74	4.23	9.51
6.75	4.94	6.58	73	4.27	9.70
7.00	5.08	6.62	73	4.31	9.87
7.25	5.23	6.66	72	4.35	10.04
7.50	5.37	6.70	72	4.39	10.21
7.75	5.51	6.74	71	4.43	10.37
8.00	5.65	6.78	71	4.47	10.53
8.25	5.79	6.82	70	4.51	10.68
8.50	5.93	6.85	70	4.54	10.83
8.75	6.06	6.89	69	4.58	10.98
9.00	6.20	6.92	69	4.61	11.13
9.25	6.33	6.96	68	4.65	11.27
9.50	6.47	6.99	68	4.68	11.41
9.75	6.60	7.02	68	4.71	11.54

Gutter	Bypass		
Velocity	Q	Spread	Depth
(ft/s)	(cfs)	(ft)	(in)
3.60	0.00	0.00	0.00
4.29	0.00	0.17	0.20
4.74	0.01	0.40	0.49
5.10	0.04	0.59	0.71
5.31	0.07	0.73	0.89
5.38	0.11	0.86	1.04
5.41	0.16	0.98	1.19
5.43	0.21	1.09	1.32
5.45	0.26	1.20	1.45
5.48	0.33	1.30	1.57
5.51	0.39	1.39	1.68
5.55	0.46	1.48	1.79
5.59	0.54	1.56	1.89
5.62	0.61	1.64	1.99
5.67	0.69	1.72	2.08
5.70	0.77	1.79	2.17
5.74	0.86	1.86	2.26
5.78	0.95	1.93	2.34
5.82	1.04	2.00	2.42
5.86	1.13	2.30	2.50
5.90	1.22	2.62	2.57
5.94	1.31	2.91	2.64
5.98	1.41	3.18	2.71
6.02	1.51	3.45	2.77
6.05	1.61	3.70	2.83
6.09	1.71	3.93	2.89
6.13	1.81	4.17	2.94
6.16	1.92	4.38	3.00
6.20	2.02	4.59	3.05
6.23	2.13	4.80	3.09
6.27	2.24	5.00	3.14
6.30	2.35	5.18	3.19
6.33	2.46	5.36	3.23
6.37	2.57	5.54	3.27
6.40	2.69	5.71	3.31
6.43	2.80	5.88	3.35
6.46	2.92	6.04	3.39
6.49	3.03	6.20	3.43
6.53	3.15	6.36	3.47

Inlet Report

Hydraflow Express Extension for Autodesk® AutoCAD® Civil 3D® by Autodesk, Inc.

Thursday, Nov 14 2019

NMDOT Combination Drop Inlet Type 2-B on Grade (5.16% slope)

Combination Inlet

Location	=	On grade
Curb Length (ft)	=	9.58
Throat Height (in)	=	5.06
Grate Area (sqft)	=	-0-
Grate Width (ft)	=	1.38
Grate Length (ft)	=	9.58

Gutter

Slope, Sw (ft/ft)	= 0.101
Slope, Sx (ft/ft)	= 0.020
Local Depr (in)	= 2.31
Gutter Width (ft)	= 2.00
Gutter Slope (%)	= 5.16
Gutter n-value	= 0.017


Calculations

Compute by: Q vs Depth
Max Depth (in) = 7

Highlighted

Q Total (cfs)	= 7.00
Q Capt (cfs)	= 5.08
Q Bypass (cfs)	= 1.92
Depth at Inlet (in)	= 6.62
Efficiency (%)	= 73
Gutter Spread (ft)	= 9.87
Gutter Vel (ft/s)	= 6.16
Bypass Spread (ft)	= 4.38
Bypass Depth (in)	= 3.00

All dimensions in feet



Q		Inlet		Gutter		Bypass			
Total	Captured	Depth	Efficiency	Depth	Spread	Velocity	Q	Spread	Depth
(cfs)	(cfs)	(in)	(%)	(in)	(ft)	(ft/s)	(cfs)	(ft)	(in)
0.25	0.25	3.69	100	1.38	1.14	3.81	0.00	0.00	0.00
0.50	0.50	4.10	100	1.79	1.48	4.54	0.00	0.00	0.00
0.75	0.75	4.39	100	2.08	1.72	5.02	0.00	0.00	0.00
1.00	1.00	4.63	100	2.32	1.92	5.39	0.00	0.00	0.00
1.25	1.19	4.83	95	2.52	2.42	5.67	0.06	0.67	0.81
1.50	1.39	5.00	93	2.69	3.13	5.78	0.11	0.83	1.01
1.75	1.59	5.15	91	2.84	3.73	5.81	0.16	0.97	1.18
2.00	1.77	5.27	89	2.96	4.25	5.84	0.23	1.10	1.34
2.25	1.94	5.38	86	3.07	4.71	5.86	0.31	1.23	1.49
2.50	2.11	5.48	84	3.17	5.13	5.89	0.39	1.35	1.64
2.75	2.26	5.57	82	3.26	5.50	5.92	0.49	1.46	1.77
3.00	2.41	5.66	80	3.35	5.85	5.95	0.59	1.57	1.90
3.25	2.55	5.73	79	3.42	6.17	5.99	0.70	1.67	2.03
3.50	2.69	5.81	77	3.50	6.48	6.02	0.81	1.77	2.14
3.75	2.82	5.88	75	3.57	6.76	6.06	0.93	1.86	2.26
4.00	2.95	5.94	74	3.63	7.03	6.10	1.05	1.95	2.36
4.25	3.08	6.00	72	3.69	7.28	6.14	1.17	2.17	2.46

Inlet Report

NMDOT Type 1-B On Grade 6% slope

Combination Inlet

Location	= On grade
Curb Length (ft)	= 5.58
Throat Height (in)	= 5.06
Grate Area (sqft)	= -0-
Grate Width (ft)	= 1.38
Grate Length (ft)	= 4.50

Gutter

Slope, Sw (ft/ft)	= 0.101
Slope, Sx (ft/ft)	= 0.020
Local Depr (in)	= 2.31
Gutter Width (ft)	= 2.00
Gutter Slope (%)	= 6.00
Gutter n-value	= 0.017


Calculations

Compute by:	Q vs Depth
Max Depth (in)	= 6

Highlighted

Q Total (cfs)	= 4.00
Q Capt (cfs)	= 2.95
Q Bypass (cfs)	= 1.05
Depth at Inlet (in)	= 5.94
Efficiency (%)	= 74
Gutter Spread (ft)	= 7.03
Gutter Vel (ft/s)	= 6.10
Bypass Spread (ft)	= 1.95
Bypass Depth (in)	= 2.36

All dimensions in feet



Inlet Report

NMDOT Combination Drop Inlet Type 2-B sag

Combination Inlet

Location	= Sag
Curb Length (ft)	= 9.58
Throat Height (in)	= 5.06
Grate Area (sqft)	= 13.22
Grate Width (ft)	= 1.38
Grate Length (ft)	= 9.58

Gutter

Slope, Sw (ft/ft)	= 0.101
Slope, Sx (ft/ft)	= 0.020
Local Depr (in)	= 2.31
Gutter Width (ft)	= 2.00
Gutter Slope (%)	= -0-
Gutter n-value	= -0-


Calculations

Compute by:	Q vs Depth
Max Depth (in)	= 7

Highlighted

Q Total (cfs)	= 9.00
Q Capt (cfs)	= 9.00
Q Bypass (cfs)	= -0-
Depth at Inlet (in)	= 7.04
Efficiency (%)	= 100
Gutter Spread (ft)	= 11.62
Gutter Vel (ft/s)	= 6.53
Bypass Spread (ft)	= -0-
Bypass Depth (in)	= -0-

All dimensions in feet



Q		Inlet		Gutter	
Total	Captured	Depth	Efficiency	Depth	Spread
(cfs)	(cfs)	(in)	(%)	(in)	(ft)
0.25	0.25	0.99	100	-1.32	0.42
0.50	0.50	1.54	100	-0.77	0.65
0.75	0.75	2.00	100	-0.31	0.84
1.00	1.00	2.39	100	0.08	1.01
1.25	1.25	2.75	100	0.44	1.16
1.50	1.50	3.08	100	0.77	1.30
1.75	1.75	3.27	100	0.96	1.38
2.00	2.00	3.43	100	1.12	1.45
2.25	2.25	3.71	100	1.40	1.57
2.50	2.50	3.98	100	1.67	1.68
2.75	2.75	4.24	100	1.93	1.79
3.00	3.00	4.50	100	2.19	1.90
3.25	3.25	4.74	100	2.43	2.02
3.50	3.50	4.86	100	2.55	2.52
3.75	3.75	4.97	100	2.66	3.00
4.00	4.00	5.09	100	2.78	3.48
4.25	4.25	5.20	100	2.89	3.95
4.50	4.50	5.31	100	3.00	4.41
4.75	4.75	5.42	100	3.11	4.86
5.00	5.00	5.53	100	3.22	5.30
5.25	5.25	5.63	100	3.32	5.74
5.50	5.50	5.73	100	3.42	6.17
5.75	5.75	5.83	100	3.52	6.59
6.00	6.00	5.93	100	3.62	7.00
6.25	6.25	6.03	100	3.72	7.41
6.50	6.50	6.13	100	3.82	7.82
6.75	6.75	6.23	100	3.92	8.22
7.00	7.00	6.32	100	4.01	8.61
7.25	7.25	6.41	100	4.10	9.00
7.50	7.50	6.51	100	4.20	9.39
7.75	7.75	6.60	100	4.29	9.77
8.00	8.00	6.69	100	4.38	10.15
8.25	8.25	6.78	100	4.47	10.52
8.50	8.50	6.87	100	4.56	10.89
8.75	8.75	6.95	100	4.64	11.25
9.00	9.00	7.04	100	4.73	11.62

