

Trip Generation Tables

Use	Units		Trip Generation							Peak Hour Trips			
			Weekday	AM Peak			PM Peak			AM Peak		PM Peak	
			Trips	Total	Enter	Exit	Total	Enter	Exit	In	Out	In	Out
ITE 538 Charter School (K-12)	1156	Students	N/A	1079	53%	47%	831	50%	50%	572	507	416	415
	948	Students (w/o Bus Students)	N/A	859	53%	47%	640	50%	50%	455	404	320	320

Notes:

ITE Trip Generation Manual Rates
Daily Rate: Weekday
Average Rate: N/A No Data Available
AM Peak: Peak Hour of Generator
Fitted Curve: $1.06(x)-146.78$ ($R^2 = 0.97$)
PM Peak: Peak Hour of Generator
Fitted Curve: $0.92(x)-232.86$ ($R^2 = 0.91$)