



City of Albuquerque

Planning Department
Development & Building Services Division

DRAINAGE AND TRANSPORTATION INFORMATION SHEET (DTIS)

Project Title: _____ Hydrology File # _____

Legal Description: _____

City Address, UPC, OR Parcel: _____

Applicant/Agent: _____ Contact: _____

Address: _____ Phone: _____

Email: _____

Applicant/Owner: _____ Contact: _____

Address: _____ Phone: _____

Email: _____

(Please note that a DFT SITE is one that needs Site Plan Approval & ADMIN SITE is one that does not need it.)

TYPE OF DEVELOPMENT: PLAT (#of lots) _____ RESIDENCE
DFT SITE ADMIN SITE

RE-SUBMITTAL: YES NO

DEPARTMENT: TRANSPORTATION HYDROLOGY/DRAINAGE

Check all that apply under Both the Type of Submittal and the Type of Approval Sought:

TYPE OF SUBMITTAL:

ENGINEER/ARCHITECT CERTIFICATION
PAD CERTIFICATION
CONCEPTUAL G&D PLAN
GRADING & DRAINAGE PLAN
DRAINAGE REPORT
DRAINAGE MASTER PLAN
CLOMR/LOMR
TRAFFIC CIRCULATION LAYOUT (TCL)
ADMINISTRATIVE
TRAFFIC CIRCULATION LAYOUT FOR DFT
APPROVAL
TRAFFIC IMPACT STUDY (TIS)
STREET LIGHT LAYOUT
OTHER (SPECIFY) _____

TYPE OF APPROVAL SOUGHT:

BUILDING PERMIT APPROVAL
CERTIFICATE OF OCCUPANCY **PERMANENT**
CONCEPTUAL TCL DFT APPROVAL
PRELIMINARY PLAT APPROVAL
FINAL PLAT APPROVAL
SITE PLAN FOR BLDG PERMIT DFT
APPROVAL
SIA/RELEASE OF FINANCIAL GUARANTEE
FOUNDATION PERMIT APPROVAL
GRADING PERMIT APPROVAL
SO-19 APPROVAL
PAVING PERMIT APPROVAL
GRADING PAD CERTIFICATION
WORK ORDER APPROVAL
CLOMR/LOMR
OTHER (SPECIFY) _____

DATE SUBMITTED: _____



TRAFFIC CERTIFICATION



I, Genevieve L. Donart, NMPE No. 15088 of the firm Isaacson & Arfman, Inc, hereby certify that this project is in substantial compliance with and in accordance with the design intent of the approved plan dated 03/09/2023. I further certify that I or someone under my direct supervision have personally visited the project site on 02/09/2024 and have determined by visual inspection that the survey data provided is representative of actual site conditions and is true and correct to the best of my knowledge and belief. This certification is submitted in support of a request for Permanent Occupancy.

The record information presented hereon is not necessarily complete and intended only to verify substantial compliance of the traffic aspects of this project. Those relying on the record document are advised to obtain independent verification of its accuracy before using it for any other purpose.

Genevieve L. Donart, PE

02/09/2024

Date



TRAFFIC CIRCULATION
LAYOUT APPROVED

Ernest Armano 3/9/2023
Signed Date

SOLID WASTE APPROVAL NOTE:
IF UPON FINAL INSPECTION OF THE REFUSE ENCLOSURE THE SOLID WASTE DEEMS THE REFUSE BINS INACCESSIBLE DUE TO THE SLOPE OF THE ENCLOSURE OR APPROACH, THE OWNER WILL PURCHASE AND MODIFY THE REFUSE BINS TO BRING THEM INTO COMPLIANCE.

SOLID WASTE APPROVAL DATE

KEYED NOTES

- EXISTING CURB & GUTTER TO REMAIN.
- EXISTING SIDEWALK TO REMAIN.
- ASPHALT PAVING, PER DETAIL ON SHEET CP-501.
- CONCRETE PAVING, PER DETAIL ON SHEET CP-501.
- PCC MEDIAN CURB AND GUTTER, PER DETAIL ON SHEET CP-501.
- PCC FLATWORK, PER DETAIL ON SHEET CP-501.
- 4" WHITE STRIPE IN TRAFFIC PAINT TYP.
- CROSS WALK / EXIT LANE STRIPING, PER DETAIL ON SHEET CP-501.
- DIRECTION ARROW, PER DETAIL ON SHEET CP-501.
- ADA ACCESSIBLE RAMP, PER DETAIL ON SHEET CP-501.
- ADA PARKING, PER DETAIL ON SHEET CP-501.
- ADA PARKING SIGNAGE, PER DETAIL ON SHEET CP-501.
- REFUSE ENCLOSURE, SEE ARCHITECTURAL PLANS.
- LANDSCAPING, SEE LANDSCAPE PLANS.
- BIKE RACK, SEE ARCHITECTURAL PLANS FOR DETAIL.
- "ONE WAY" PAVEMENT MARKINGS.
- PARKING BUMPER.
- MINI CLEAR SIGHT TRIANGLE. SEE GENERAL NOTE E.
- DRIVE THRU EXIT SIGNAGE, SEE ARCHITECTURAL FOR DETAIL.
- DO NOT ENTER SIGNAGE PER DETAIL ON SHEET CP-501.
- ONE-WAY SIGN PER DETAIL ON SHEET CP-501.
- MOTORCYCLE PARKING, SIGNAGE PER DETAIL ON SHEET CP-501.
- ALONG DASHED LINE, PAINT FACE AND TOP OF CURB RED AND PAINT WHITE STENCILLED LETTERING ON TOP OF CURB "NO PARKING" AND "FIRE LANE" ALTERNATING AT 30 FT. O.C.
- STANDARD CURB & GUTTER, PER COA STD DWG 2415A.
- DRIVEPAD PER COA STD DWG 2426.
- PUBLIC SIDEWALK (WIDTH PER PLAN) PER COA STD DWG 2430.
- NEW ADA RAMP PER COA STD DWG 2441.
- STOP SIGN PER DETAIL ON SHEET CP-501.
- EXISTING CMU WALL TO REMAIN. CONTRACTOR TO PAINT CHARCOL GRAY (OR OWNER APPROVED ALTERNATE, COLOR TO MATCH REFUSE/BUILDING) WITH ANTI-GRAFFITI PRIMER. CONTRACTOR TO REMOVE BARBED WIRE WHERE APPLICABLE.
- DRIVE THRU SCREENING. 3' SOLID CMU WALL OR APPROVED LANDSCAPING, TO BE DETERMINED BY OWNER.

PROJECT INFORMATION


PARKING CALCULATION (IDO Table 5-5-1):
8 SPACES PER 1,000 GFA = 8 PARKING SPACES REQUIRED
TOTAL PARKING REQUIRED= 8
TOTAL PARKING PROVIDED = 12 (including 1 ADA Van space)

DRIVETHRU QUEUING SPACES REQUIRED PER IDO TABLE 5-5-8=12
DRIVETHRU QUEUING SPACES PROVIDED=12+

MOTORCYCLE PARKING REQUIRED = 1 (IDO Table 5-5-4)
MOTORCYCLE PARKING PROVIDED = 1

BICYCLE PARKING REQUIRED = 3 (IDO Table 5-5-5)
BICYCLE PARKING PROVIDED = 3 (3 bicycles per 1 bike rack)

VICINITY MAP




GENERAL NOTES

- DIMENSIONS ARE TO FACE OF CURB, OR WALL, OR EDGE OF PAVEMENT UNLESS OTHERWISE NOTED.
- ALL CURB RADII ARE 2' UNLESS OTHERWISE NOTED.
- CURBS AND ACCESSIBLE RAMPS WILL BE DESIGNED AND BUILT ACCORDING TO THE CITY OF ALBUQUERQUE STANDARDS.
- STREETS, PARKING SPACES AND ASSOCIATED DRIVES TO BE ASPHALT UNLESS NOTED OTHERWISE.
- LANDSCAPING AND SIGNAGE WILL NOT INTERFERE WITH CLEAR SIGHT REQUIREMENTS. THEREFORE, SIGNS, WALLS, TREES, AND SHRUBBERY BETWEEN 3 AND 8 FEET TALL (AS MEASURED FROM THE GUTTER PAN) WILL NOT BE ACCEPTABLE IN THE CLEAR SIGHT TRIANGLE.
- ALL BROKEN OR CRACKED SIDEWALK MUST BE REPLACED WITH SIDEWALK AND CURB & GUTTER. NEW CURB & GUTTER TO BE CONSTRUCTED PER COA STD DWG 2415A. NEW SIDEWALK TO BE CONSTRUCTED PER COA STD DWG 2430.
- FIVE WORKING DAYS PRIOR TO ANY EXCAVATION, THE CONTRACTOR MUST CONTACT NEW MEXICO ONE CALL SYSTEM (805-260-1990) FOR LOCATION OF EXISTING UTILITIES.
- PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL EXCAVATE AND VERIFY THE HORIZONTAL AND VERTICAL LOCATIONS OF ALL OBSTRUCTIONS. SHOULD A CONFLICT EXIST, THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY SO THAT THE CONFLICT CAN BE RESOLVED WITH A MINIMUM AMOUNT OF DELAY.
- CONTRACTOR TO VERIFY LOCATION OF EXISTING CURB, ASPHALT, AND CONCRETE PAVEMENT TIE-IN LOCATIONS AND MATCH EXISTING WITH SMOOTH TRANSITION. NOTIFY ENGINEER OF ANY DISCREPANCIES.
- SEE CD-100 - DEMOLITION PLAN FOR EXTENTS OF ASPHALT, CURB, AND SIDEWALK REMOVAL.


LEGEND

- EXISTING CURB AND GUTTER
- PROPOSED CURB AND GUTTER
- ADA PATHWAY (6' TYP., CLEAR PATH)
- DRIVE THRU QUEUING SPACE (8'x20')
- ASPHALT PAVING SECTION
- PCC PAVING SECTION
- POST MOUNTED SIGN




Isaacson & Arfman, Inc.
Civil Engineering Consultants

128 Monroe Street NE
Albuquerque, NM 87108
505-268-8828 | www.iacivil.com



© 2020 Isaacson & Arfman, Inc.
This design, calculations, and concepts are owned by and remain the property of Isaacson & Arfman, Inc. and no part thereof shall be utilized by any person, firm or corporation for any purpose whatsoever except with the written permission of Isaacson & Arfman, Inc.

Engineer 02/15/2023



Dutch Bros. Coffee
10001 Central Ave NE
Accelerated
DEVELOPMENT SERVICES

DESIGN	ISSUE	PROJECT NUMBER	FILE	DRAWN BY	CHECKED BY	DATE
DEVELOPMENT		IA 2528				XX

No	Date	Description

SHEET TITLE

TCL & PAVING PLAN

SHEET NUMBER

CP-101