# CITY OF ALBUQUERQUE

Planning Department Alan Varela, Director



Mayor Timothy M. Keller

December 29, 2023

David Soule, P.E. Rio Grande Engineering P.O. Box 93924 Albuquerque, NM 87199

RE: 13701 Covered Wagon Ave SE Grading and Drainage Plan Engineer's Stamp Date: 12/19/23 Hydrology File: L23D014M

Dear Mr. Soule:

Based upon the information provided in your submittal received 12/19/2023, the Grading and Drainage Plan is approved for Building Permit and Grading Permit. Since this site is relatively flat and grades to the road, a pad certification is not needed for this project. Please attach a copy of this approved plan in the construction sets for Building Permit processing along with a copy of this letter.

Albuquerque

#### PRIOR TO CERTIFICATE OF OCCUPANCY:

NM 87103
1. Engineer's Certification, per the DPM Part 6-14 (F): Engineer's Certification Checklist For Non-Subdivision is required.

www.cabq.gov

If you have any questions, please contact me at 924-3995 or <u>rbrissette@cabq.gov</u>.

Sincerely,

Renée C. Brissette

Renée C. Brissette, P.E. CFM Senior Engineer, Hydrology Planning Department



## **City of Albuquerque**

Planning Department Development & Building Services Division

#### DRAINAGE AND TRANSPORTATION INFORMATION SHEET (DTIS)

Project Title:	Hydrology File #
City Address, UPC, OR Parcel:	
Applicant/Agent:	Contact:
	Phone:
Email:	
Applicant/Owner:	Contact:
Address:	Phone:
Email:	
(Please note that a DFT SITE is one that need	ds Site Plan Approval & ADMIN SITE is one that does not need it.)
TYPE OF DEVELOPMENT: PLAT	(#of lots) RESIDENCE
DFT	SITE ADMIN SITE
RE-SUBMITTAL: YES NO	
DEPARTMENT: TRANSPORTA	TION HYDROLOGY/DRAINAGE
Check all that apply under Both the Type	of Submittal and the Type of Approval Sought:
TYPE OF SUBMITTAL:	<b>TYPE OF APPROVAL SOUGHT:</b>
ENGINEER/ARCHITECT CERTIFICA	TION BUILDING PERMIT APPROVAL
PAD CERTIFICATION	CERTIFICATE OF OCCUPANCY
CONCEPTUAL G&D PLAN	CONCEPTUAL TCL DFT APPROVAL
GRADING & DRAINAGE PLAN	PRELIMINARY PLAT APPROVAL
DRAINAGE REPORT	FINAL PLAT APPROVAL
DRAINAGE MASTER PLAN	SITE PLAN FOR BLDG PERMIT DFT
CLOMR/LOMR	APPROVAL
TRAFFIC CIRCULATION LAYOUT (7	SIA/RELEASE OF FINANCIAL GUARANTEE
ADMINISTRATIVE	FOUNDATION PERMIT APPROVAL
TRAFFIC CIRCULATION LAYOUT F APPROVAL	OR DFT GRADING PERMIT APPROVAL
TRAFFIC IMPACT STUDY (TIS)	SO-19 APPROVAL
STREET LIGHT LAYOUT	PAVING PERMIT APPROVAL
OTHER (SPECIFY)	GRADING PAD CERTIFICATION
omer(billen i)	WORK ORDER APPROVAL
	CLOMR/LOMR
	OTHER (SPECIFY)

DATE SUBMITTED: \_\_\_\_

								100-Year, 6-hr.			100 yr 10-day			
Basin	Area	Area	Treat	ment A	Trea	atment B	Treat	ment C	Treat	ment D	Weighted E	Volume	Flow	Volume
	(sf)	(acres)	%	(acres)	%	(acres)	%	(acres)	%	(acres)	(ac-ft)	(ac-ft)	cfs	(ac-ft)
EXISTING	3927.00	0.090	100%	0.0902	0%	0.000	0%	0.000	0%	0.000	0.760	0.006	0.19	0.006
PROPOSED	3927.00	0.090	0%	0	20%	0.018	26%	0.023	54%	0.049	2.306	0.017	0.36	0.019

Weighted E = Ea\*Aa + Eb\*Ab + Ec\*Ac + Ed\*Ad / (Total Area)

Volume = Weighted D \* Total Area


Equations:

Flow = Qa \* Aa + Qb \* Ab + Qc \* Ac + Qd \* Ad

Where for 100-yea	ar, 6-hour storm(zone2) Ea= 0.76 Eb= 0.95 Ec= 1.2 Ed= 3.34	Qa= 2.09 Qb= 2.73 Qc= 3.41 Qd= 4.78	
Developed Condit	ons		100-YEAR,
EXI	STING DISCHARGE		0.19 CF
PRO	0.36 CF		
INC	REASE		0.17 CF

This site isone of the last vacant lots in an existing subdivision. The subdivision was analyzed and approved with drainage file E21-D16. The drainge file appears to be incomplete, yet all the lots free discharge. Therefore we believe this lot should be allowed to free discharge.

Drainage patterns will remain as historical and drain to the adjacent roadways. No upland flows impact this site



 $\times$ 

5693.12 ×

5692.7

<\_/

TBM ELEV= 5694.25 -

### **CAUTION:**

EXISTING UTILITIES ARE NOT SHOWN. IT SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO CONDUCT ALL NECESSARY FIELD INVESTIGATIONS PRIOR TO ANY EXCAVATION TO DETERMINE THE ACTUAL LOCATION OF UTILITIES & OTHER IMPROVEMENTS.

### **EROSION CONTROL NOTES:**

1. CONTRACTOR IS RESPONSIBLE FOR OBTAINING A TOPSOIL DISTURBANCE PERMIT PRIOR TO BEGINNING WORK.


2. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING RUN-OFF ON SITE DURING CONSTRUCTION.


3. CONTRACTOR IS RESPONSIBLE FOR CLEANING ALL SEDIMENT THAT GETS INTO EXISTING RIGHT-OF-WAY.

4. REPAIR OF DAMAGED FACILITIES AND CLEANUP OF SEDIMENT ACCUMULATIONS ON ADJACENT PROPERTIES AND IN PUBLIC FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR.

5. ALL EXPOSED EARTH SURFACES MUST BE PROTECTED FROM WIND AND WATER EROSION PRIOR TO FINAL ACCEPTANCE OF ANY PROJECT.







Rio Grande

Engineering

PO BOX 93924 ALBUQUERQUE, NM 87199 (505) 321-9099

"G<sub>F</sub>)

12/19/23

DAVID SOULE P.E. #14522

SHEET #

JOB #

\_\_\_\_\_

C1

