



2 - #4  
Around well  
Steel bars  
AD

CHIP CONCRETE—MAINTAIN EX. REBAR  
BEND EX. REBAR INTO NEW  
PENETRATION COLLAR

CUT PIPE FLUSH  
GRIND EDGE SMOOTH  
W/ 1/4" TO 1/2" RADIUS

SAWCUT 1 1/2" DEEP FOR  
FOR NEAT LINE

PROVIDE FLEXIBLE, GASKETED JOINT  
@ OUTSIDE FACE OF WALL  
CONCRETE ENCASE 24" RCP BELL  
W/ ~~LEAN FILL~~ *CONCRETE* *AD*  
CONTRACTOR SHALL MINIMIZE  
REBAR CUT AND WILL MAINTAIN BARS UNTIL EXPOSED  
AND BEND EX. BARS INTO BELL  
ENCASEMENT

PENETRATE EX. CITY CHANNEL  
3' ABOVE EX. FL  
INV=5610.83

Ensure Solid  
Bedding Under Pipes  
Beyond Encasement.  
(May need leanfill  
to spring line on  
first section of  
pipe)

SECTION A-A  
NTS—Prior to cutting wall, pouring concrete, contractor shall notify the storm drain