


DRAINAGE REPORT
for
BROADWAY INDUSTRIAL CENTER



9-12-97

Prepared For
Broadway Developement Company
PO Box 10005
Albuquerque, NM 87184

September 1997

TABLE OF CONTENTS

Report

- *Cover Page*
- *Drainage Information Sheet*
- *Vicinity map (M-14)*
- *Purpose*
- *Legal Description*
- *Existing Conditions*
- *Proposed Management Plan*
- *Summary of Sector Plan flows to Broadway*

Calculations and Data

- *Table 2 — Summary of Existing Conditions Hydrology*
- *AHYMO Summary*
- *AHYMO Output*
- *AHYMO Data*
- *Street Capacity Plate 22.3 D-2*
- *Grate Capacity Plate 22.3 D-6*
- *Exerpts from South Broadway Sector Drainage Management Plan*

Maps

- *Current FIRM — Existing Conditions Basin Map*
- *Sector Plan Basin Map*

Pockets

- *Grading and Drainage Master Plan, Sheet 1 of 1*

DRAINAGE INFORMATION SHEET

PROJECT TITLE:

Broadway Industrial Center

ZONEATLAS/DRNG,FILE#

M-14

DRB#:

97-217

EPC#

WORK ORDER#:

LEGAL DESCRIPTION:

See Page 1 of Report or Master Grading Plan

CITY ADDRESS:

2600 Broadway Blvd. NE

ENGINEERING FIRM:

Mark Goodwin & Associates, PA

CONTACT:

James D. Hughes, P.E

ADDRESS:

P.O Box 90606 Albuq., NM 87199

PHONE:

(505) 828-2200

OWNER

Broadway Developement Corporation

CONTACT:

Ted Waterman

ADDRESS:

P O. Box 10005 Albuq., NM 87184

PHONE:

(505) 266-6693

ARCHITECT.

N/A

CONTACT:

ADDRESS

PHONE

SURVEYOR

Aldrich Land Surveying, Inc.

CONTACT:

Tim Aldrich

ADDRESS

P O. Box 30701 Albuq , NM 87107

PHONE

(505) 884-1990

CONTACTOR

CONTACT

ADDRESS:

PHONE

TYPE OF SUBMITTAL:

X

DRAINAGE REPORT

DRAINAGE PLAN

CONCEPTUAL GRADING & DRAINAGE PLAN

X

GRADING PLAN

X

EROSION CONTROL

ENGINEER'S CERTIFICATION

OTHER

PRE-DESIGN MEETING:

YES

X

NO

COPY PROVIDED

CHECK TYPE OF APPROVAL SOUGHT:

SKETCH PLAT APRROVAL

X

PRELIMINARY PLAT APPROVAL

S. DEV. PLAN FOR SUB'D APPROVAL

S. DEV. PLAN FOR BLDG PERMIT APPROVAL

SECTOR PLAN APPROVAL

X

FINAL PLAT APPROVAL

FOUNDATION PERMIT APPROVAL

BUILDING PERMIT APPROVAL

CERTIFICATION OF OCCUPANCY APPROVAL

X

GRADING PERMIT APPROVAL

PAVING PERMIT APPROVAL

S.A.D. DRAINAGE REPORT

DRAINAGE REQUIREMENTS

OTHER

DATE SUBMITTED.

BY. James D Hughes, P E.

PURPOSE

The purpose of this report is to present the Drainage Management and Grading Plan for final plat and Work Order approvals for the proposed Broadway Industrial Center.

LEGAL DESCRIPTION

A tract of land situate within Sections 28, 29, 32 and 33, Township 10 North, Range 3 East, New Mexico Principal Meridian, City of Albuquerque, Bernalillo County, New Mexico, being a portion of Tracts A and B, McKinney-Apodaca Area as the same is shown and designated on said plat filed for record in the office of the County Clerk of Bernalillo County, New Mexico on January 27, 1953, in volume C2, folio 143, together with all of Tract A, Land of Gordon Zucht as the same is shown and designated on said plat filed for record in the office of the County Clerk of Bernalillo County, New Mexico on June 8, 1977, in volume A6, folio 58, together with a portion of Parcel O, Lands of Schwartzman Packing Company as the same is shown and designated on said plat filed for record in the office of the County Clerk of Bernalillo County, New Mexico on April 17, 1961, in volume D2, folio 133, together with a remaining portion of Small Holding Claim File Number 2534 and 2535, Plat of Small Holding Claims as the same is shown and designated on said plat filed in the General Land Office, in Santa Fe, New Mexico on December 5, 1895, and together with a portion of Vacated High Street and Arno Street S.E. and containing 60.8423 acres, more or less.

EXISTING CONDITIONS

This 60.84 acre site is undeveloped with the exception of a 5.3 acre towing company. This master drainage plan also covers 9.9 additional acres north of the subdivision which are currently undeveloped and owned by others. All 7.07 acres covered by the plan generally drains from east to west at approximately 2.5% slope to Broadway via surface drainage. The southerly portion of the site, including existing basins 109 through 115, drains through an existing residential development before it gets to Broadway. Several small upstream off-site basins drain into this property via surface sheet drainage, and four existing culverts under Interstate 25 produce small concentrations of surface drainage at the upstream edge of the site. The AMAFCA owned property discharges concentrated surface drainage into this site at two locations (basins 109 & 110) at the southerly upstream edge of the site. The South Diversion Channel forms the upstream edge of the drainage basin boundaries cutting off all approaching flows from the east and diverting them south. An existing 48" RCP storm sewer runs through the middle of the site from east to west and carries no flow in it under existing conditions because the south diversion channel cut off the upstream watershed, and there are no inlets to the storm sewer between Broadway Ave and the South Diversion Channel.

This development is within the previously approved South Broadway Sector Drainage Management Plan which established 145.70 cfs as the developed flow from this 70.7 acre Master Planed Area. The sector plan used methods of predicting runoff that are no longer acceptable to the City of Albuquerque. The new methodology, AHYMO, predicts substantially higher flows, thus indicating that the capacity of the existing hydraulic structures will be exceeded unless peak flows are decreased by detention ponds through out the sector plan area. The Sector Drainage Management Plan further identifies an existing downstream floodplain in San Jose Ave, and proposes a storm sewer diversion project in Broadway Blvd. and Bethel Ave., to divert both the flows from this site and the flows approaching in Broadway Blvd. from the north of this site, around the flood plain and directly into the San Jose Drain. The City has already constructed several of the other projects identified by the sector plan to reduce flows from the north, and has programming in the current 10 year plan for a \$300,000.00 Capital Bond Improvement in 1999, a \$1.5 million bond in 2003 and another \$1.5 million bond in 2005 for this diversion project and the other projects identified in the sector plan.

PROPOSED MANAGEMENT PLAN

Private temporary retention ponds are to be constructed on each individual lot so that no developed drainage will be added to the downstream floodplain in San Jose Ave. It will be the responsibility of the individual lot owners to convey the surface drainage from the existing upstream off-site basins through their site and to size the individual ponds to accommodate both the existing off-site and proposed on-site drainage. After the City constructs the storm sewer diversion in Broadway Blvd and Bethel Ave to the San Jose Drain, the temporary retention requirement will be dropped and replaced with a permanent private detention requirement in which each individual lot will only be allowed to discharge at 1.666 cfs per acrea in accordance with the Sector Drainage Management Plan, and this master drainage management plan.

The southerly portion of this site that drained through the existing downstream residential development between this site and Broadway Blvd is to be diverted on-site directly to Broadway Blvd. The increased drainage area to Broadway Blvd has been factored into the allowable discharge rate so that the total peak drainage from this site to Broadway will be the same as that identified in the Sector Drainage Management Plan, and the existing drainage problems in the downstream residential development will thereby be improved.

The public streets will be allowed free discharge of 18.26 cfs into the existing 48" storm sewer at Broadway Blvd. Additionally the 3.5 acre portion of Basin 120 will be allowed Free Discharge of 15.44 cfs to Wheeler Ave, and the remainder of the Master Plan area will compensate for increased flow. The only grading associated with this development is that of the public streets. The responsibility for grading of the lots is being left to the individual private lot owners, at the time of Building Permit.

Summary of Sector Plan Flows to Broadway

Basin #	Area (sq mi)		100 yr. Flow (cfs)	
	Master Plan Contribution	Total from sector Plan	Total from Sector Plan	Prorated Contribution from Master Plan
109 ⁽¹⁾	0.0312	0.1042	169	50.6
202	0.0304	0.0820	84	31.1
700	0.0483	0.0565	134	114.6
Total at Broadway (excluding basin 109)				145.70 cfs

Free Discharge from onsite master planed Right of Ways is 18.26 cfs from 4.14 Acres at 90% impervious. Additional free discharge from the 3.5 acrea undeveloped portion of Basin 120 at 90% impervious is 15.44 cfs. So the remaining allowable discharge is 112.00 cfs from the remaining 67.24 acres of Private Property:

1.666 cfs/ac.

TABLE 2 — SUMMARY OF EXISTING CONDITIONS HYDROLOGY
(from AHYMO and Equation 9 and Table 3 of DPM Sec. 22.2)

Basin No.	Area (Ac.)	Area (Sq. Mi.)	<i>Cumulative</i> ~~Tc~~ (Hr.)	Land Treatments (%)				100 Year	
				A	B	C	D	Increm. Q (cfs)	Cumulative Q(cfs)
101	1.81	0.00283	—	0	40	0	60	6.60	
102	1.93	0.00302	103	0	40	0	60	7.04	19.20
103	3.79	0.00592	—	0	0	90	10	12.16	
104	4.03	0.00630	—	0	0	90	10	12.94	
105	3.25	0.00508		0	0	70	30	11.45	
106	4.42	0.00691	105	0	0	90	10	14.19	25.64
107	2.53	0.00395	104	0	0	70	30	8.90	21.84
108	1.26	0.00197	101, 102, 103	0	0	70	30	4.45	30.25
109	3.37	0.00527	—	0	0	90	10	10.83	
110	1.99	0.00310	—	0	0	90	10	6.38	
111	1.99	0.00311	110	90	0	10	0	3.20	9.50
112	0.30	0.00047	—	90	0	10	0	0.49	
113	1.56	0.00244	—	100	0	0	0	2.30	
114	9.15	0.01430	109	90	0	10	0	14.69	25.28
115	10.11	0.01580	—	90	0	10	0	16.22	
116	29.49	0.04608	101-104, 107, 108	90	0	10	0	47.30	98.28
117	4.63	0.00723	—	60	0	40	0	9.37	
118	3.61	0.00564	105, 106	60	0	40	0	7.31	32.86
119	5.12	0.00800	117	95	0	0	5	8.28	17.65
120	9.50	0.01484	117, 119	37	3	3	57	31.36	48.76
121 ⁽²⁾	27.6	0.04313	105, 106, 118	0	30	10	60	86.08	116.09
122	1.87	0.00292	101-104, 107, 108, 116	0	30	10	60	6.97	105.25
152 ⁽²⁾	83.51	0.13048	162	0	45	20	35 ⁽¹⁾	253.89	285.89
153 ⁽²⁾	32.14	0.05022	153, 162, 163	0	45	15	40 ⁽¹⁾	101.21	476.00
162	10.62	0.01659	—	0	40	35	25	32.76	
163	33.86	0.05291	—	0	40	30	30	107.13	

Basin No.	Area (Ac.)	Area (Sq.Mi.)	Tc (hr.)	Land Treatments (%)				100 Year	
				A	B	C	D	Increm. Q (cfs)	Cumulative Q(cfs)
200 ⁽²⁾	19.23	0.03004	152, 153, 162, 163	0	45	15	40	59.95	513.06
202	Sum of 120 & 121		105, 106, 117-121, 152, 153, 162, 163	—	—	—	—	—	164.14
700	Cummulative @ 122		101-108, 116-122, 152, 153, 162, 163, 200	—	—	—	—	—	769.60


100 Year Precipitation

(from Figures D, E and F and Eq. 28 of DPM 22.2)


$$P_{60} = 1.97", P_{360} = 2.29", P_{1440} = 2.65", P_{10\text{days}} = 10.0 - [24.9 / (2.65")^{1.4}] = 3.64"$$

- (1) Basin 152 has approximately 400 lots (4.9 du/ac) which, per DPM 22.2 eqn 4, suggests that 49% impervious may be appropriate instead of the 35% used in the sector drainage management plan. Basin 153 has approximately 150 lots (4.6 du/ac) so 47% impervious may be appropriate instead of the 40% used in the sector plan.
- (2) Tp for sector plan is 0.187 hr for basin 121 and 0.147 for basin 152, 0.1412 for basin 153, and 0.1453 hr for basin 200, and less than the AHYMO default minimum for the remaining basins so 0.133 is used for all other existing basins.
- (3) Existing Development within basin #120 is at about 90% impervious for 6.0 acres and 0.% impervious for the remaining 3.5 acres which has not yet developed. After development the 3.5 ac. will be allowed Free Discharge at 15.44 cfs at 90% impervious to Wheeler Ave. and the remainder of the Master Plan Area will compensate for the increased flow.


GRATING CAPACITIES FOR TYPE "A", "C" and "D"



GRATING & GUTTER PLAN



TYPICAL HALF STREET SECTION
(ABOVE BASIN)



AHYMO SUMMARY TABLE (AHYMO194) - AMAFCA Hydrologic Model - January, 1994
 INPUT FILE = BROD99.DAT

RUN DATE (MON/DAY/YR) = 08/25/1997
 USER NO. = M_GOODWN.I01

COMMAND	HYDROGRAPH IDENTIFICATION	FROM ID NO.	TO ID NO.	AREA (SQ MI)	PEAK DISCHARGE (CFS)	RUNOFF VOLUME (AC-FT)	RUNOFF (INCHES)	TIME TO PEAK (HOURS)	CFS PER ACRE	PAGE = 1 NOTATION
START										TIME= .00
RAINFALL TYPE= 1										RAIN6= 2.290
COMPUTE NM HYD	101.00	-	1	.00283	6.60	.231	1.52996	1.499	3.644	PER IMP= 60.00
COMPUTE NM HYD	102.00	-	2	.00302	7.04	.246	1.52996	1.499	3.643	PER IMP= 60.00
COMPUTE NM HYD	103.00	-	3	.00592	12.16	.373	1.18095	1.499	3.209	PER IMP= 10.00
ADD HYD	102.10	2& 3	2	.00894	19.20	.619	1.29878	1.499	3.356	
COMPUTE NM HYD	104.00	-	4	.00630	12.94	.397	1.18095	1.499	3.209	PER IMP= 10.00
COMPUTE NM HYD	105.00	-	5	.00508	11.45	.373	1.37541	1.499	3.521	PER IMP= 30.00
COMPUTE NM HYD	106.00	-	6	.00691	14.19	.435	1.18095	1.499	3.209	PER IMP= 10.00
ADD HYD	106.10	5& 6	6	.01199	25.64	.808	1.26329	1.499	3.341	
COMPUTE NM HYD	107.00	-	7	.00395	8.90	.290	1.37541	1.499	3.522	PER IMP= 30.00
ADD HYD	107.10	4& 7	7	.01025	21.84	.687	1.25583	1.499	3.330	
COMPUTE NM HYD	108.00	-	8	.00197	4.45	.145	1.37541	1.499	3.530	PER IMP= 30.00
ADD HYD	108.10	1& 8	8	.00480	11.05	.375	1.46642	1.499	3.597	
ADD HYD	108.20	2& 8	8	.01374	30.25	.995	1.35735	1.499	3.440	
COMPUTE NM HYD	109.00	-	9	.00527	10.83	.332	1.18095	1.499	3.210	PER IMP= 10.00
COMPUTE NM HYD	110.00	-	10	.00310	6.38	.195	1.18095	1.499	3.214	PER IMP= 10.00
COMPUTE NM HYD	111.00	-	11	.00311	3.20	.090	.54195	1.532	1.607	PER IMP= .00
ADD HYD	111.10	10&11	11	.00621	9.50	.285	.86088	1.499	2.390	
COMPUTE NM HYD	112.00	-	12	.00047	.49	.014	.54195	1.532	1.628	PER IMP= .00
COMPUTE NM HYD	113.00	-	13	.00244	2.30	.065	.49889	1.532	1.473	PER IMP= .00
COMPUTE NM HYD	114.00	-	14	.01430	14.69	.413	.54195	1.532	1.605	PER IMP= .00
ADD HYD	114.10	14& 9	14	.01957	25.28	.745	.71401	1.532	2.018	
COMPUTE NM HYD	115.00	-	15	.01580	16.22	.457	.54195	1.532	1.604	PER IMP= .00
COMPUTE NM HYD	116.00	-	16	.04608	47.30	1.332	.54195	1.532	1.604	PER IMP= .00
ADD HYD	116.70	7&16	16	.05633	68.62	2.018	.67185	1.532	1.903	
ADD HYD	116.80	16& 8	16	.07007	98.28	3.013	.80627	1.499	2.192	
COMPUTE NM HYD	117.00	-	17	.00723	9.37	.265	.68597	1.532	2.026	PER IMP= .00
COMPUTE NM HYD	118.00	-	18	.00564	7.31	.206	.68597	1.532	2.026	PER IMP= .00
ADD HYD	118.10	6&18	18	.01763	32.86	1.014	1.07860	1.499	2.912	
COMPUTE NM HYD	119.00	-	19	.00800	8.28	.246	.57675	1.532	1.617	PER IMP= 5.00
ADD HYD	119.10	17&19	19	.01523	17.65	.511	.62857	1.532	1.811	
COMPUTE NM HYD	120.00	-	20	.01484	41.43	1.523	1.92450	1.499	4.363	PER IMP= 90.00
ADD HYD	120.10	19&20	20	.03007	58.84	2.034	1.26812	1.499	3.057	
COMPUTE NM HYD	121.00	-	21	.04313	86.08	3.588	1.55983	1.565	3.118	PER IMP= 60.00
ADD HYD	121.10	18&21	21	.06076	116.09	4.602	1.42019	1.532	2.985	
COMPUTE NM HYD	122.00	-	22	.00292	6.97	.243	1.55983	1.499	3.728	PER IMP= 60.00
ADD HYD	122.10	16&22	22	.07299	105.25	3.256	.83641	1.499	2.253	
COMPUTE NM HYD	152.00	-	1	.13048	266.01	9.480	1.36223	1.532	3.185	PER IMP= 45.00
COMPUTE NM HYD	153.00	-	2	.05022	103.56	3.649	1.36223	1.532	3.222	PER IMP= 45.00
COMPUTE NM HYD	162.00	-	3	.01659	32.76	1.043	1.17826	1.499	3.085	PER IMP= 25.00
COMPUTE NM HYD	163.00	-	4	.05291	107.13	3.465	1.22797	1.499	3.164	PER IMP= 30.00
COMPUTE NM HYD	200.00	-	5	.03004	59.95	2.102	1.31174	1.532	3.118	PER IMP= 40.00
ADD HYD	152.10	1& 3	1	.14707	298.12	10.522	1.34147	1.532	3.167	
ADD HYD	153.90	2& 4	2	.10313	210.53	7.114	1.29334	1.499	3.190	

ADD HYD	153.10	1& 2	1	.25020	506.49	17.636	1.32163	1.532	3.163
ADD HYD	200.10	1& 5	1	.28024	566.43	19.737	1.32057	1.532	3.158
ADD HYD	202.00	20&21	2	.09083	173.42	6.636	1.36985	1.532	2.983
ADD HYD	202.10	1& 2	1	.37107	739.86	26.373	1.33263	1.532	3.115

COMMAND	HYDROGRAPH IDENTIFICATION	FROM ID NO.	TO ID NO.	AREA (SQ MI)	PEAK DISCHARGE (CFS)	RUNOFF VOLUME (AC-FT)	RUNOFF (INCHES)	TIME TO PEAK (HOURS)	CFS PER ACRE	PAGE = 2 NOTATION
ADD HYD FINISH	700.10	1&22	1	.44406	844.64	29.629	1.25107	1.532	2.972	

AHYMO SUMMARY TABLE (AHYMO194) - AMAFCA Hydrologic Model - January, 1994
 INPUT FILE = broad99.dat

RUN DATE (MON/DAY/YR) =09/11/1997
 USER NO. = M_GOODWN.101

COMMAND	HYDROGRAPH IDENTIFICATION	FROM ID NO.	TO ID NO.	AREA (SQ MI)	PEAK DISCHARGE (CFS)	RUNOFF VOLUME (AC-FT)	RUNOFF (INCHES)	TIME TO PEAK (HOURS)	CFS PER ACRE	PAGE = 1 NOTATION
START										TIME= .00
RAINFALL TYPE= 1										RAIN6= 2.290
COMPUTE NM HYD	101.00	-	1	.00283	6.60	.231	1.52996	1.499	3.644	PER IMP= 60.00
COMPUTE NM HYD	102.00	-	2	.00302	7.04	.246	1.52996	1.499	3.643	PER IMP= 60.00
COMPUTE NM HYD	103.00	-	3	.00592	12.16	.373	1.18095	1.499	3.209	PER IMP= 10.00
ADD HYD	102.10	2& 3	2	.00894	19.20	.619	1.29878	1.499	3.356	
COMPUTE NM HYD	104.00	-	4	.00630	12.94	.397	1.18095	1.499	3.209	PER IMP= 10.00
COMPUTE NM HYD	105.00	-	5	.00508	11.45	.373	1.37541	1.499	3.521	PER IMP= 30.00
COMPUTE NM HYD	106.00	-	6	.00691	14.19	.435	1.18095	1.499	3.209	PER IMP= 10.00
ADD HYD	106.10	5& 6	6	.01199	25.64	.808	1.26329	1.499	3.341	
COMPUTE NM HYD	107.00	-	7	.00395	8.90	.290	1.37541	1.499	3.522	PER IMP= 30.00
ADD HYD	107.10	4& 7	7	.01025	21.84	.687	1.25583	1.499	3.330	
COMPUTE NM HYD	108.00	-	8	.00197	4.45	.145	1.37541	1.499	3.530	PER IMP= 30.00
ADD HYD	108.10	1& 8	8	.00480	11.05	.375	1.46642	1.499	3.597	
ADD HYD	108.20	2& 8	8	.01374	30.25	.995	1.35735	1.499	3.440	
COMPUTE NM HYD	109.00	-	9	.00527	10.83	.332	1.18095	1.499	3.210	PER IMP= 10.00
COMPUTE NM HYD	110.00	-	10	.00310	6.38	.195	1.18095	1.499	3.214	PER IMP= 10.00
COMPUTE NM HYD	111.00	-	11	.00311	3.20	.090	.54195	1.532	1.607	PER IMP= .00
ADD HYD	111.10	10&11	11	.00621	9.50	.285	.86088	1.499	2.390	
COMPUTE NM HYD	112.00	-	12	.00047	.49	.014	.54195	1.532	1.628	PER IMP= .00
COMPUTE NM HYD	113.00	-	13	.00244	2.30	.065	.49889	1.532	1.473	PER IMP= .00
COMPUTE NM HYD	114.00	-	14	.01430	14.69	.413	.54195	1.532	1.605	PER IMP= .00
ADD HYD	114.10	14& 9	14	.01957	25.28	.745	.71401	1.532	2.018	
COMPUTE NM HYD	115.00	-	15	.01580	16.22	.457	.54195	1.532	1.604	PER IMP= .00
COMPUTE NM HYD	116.00	-	16	.04608	47.30	1.332	.54195	1.532	1.604	PER IMP= .00
ADD HYD	116.70	7&16	16	.05633	68.62	2.018	.67185	1.532	1.903	
ADD HYD	116.80	16& 8	16	.07007	98.28	3.013	.80627	1.499	2.192	
COMPUTE NM HYD	117.00	-	17	.00723	9.37	.265	.68597	1.532	2.026	PER IMP= .00
COMPUTE NM HYD	118.00	-	18	.00564	7.31	.206	.68597	1.532	2.026	PER IMP= .00
ADD HYD	118.10	6&18	18	.01763	32.86	1.014	1.07860	1.499	2.912	
COMPUTE NM HYD	119.00	-	19	.00800	8.28	.246	.57675	1.532	1.617	PER IMP= 5.00
ADD HYD	119.10	17&19	19	.01523	17.65	.511	.62857	1.532	1.811	
COMPUTE NM HYD	120.00	-	20	.01484	31.36	1.113	1.40584	1.499	3.302	PER IMP= 57.00
ADD HYD	120.10	19&20	20	.03007	48.76	1.623	1.01215	1.499	2.534	
COMPUTE NM HYD	121.00	-	21	.04313	86.08	3.588	1.55983	1.565	3.118	PER IMP= 60.00
ADD HYD	121.10	18&21	21	.06076	116.09	4.602	1.42019	1.532	2.985	
COMPUTE NM HYD	122.00	-	22	.00292	6.97	.243	1.55983	1.499	3.728	PER IMP= 60.00
ADD HYD	122.10	16&22	22	.07299	105.25	3.256	.83641	1.499	2.253	
COMPUTE NM HYD	152.00	-	1	.13048	253.89	8.780	1.26174	1.532	3.040	PER IMP= 35.00
COMPUTE NM HYD	153.00	-	2	.05022	101.21	3.513	1.31174	1.532	3.149	PER IMP= 40.00
COMPUTE NM HYD	162.00	-	3	.01659	32.76	1.043	1.17826	1.499	3.085	PER IMP= 25.00
ROUTE	162.90	3	6	.01659	32.00	1.043	1.17827	1.532	3.014	
COMPUTE NM HYD	163.00	-	4	.05291	107.13	3.465	1.22797	1.499	3.164	PER IMP= 30.00
COMPUTE NM HYD	200.00	-	5	.03004	59.95	2.102	1.31174	1.532	3.118	PER IMP= 40.00
ADD HYD	152.10	1& 6	1	.14707	285.89	9.823	1.25232	1.532	3.037	

ROUTE	152.90	1	3	.14707	270.91	9.823	1.25233	1.565	2.878
ADD HYD	153.20	2& 4	2	.10313	208.01	6.979	1.26876	1.499	3.151
ADD HYD	153 10	3& 2	1	.25020	476.00	16.801	1.25910	1.532	2.973
ROUTE	153.90	1	3	.25020	457.70	16.801	1.25910	1.565	2.858

[illegible]

AHYMO SUMMARY TABLE (AHYMO194) - AMAFCA Hydrologic Model - January, 1994
INPUT FILE = broad99.dat

RUN DATE (MON/DAY/YR) =09/11/1997
USER NO.= M_GOODWN.101

COMMAND	HYDROGRAPH IDENTIFICATION	FROM ID NO.	TO ID NO.	AREA (SQ MI)	PEAK DISCHARGE (CFS)	RUNOFF VOLUME (AC-FT)	RUNOFF (INCHES)	TIME TO PEAK (HOURS)	CFS PER ACRE	PAGE = 1 NOTATION
START										TIME= .00
RAINFALL TYPE= 1										RAIN6= 2.290
COMPUTE NM HYD	101.00	-	1	.00283	6.60	.231	1.52996	1.499	3.644	PER IMP= 60.00
COMPUTE NM HYD	102.00	-	2	.00302	7.04	.246	1.52996	1.499	3.643	PER IMP= 60.00
COMPUTE NM HYD	103.00	-	3	.00592	12.16	.373	1.18095	1.499	3.209	PER IMP= 10.00
ADD HYD	102.10	2& 3	2	.00894	19.20	.619	1.29878	1.499	3.356	
COMPUTE NM HYD	104.00	-	4	.00630	12.94	.397	1.18095	1.499	3.209	PER IMP= 10.00
COMPUTE NM HYD	105.00	-	5	.00508	11.45	.373	1.37541	1.499	3.521	PER IMP= 30.00
COMPUTE NM HYD	106.00	-	6	.00691	14.19	.435	1.18095	1.499	3.209	PER IMP= 10.00
ADD HYD	106.10	5& 6	6	.01199	25.64	.808	1.26329	1.499	3.341	
COMPUTE NM HYD	107.00	-	7	.00395	8.90	.290	1.37541	1.499	3.522	PER IMP= 30.00
ADD HYD	107.10	4& 7	7	.01025	21.84	.687	1.25583	1.499	3.330	
COMPUTE NM HYD	108.00	-	8	.00197	4.45	.145	1.37541	1.499	3.530	PER IMP= 30.00
ADD HYD	108.10	1& 8	8	.00480	11.05	.375	1.46642	1.499	3.597	
ADD HYD	108.20	2& 8	8	.01374	30.25	.995	1.35735	1.499	3.440	
COMPUTE NM HYD	109.00	-	9	.00527	10.83	.332	1.18095	1.499	3.210	PER IMP= 10.00
COMPUTE NM HYD	110.00	-	10	.00310	6.38	.195	1.18095	1.499	3.214	PER IMP= 10.00
COMPUTE NM HYD	111.00	-	11	.00311	3.20	.090	.54195	1.532	1.607	PER IMP= .00
ADD HYD	111.10	10&11	11	.00621	9.50	.285	.86088	1.499	2.390	
COMPUTE NM HYD	112.00	-	12	.00047	.49	.014	.54195	1.532	1.628	PER IMP= .00
COMPUTE NM HYD	113.00	-	13	.00244	2.30	.065	.49889	1.532	1.473	PER IMP= .00
COMPUTE NM HYD	114.00	-	14	.01430	14.69	.413	.54195	1.532	1.605	PER IMP= .00
ADD HYD	114.10	14& 9	14	.01957	25.28	.745	.71401	1.532	2.018	
COMPUTE NM HYD	115.00	-	15	.01580	16.22	.457	.54195	1.532	1.604	PER IMP= .00
COMPUTE NM HYD	116.00	-	16	.04608	47.30	1.332	.54195	1.532	1.604	PER IMP= .00
ADD HYD	116.70	7&16	16	.05633	68.62	2.018	.67185	1.532	1.903	
ADD HYD	116.80	16& 8	16	.07007	98.28	3.013	.80627	1.499	2.192	
COMPUTE NM HYD	117.00	-	17	.00723	9.37	.265	.68597	1.532	2.026	PER IMP= .00
COMPUTE NM HYD	118.00	-	18	.00564	7.31	.206	.68597	1.532	2.026	PER IMP= .00
ADD HYD	118.10	6&18	18	.01763	32.86	1.014	1.07860	1.499	2.912	
COMPUTE NM HYD	119.00	-	19	.00800	8.28	.246	.57675	1.532	1.617	PER IMP= 5.00
ADD HYD	119.10	17&19	19	.01523	17.65	.511	.62857	1.532	1.811	
COMPUTE NM HYD	120.00	-	20	.01484	31.36	1.113	1.40584	1.499	3.302	PER IMP= 57.00
ADD HYD	120.10	19&20	20	.03007	48.76	1.623	1.01215	1.499	2.534	
COMPUTE NM HYD	121.00	-	21	.04313	86.08	3.588	1.55983	1.565	3.118	PER IMP= 60.00
ADD HYD	121.10	18&21	21	.06076	116.09	4.602	1.42019	1.532	2.985	
COMPUTE NM HYD	122.00	-	22	.00292	6.97	.243	1.55983	1.499	3.728	PER IMP= 60.00
ADD HYD	122.10	16&22	22	.07299	105.25	3.256	.83641	1.499	2.253	
COMPUTE NM HYD	152.00	-	1	.13048	253.89	8.780	1.26174	1.532	3.040	PER IMP= 35.00
COMPUTE NM HYD	153.00	-	2	.05022	101.21	3.513	1.31174	1.532	3.149	PER IMP= 40.00
COMPUTE NM HYD	162.00	-	3	.01659	32.76	1.043	1.17826	1.499	3.085	PER IMP= 25.00
ROUTE	162.90	3	6	.01659	32.00	1.043	1.17827	1.532	3.014	
COMPUTE NM HYD	163.00	-	4	.05291	107.13	3.465	1.22797	1.499	3.164	PER IMP= 30.00
COMPUTE NM HYD	200.00	-	5	.03004	59.95	2.102	1.31174	1.532	3.118	PER IMP= 40.00
ADD HYD	152.10	1& 6	1	.14707	285.89	9.823	1.25232	1.532	3.037	

ROUTE	152.90	1	3	.14707	270.91	9.823	1.25233	1.565	2.878
ADD HYD	153.20	2& 4	2	.10313	208.01	6.979	1.26876	1.499	3.151
ADD HYD	153.10	3& 2	1	.25020	476.00	16.801	1.25910	1.532	2.973
ROUTE	153.90	1	3	.25020	457.70	16.801	1.25910	1.565	2.858

[illegible]

PRINT HYD	TP=0.13333 HR MASS RAINFALL=-1
COMPUTE NM HYD	ID=9 CODE=1
	ID=10 HYD NO=110.0 AREA=0.00310 SQ MI
	(A,B,C,D) 0 0 90 10
	TP=0.13333 HR MASS RAINFALL=-1
PRINT HYD	ID=10 CODE=1
COMPUTE NM HYD	ID=11 HYD NO=111.0 AREA=0.00311 SQ MI
	(A,B,C,D) 90 0 10 0
	TP=0.13333 HR MASS RAINFALL=-1
PRINT HYD	ID=11 CODE=1
ADD HYD	ID=11 SUM NO=111.1 IDS=10 & 11
PRINT HYD	ID=11 CODE=1
COMPUTE NM HYD	ID=12 HYD NO=112.0 AREA=0.00047 SQ MI
	(A,B,C,D) 90 0 10 0
	TP=0.13333 HR MASS RAINFALL=-1
PRINT HYD	ID=12 CODE=1
COMPUTE NM HYD	ID=13 HYD NO=113.0 AREA=0.00244 SQ MI
	(A,B,C,D) 100 0 0 0
	TP=0.13333 HR MASS RAINFALL=-1
PRINT HYD	ID=13 CODE=1
COMPUTE NM HYD	ID=14 HYD NO=114.0 AREA=0.01430 SQ MI
	(A,B,C,D) 90 0 10 0
	TP=0.13333 HR MASS RAINFALL=-1
PRINT HYD	ID=14 CODE=1
ADD HYD	ID=14 SUM NO=114.1 IDS=14 & 9
PRINT HYD	ID=14 CODE=1
COMPUTE NM HYD	ID=15 HYD NO=115.0 AREA=0.01580 SQ MI
	(A,B,C,D) 90 0 10 0
	TP=0.13333 HR MASS RAINFALL=-1
PRINT HYD	ID=15 CODE=1
COMPUTE NM HYD	ID=16 HYD NO=116.0 AREA=0.04608 SQ MI
	(A,B,C,D) 90 0 10 0
	TP=0.13333 HR MASS RAINFALL=-1
PRINT HYD	ID=16 CODE=1
ADD HYD	ID=16 SUM NO=116.7 IDS=7 & 16
PRINT HYD	ID=16 CODE=1
ADD HYD	ID=16 SUM NO=116.8 IDS=16 & 8
PRINT HYD	ID=16 CODE=1
COMPUTE NM HYD	ID=17 HYD NO=117.0 AREA=0.00723 SQ MI
	(A,B,C,D) 60 0 40 0
	TP=0.13333 HR MASS RAINFALL=-1
PRINT HYD	ID=17 CODE=1
COMPUTE NM HYD	ID=18 HYD NO=118.0 AREA=0.00564 SQ MI
	(A,B,C,D) 60 0 40 0
	TP=0.13333 HR MASS RAINFALL=-1
PRINT HYD	ID=18 CODE=1
ADD HYD	ID=18 SUM NO=118.1 IDS=6 & 18
PRINT HYD	ID=18 CODE=1
COMPUTE NM HYD	ID=19 HYD NO=119.0 AREA=0.00800 SQ MI
	(A,B,C,D) 95 0 0 5
	TP=0.13333 HR MASS RAINFALL=-1
PRINT HYD	ID=19 CODE=1

ADD HYD	ID=19 SUM NO=119.1 IDS=17 & 19
PRINT HYD	ID=19 CODE=1
COMPUTE NM HYD	ID=20 HYD NO=120.0 AREA=0.01484 SQ MI (A,B,C,D) 37 3 3 57 TP=0.13333 HR MASS RAINFALL=-1
PRINT HYD	ID=20 CODE=1
ADD HYD	ID=20 SUM NO=120.1 IDS=19 & 20
PRINT HYD	ID=20 CODE=1
COMPUTE NM HYD	ID=21 HYD NO=121.0 AREA=0.04313 SQ MI (A,B,C,D) 0 30 10 60 TP=0.187 HR MASS RAINFALL=-1
PRINT HYD	ID=21 CODE=1
ADD HYD	ID=21 SUM NO=121.1 IDS=18 & 21
PRINT HYD	ID=21 CODE=1
COMPUTE NM HYD	ID=22 HYD NO=122.0 AREA=0.00292 SQ MI (A,B,C,D) 0 30 10 60 TP=0.13333 HR MASS RAINFALL=-1
PRINT HYD	ID=22 CODE=1
ADD HYD	ID=22 SUM NO=122.1 IDS=16 & 22
PRINT HYD	ID=22 CODE=1
COMPUTE NM HYD	ID=1 HYD NO=152.0 AREA=0.13048 SQ MI (A,B,C,D) 0 45 20 35 TP=0.1476 HR MASS RAINFALL=-1
PRINT HYD	ID=1 CODE=1
COMPUTE NM HYD	ID=2 HYD NO=153.0 AREA=0.05022 SQ MI (A,B,C,D) 0 45 15 40 TP=0.1412 HR MASS RAINFALL=-1
PRINT HYD	ID=2 CODE=1
COMPUTE NM HYD	ID=3 HYD NO=162.0 AREA=0.01659 SQ MI (A,B,C,D) 0 40 35 25 TP=0.13333 HR MASS RAINFALL=-1
PRINT HYD	ID=3 CODE=1
COMPUTE RATING CURVE	CID=1 VS NO=1 CODE=-1 SLP=.027 DIA=2.5 FT N=.013
COMPUTE TRAVEL TIME	ID=6 REACH NO=1 NO VS=1 L=1600 FT SLP=.027
ROUTE	ID=6 HYD NO=162.9 INFLOW ID=3 DT=0 HR
PRINT HYD	ID=6 CODE=1
COMPUTE NM HYD	ID=4 HYD NO=163.0 AREA=0.05291 SQ MI (A,B,C,D) 0 40 30 30 TP=0.13333 HR MASS RAINFALL=-1
PRINT HYD	ID=4 CODE=1
COMPUTE NM HYD	ID=5 HYD NO=200.0 AREA=0.03004 SQ MI (A,B,C,D) 0 45 15 40 TP=0.1453 HR MASS RAINFALL=-1
PRINT HYD	ID=5 CODE=1
ADD HYD	ID=1 SUM NO=152.1 IDS=1 & 6
PRINT HYD	ID=1 CODE=1
***** ROUTE FLOWS FROM KATHRYN TO THAXTON IN 72" RCP	
***** NOTE THAT CAPACITY EXCEEDED (real slope=0.21%)	
COMPUTE RATING CURVE	CID=1 VS NO=1 CODE=-1 SLP=.0045 DIA=6.0 FT N=.013
COMPUTE TRAVEL TIME	ID=3 REACH NO=1 NO VS=1 L=1350 FT SLP=.0045
ROUTE	ID=3 HYD NO=152.9 INFLOW ID=1 DT=0 HR
PRINT HYD	ID=3 CODE=1

```

ADD HYD          ID=2 SUM NO=153.2 IDS=2 & 4
PRINT HYD        ID=2 CODE=1
ADD HYD          ID=1 SUM NO=153.1 IDS=3 & 2
PRINT HYD        ID=1 CODE=1
***** ROUTE FLOWS FROM KATHRYN TO THAXTON IN 72" RCP
***** NOTE THAT CAPACITY EXCEEDED (real slope=0.21%)
COMPUTE RATING CURVE CID=1 VS NO=1 CODE=-1 SLP=.012 DIA=6.0 FT N=.013
COMPUTE TRAVEL TIME ID=3 REACH NO=1 NO VS=1 L=2250 FT SLP=.012
ROUTE            ID=3 HYD NO=153.9 INFLOW ID=1 DT=0 HR
PRINT HYD        ID=3 CODE=1
ADD HYD          ID=1 SUM NO=200.1 IDS=3 & 5
PRINT HYD        ID=1 CODE=1
ADD HYD          ID=2 SUM NO=202.0 IDS=20 & 21
PRINT HYD        ID=2 CODE=1
ADD HYD          ID=1 SUM NO=202.1 IDS=1 & 2
PRINT HYD        ID=1 CODE=1
ADD HYD          ID=1 SUM NO=700.1 IDS=1 & 22
PRINT HYD        ID=1 CODE=1
FINISH
□

```

AHYMO PROGRAM (AHYMO194) - AMAFCA Hydrologic Model - January, 1994
 RUN DATE (MON/DAY/YR) = 09/11/1997
 START TIME (HR:MIN:SEC) = 08:07:40 USER NO.= M_GOODWN.I01
 INPUT FILE = broad99.dat

START TIME=0.0
 ***** SOUTH BROADWAY INDUSTRIAL PARK
 ***** PRE-DEVELOPED-EXISTING CONDITIONS
 ***** 100-YEAR 6-HOUR STORM EVENT
 ***** AUG. 21, 1997
 RAINFALL TYPE=1 RAIN QUARTER=0.0 IN
 RAIN ONE=1.97 IN RAIN SIX=2.29 IN
 RAIN DAY=2.65 IN DT=0.0333 HR

COMPUTED 6-HOUR RAINFALL DISTRIBUTION BASED ON NOAA ATLAS 2 - PEAK AT 1.40 HR.
 DT = .033300 HOURS END TIME = 5.994000 HOURS

.0000	.0015	.0029	.0045	.0060	.0076	.0092
.0109	.0126	.0143	.0161	.0180	.0199	.0218
.0238	.0258	.0280	.0302	.0324	.0348	.0372
.0397	.0423	.0450	.0479	.0508	.0539	.0572
.0606	.0642	.0680	.0734	.0792	.0854	.0982
.1277	.1731	.2383	.3276	.4449	.5947	.7813
1.0091	1.2279	1.3176	1.3932	1.4602	1.5212	1.5773
1.6295	1.6781	1.7238	1.7667	1.8072	1.8455	1.8817
1.9160	1.9485	1.9794	2.0087	2.0365	2.0439	2.0498
2.0553	2.0606	2.0656	2.0705	2.0751	2.0795	2.0838
2.0879	2.0919	2.0958	2.0995	2.1031	2.1067	2.1101
2.1134	2.1167	2.1199	2.1230	2.1260	2.1290	2.1319
2.1347	2.1375	2.1402	2.1429	2.1455	2.1480	2.1506
2.1530	2.1555	2.1579	2.1602	2.1625	2.1648	2.1671
2.1693	2.1714	2.1736	2.1757	2.1778	2.1798	2.1819
2.1839	2.1858	2.1878	2.1897	2.1916	2.1935	2.1954
2.1972	2.1990	2.2008	2.2026	2.2043	2.2060	2.2078
2.2095	2.2111	2.2128	2.2144	2.2161	2.2177	2.2193
2.2208	2.2224	2.2240	2.2255	2.2270	2.2285	2.2300
2.2315	2.2330	2.2344	2.2359	2.2373	2.2387	2.2401
2.2415	2.2429	2.2443	2.2456	2.2470	2.2483	2.2496
2.2510	2.2523	2.2536	2.2549	2.2562	2.2574	2.2587
2.2599	2.2612	2.2624	2.2636	2.2649	2.2661	2.2673
2.2685	2.2697	2.2708	2.2720	2.2732	2.2743	2.2755
2.2766	2.2778	2.2789	2.2800	2.2811	2.2822	2.2833
2.2844	2.2855	2.2866	2.2877	2.2887	2.2898	

COMPUTE NM HYD ID=1 HYD NO=101.0 AREA=0.00283 SQ MI
(A,B,C,D) 0 40 0 60
TP=0.13333 HR MASS RAINFALL=-1

K = .072665HR TP = .133330HR K/TP RATIO = .545000 SHAPE CONSTANT, N = 7.106420
UNIT PEAK = 6.7023 CFS UNIT VOLUME = .9975 B = 526.28 P60 = 1.9700
AREA = .001698 SQ MI IA = .10000 INCHES INF = .04000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

K = .131635HR TP = .133330HR K/TP RATIO = .987285 SHAPE CONSTANT, N = 3.576408
UNIT PEAK = 2.7667 CFS UNIT VOLUME = .9955 B = 325.86 P60 = 1.9700
AREA = .001132 SQ MI IA = .50000 INCHES INF = 1.25000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=1 CODE=1

PARTIAL HYDROGRAPH 101.00

RUNOFF VOLUME = 1.52996 INCHES = .2309 ACRE-Feet
PEAK DISCHARGE RATE = 6.60 CFS AT 1.499 HOURS BASIN AREA = .0028 SQ. MI.

COMPUTE NM HYD ID=2 HYD NO=102.0 AREA=0.00302 SQ MI
(A,B,C,D) 0 40 0 60
TP=0.13333 HR MASS RAINFALL=-1

K = .072665HR TP = .133330HR K/TP RATIO = .545000 SHAPE CONSTANT, N = 7.106420
UNIT PEAK = 7.1523 CFS UNIT VOLUME = .9978 B = 526.28 P60 = 1.9700
AREA = .001812 SQ MI IA = .10000 INCHES INF = .04000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

K = .131635HR TP = .133330HR K/TP RATIO = .987285 SHAPE CONSTANT, N = 3.576408
UNIT PEAK = 2.9524 CFS UNIT VOLUME = .9955 B = 325.86 P60 = 1.9700
AREA = .001208 SQ MI IA = .50000 INCHES INF = 1.25000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=2 CODE=1

PARTIAL HYDROGRAPH 102.00

RUNOFF VOLUME = 1.52996 INCHES = .2464 ACRE-Feet
PEAK DISCHARGE RATE = 7.04 CFS AT 1.499 HOURS BASIN AREA = .0030 SQ. MI.

COMPUTE NM HYD ID=3 HYD NO=103.0 AREA=0.00592 SQ MI
(A,B,C,D) 0 0 90 10
TP=0.13333 HR MASS RAINFALL=-1

K = .072665HR TP = .133330HR K/TP RATIO = .545000 SHAPE CONSTANT, N = 7.106420
UNIT PEAK = 2.3367 CFS UNIT VOLUME = .9948 B = 526.28 P60 = 1.9700
AREA = .000592 SQ MI IA = .10000 INCHES INF = .04000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

K = .107019HR TP = .133330HR K/TP RATIO = .802661 SHAPE CONSTANT, N = 4.461616
UNIT PEAK = 15.379 CFS UNIT VOLUME = .9996 B = 384.85 P60 = 1.9700
AREA = .005328 SQ MI IA = .35000 INCHES INF = .83000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=3 CODE=1

PARTIAL HYDROGRAPH 103.00

RUNOFF VOLUME = 1.18095 INCHES = .3729 ACRE-FEET
PEAK DISCHARGE RATE = 12.16 CFS AT 1.499 HOURS BASIN AREA = .0059 SQ. MI.

ADD HYD ID=2 SUM NO=102.1 IDS=2 & 3
PRINT HYD ID=2 CODE=1

PARTIAL HYDROGRAPH 102.10

RUNOFF VOLUME = 1.29878 INCHES = .6193 ACRE-FEET
PEAK DISCHARGE RATE = 19.20 CFS AT 1.499 HOURS BASIN AREA = .0089 SQ. MI.

COMPUTE NM HYD ID=4 HYD NO=104.0 AREA=0.00630 SQ MI
(A,B,C,D) 0 0 90 10
TP=0.13333 HR MASS RAINFALL=-1

K = .072665HR TP = .133330HR K/TP RATIO = .545000 SHAPE CONSTANT, N = 7.106420
UNIT PEAK = 2.4867 CFS UNIT VOLUME = .9948 B = 526.28 P60 = 1.9700
AREA = .000630 SQ MI IA = .10000 INCHES INF = .04000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

K = .107019HR TP = .133330HR K/TP RATIO = .802661 SHAPE CONSTANT, N = 4.461616
UNIT PEAK = 16.366 CFS UNIT VOLUME = .9997 B = 384.85 P60 = 1.9700
AREA = .005670 SQ MI IA = .35000 INCHES INF = .83000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=4 CODE=1

PARTIAL HYDROGRAPH 104.00

RUNOFF VOLUME = 1.18095 INCHES = .3968 ACRE-Feet
PEAK DISCHARGE RATE = 12.94 CFS AT 1.499 HOURS BASIN AREA = .0063 SQ. MI.

COMPUTE NM HYD ID=5 HYD NO=105.0 AREA=0.00508 SQ MI
(A,B,C,D) 0 0 70 30
TP=0.13333 HR MASS RAINFALL=-1

K = .072665HR TP = .133330HR K/TP RATIO = .545000 SHAPE CONSTANT, N = 7.106420
UNIT PEAK = 6.0155 CFS UNIT VOLUME = .9975 B = 526.28 P60 = 1.9700
AREA = .001524 SQ MI IA = .10000 INCHES INF = .04000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

K = .107019HR TP = .133330HR K/TP RATIO = .802661 SHAPE CONSTANT, N = 4.461616
UNIT PEAK = 10.264 CFS UNIT VOLUME = .9992 B = 384.85 P60 = 1.9700
AREA = .003556 SQ MI IA = .35000 INCHES INF = .83000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=5 CODE=1

PARTIAL HYDROGRAPH 105.00

RUNOFF VOLUME = 1.37541 INCHES = .3726 ACRE-Feet
PEAK DISCHARGE RATE = 11.45 CFS AT 1.499 HOURS BASIN AREA = .0051 SQ. MI.

COMPUTE NM HYD ID=6 HYD NO=106.0 AREA=0.00691 SQ MI
(A,B,C,D) 0 0 90 10
TP=0.13333 HR MASS RAINFALL=-1

K = .072665HR TP = .133330HR K/TP RATIO = .545000 SHAPE CONSTANT, N = 7.106420
UNIT PEAK = 2.7275 CFS UNIT VOLUME = .9954 B = 526.28 P60 = 1.9700
AREA = .000691 SQ MI IA = .10000 INCHES INF = .04000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

K = .107019HR TP = .133330HR K/TP RATIO = .802661 SHAPE CONSTANT, N = 4.461616
UNIT PEAK = 17.951 CFS UNIT VOLUME = .9997 B = 384.85 P60 = 1.9700
AREA = .006219 SQ MI IA = .35000 INCHES INF = .83000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=6 CODE=1

PARTIAL HYDROGRAPH 106.00

RUNOFF VOLUME = 1.18095 INCHES = .4352 ACRE-Feet
PEAK DISCHARGE RATE = 14.19 CFS AT 1.499 HOURS BASIN AREA = .0069 SQ. MI.

ADD HYD ID=6 SUM NO=106.1 IDS=5 & 6
PRINT HYD ID=6 CODE=1

PARTIAL HYDROGRAPH 106.10

RUNOFF VOLUME = 1.26329 INCHES = .8078 ACRE-Feet
PEAK DISCHARGE RATE = 25.64 CFS AT 1.499 HOURS BASIN AREA = .0120 SQ. MI.

COMPUTE NM HYD ID=7 HYD NO=107.0 AREA=0.00395 SQ MI
(A,B,C,D) 0 0 70 30
TP=0.13333 HR MASS RAINFALL=-1

K = .072665HR TP = .133330HR K/TP RATIO = .545000 SHAPE CONSTANT, N = 7.106420
UNIT PEAK = 4.6774 CFS UNIT VOLUME = .9969 B = 526.28 P60 = 1.9700
AREA = .001185 SQ MI IA = .10000 INCHES INF = .04000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

K = .107019HR TP = .133330HR K/TP RATIO = .802661 SHAPE CONSTANT, N = 4.461616
UNIT PEAK = 7.9810 CFS UNIT VOLUME = .9989 B = 384.85 P60 = 1.9700
AREA = .002765 SQ MI IA = .35000 INCHES INF = .83000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=7 CODE=1

PARTIAL HYDROGRAPH 107.00

RUNOFF VOLUME = 1.37541 INCHES = .2898 ACRE-Feet
PEAK DISCHARGE RATE = 8.90 CFS AT 1.499 HOURS BASIN AREA = .0040 SQ. MI.

ADD HYD ID=7 SUM NO=107.1 IDS=4 & 7
PRINT HYD ID=7 CODE=1

PARTIAL HYDROGRAPH 107.10

RUNOFF VOLUME = 1.25583 INCHES = .6865 ACRE-FEET
PEAK DISCHARGE RATE = 21.84 CFS AT 1.499 HOURS BASIN AREA = .0103 SQ. MI.

COMPUTE NM HYD ID=8 HYD NO=108.0 AREA=0.00197 SQ MI
(A,B,C,D) 0 0 70 30
TP=0.13333 HR MASS RAINFALL=-1

K = .072665HR TP = .133330HR K/TP RATIO = .545000 SHAPE CONSTANT, N = 7.106420
UNIT PEAK = 2.3328 CFS UNIT VOLUME = .9941 B = 526.28 P60 = 1.9700
AREA = .000591 SQ MI IA = .10000 INCHES INF = .04000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

K = .107019HR TP = .133330HR K/TP RATIO = .802661 SHAPE CONSTANT, N = 4.461616
UNIT PEAK = 3.9804 CFS UNIT VOLUME = .9972 B = 384.85 P60 = 1.9700
AREA = .001379 SQ MI IA = .35000 INCHES INF = .83000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=8 CODE=1

PARTIAL HYDROGRAPH 108.00

RUNOFF VOLUME = 1.37541 INCHES = .1445 ACRE-FEET
PEAK DISCHARGE RATE = 4.45 CFS AT 1.499 HOURS BASIN AREA = .0020 SQ. MI.

ADD HYD ID=8 SUM NO=108.1 IDS=1 & 8
PRINT HYD ID=8 CODE=1

PARTIAL HYDROGRAPH 108.10

RUNOFF VOLUME = 1.46642 INCHES = .3754 ACRE-FEET
PEAK DISCHARGE RATE = 11.05 CFS AT 1.499 HOURS BASIN AREA = .0048 SQ. MI.

ADD HYD ID=8 SUM NO=108.2 IDS=2 & 8
PRINT HYD ID=8 CODE=1

PARTIAL HYDROGRAPH 108.20

RUNOFF VOLUME = 1.35735 INCHES = .9947 ACRE-FEET
PEAK DISCHARGE RATE = 30.25 CFS AT 1.499 HOURS BASIN AREA = .0137 SQ. MI.

COMPUTE NM HYD ID=9 HYD NO=109.0 AREA=0.00527 SQ MI
(A,B,C,D) 0 0 90 10
TP=0.13333 HR MASS RAINFALL=-1

K = .072665HR TP = .133330HR K/TP RATIO = .545000 SHAPE CONSTANT, N = 7.106420
UNIT PEAK = 2.0802 CFS UNIT VOLUME = .9941 B = 526.28 P60 = 1.9700
AREA = .000527 SQ MI IA = .10000 INCHES INF = .04000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

K = .107019HR TP = .133330HR K/TP RATIO = .802661 SHAPE CONSTANT, N = 4.461616
UNIT PEAK = 13.690 CFS UNIT VOLUME = .9995 B = 384.85 P60 = 1.9700
AREA = .004743 SQ MI IA = .35000 INCHES INF = .83000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=9 CODE=1

PARTIAL HYDROGRAPH 109.00

RUNOFF VOLUME = 1.18095 INCHES = .3319 ACRE-FEET
PEAK DISCHARGE RATE = 10.83 CFS AT 1.499 HOURS BASIN AREA = .0053 SQ. MI.

COMPUTE NM HYD ID=10 HYD NO=110.0 AREA=0.00310 SQ MI
(A,B,C,D) 0 0 90 10
TP=0.13333 HR MASS RAINFALL=-1

K = .072665HR TP = .133330HR K/TP RATIO = .545000 SHAPE CONSTANT, N = 7.106420
UNIT PEAK = 1.2236 CFS UNIT VOLUME = .9896 B = 526.28 P60 = 1.9700
AREA = .000310 SQ MI IA = .10000 INCHES INF = .04000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

K = .107019HR TP = .133330HR K/TP RATIO = .802661 SHAPE CONSTANT, N = 4.461616
UNIT PEAK = 8.0531 CFS UNIT VOLUME = .9989 B = 384.85 P60 = 1.9700
AREA = .002790 SQ MI IA = .35000 INCHES INF = .83000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=10 CODE=1

PARTIAL HYDROGRAPH 110.00

RUNOFF VOLUME = 1.18095 INCHES = .1952 ACRE-FeET
PEAK DISCHARGE RATE = 6.38 CFS AT 1.499 HOURS BASIN AREA = .0031 SQ. MI.

COMPUTE NM HYD ID=11 HYD NO=111.0 AREA=0.00311 SQ MI
(A,B,C,D) 90 0 10 0
TP=0.13333 HR MASS RAINFALL=-1

K = .155781HR TP = .133330HR K/TP RATIO = 1.168387 SHAPE CONSTANT, N = 3.035166
UNIT PEAK = 6.6402 CFS UNIT VOLUME = .9976 B = 284.68 P60 = 1.9700
AREA = .003110 SQ MI IA = .62000 INCHES INF = 1.58600 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=11 CODE=1

PARTIAL HYDROGRAPH 111.00

RUNOFF VOLUME = .54195 INCHES = .0899 ACRE-FeET
PEAK DISCHARGE RATE = 3.20 CFS AT 1.532 HOURS BASIN AREA = .0031 SQ. MI.

ADD HYD ID=11 SUM NO=111.1 IDS=10 & 11
PRINT HYD ID=11 CODE=1

PARTIAL HYDROGRAPH 111.10

RUNOFF VOLUME = .86088 INCHES = .2851 ACRE-FeET
PEAK DISCHARGE RATE = 9.50 CFS AT 1.499 HOURS BASIN AREA = .0062 SQ. MI.

COMPUTE NM HYD ID=12 HYD NO=112.0 AREA=0.00047 SQ MI
(A,B,C,D) 90 0 10 0
TP=0.13333 HR MASS RAINFALL=-1

K = .155781HR TP = .133330HR K/TP RATIO = 1.168387 SHAPE CONSTANT, N = 3.035166
UNIT PEAK = 1.0035 CFS UNIT VOLUME = .9850 B = 284.68 P60 = 1.9700
AREA = .000470 SQ MI IA = .62000 INCHES INF = 1.58600 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=12 CODE=1

PARTIAL HYDROGRAPH 112.00

RUNOFF VOLUME = .54195 INCHES = .0136 ACRE-FeET
PEAK DISCHARGE RATE = .49 CFS AT 1.532 HOURS BASIN AREA = .0005 SQ. MI.

COMPUTE NM HYD ID=13 HYD NO=113.0 AREA=0.00244 SQ MI
(A,B,C,D) 100 0 0 0
TP=0.13333 HR MASS RAINFALL=-1

K = .161199HR TP = .133330HR K/TP RATIO = 1.209023 SHAPE CONSTANT, N = 2.940974
UNIT PEAK = 5.0687 CFS UNIT VOLUME = .9968 B = 276.97 P60 = 1.9700
AREA = .002440 SQ MI IA = .65000 INCHES INF = 1.67000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=13 CODE=1

PARTIAL HYDROGRAPH 113.00

RUNOFF VOLUME = .49889 INCHES = .0649 ACRE-FeET
PEAK DISCHARGE RATE = 2.30 CFS AT 1.532 HOURS BASIN AREA = .0024 SQ. MI.

COMPUTE NM HYD ID=14 HYD NO=114.0 AREA=0.01430 SQ MI
(A,B,C,D) 90 0 10 0
TP=0.13333 HR MASS RAINFALL=-1

K = .155781HR TP = .133330HR K/TP RATIO = 1.168387 SHAPE CONSTANT, N = 3.035166
UNIT PEAK = 30.532 CFS UNIT VOLUME = .9993 B = 284.68 P60 = 1.9700
AREA = .014300 SQ MI IA = .62000 INCHES INF = 1.58600 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=14 CODE=1

PARTIAL HYDROGRAPH 114.00

RUNOFF VOLUME = .54195 INCHES = .4133 ACRE-FeET
PEAK DISCHARGE RATE = 14.69 CFS AT 1.532 HOURS BASIN AREA = .0143 SQ. MI.

ADD HYD ID=14 SUM NO=114.1 IDS=14 & 9
PRINT HYD ID=14 CODE=1

PARTIAL HYDROGRAPH 114.10

RUNOFF VOLUME = .71401 INCHES = .7452 ACRE-Feet
PEAK DISCHARGE RATE = 25.28 CFS AT 1.532 HOURS BASIN AREA = .0196 SQ. MI.

COMPUTE NM HYD ID=15 HYD NO=115.0 AREA=0.01580 SQ MI
(A,B,C,D) 90 0 10 0
TP=0.13333 HR MASS RAINFALL=-1

K = .155781HR TP = .133330HR K/TP RATIO = 1.168387 SHAPE CONSTANT, N = 3.035166
UNIT PEAK = 33.735 CFS UNIT VOLUME = .9994 B = 284.68 P60 = 1.9700
AREA = .015800 SQ MI IA = .62000 INCHES INF = 1.58600 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=15 CODE=1

PARTIAL HYDROGRAPH 115.00

RUNOFF VOLUME = .54195 INCHES = .4567 ACRE-Feet
PEAK DISCHARGE RATE = 16.22 CFS AT 1.532 HOURS BASIN AREA = .0158 SQ. MI.

COMPUTE NM HYD ID=16 HYD NO=116.0 AREA=0.04608 SQ MI
(A,B,C,D) 90 0 10 0
TP=0.13333 HR MASS RAINFALL=-1

K = .155781HR TP = .133330HR K/TP RATIO = 1.168387 SHAPE CONSTANT, N = 3.035166
UNIT PEAK = 98.387 CFS UNIT VOLUME = .9997 B = 284.68 P60 = 1.9700
AREA = .046080 SQ MI IA = .62000 INCHES INF = 1.58600 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=16 CODE=1

PARTIAL HYDROGRAPH 116.00

RUNOFF VOLUME = .54195 INCHES = 1.3319 ACRE-Feet
PEAK DISCHARGE RATE = 47.30 CFS AT 1.532 HOURS BASIN AREA = .0461 SQ. MI.

ADD HYD ID=16 SUM NO=116.7 IDS=7 & 16
PRINT HYD ID=16 CODE=1

PARTIAL HYDROGRAPH 116.70

RUNOFF VOLUME = .67185 INCHES = 2.0184 ACRE-FEET
PEAK DISCHARGE RATE = 68.62 CFS AT 1.532 HOURS BASIN AREA = .0563 SQ. MI.

ADD HYD ID=16 SUM NO=116.8 IDS=16 & 8
PRINT HYD ID=16 CODE=1

PARTIAL HYDROGRAPH 116.80

RUNOFF VOLUME = .80627 INCHES = 3.0131 ACRE-FEET
PEAK DISCHARGE RATE = 98.28 CFS AT 1.499 HOURS BASIN AREA = .0701 SQ. MI.

COMPUTE NM HYD ID=17 HYD NO=117.0 AREA=0.00723 SQ MI
(A,B,C,D) 60 0 40 0
TP=0.13333 HR MASS RAINFALL=-1

K = .139527HR TP = .133330HR K/TP RATIO = 1.046479 SHAPE CONSTANT, N = 3.373630
UNIT PEAK = 16.864 CFS UNIT VOLUME = .9992 B = 310.99 P60 = 1.9700
AREA = .007230 SQ MI IA = .53000 INCHES INF = 1.33400 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=17 CODE=1

PARTIAL HYDROGRAPH 117.00

RUNOFF VOLUME = .68597 INCHES = .2645 ACRE-FEET
PEAK DISCHARGE RATE = 9.37 CFS AT 1.532 HOURS BASIN AREA = .0072 SQ. MI.

COMPUTE NM HYD ID=18 HYD NO=118.0 AREA=0.00564 SQ MI
(A,B,C,D) 60 0 40 0
TP=0.13333 HR MASS RAINFALL=-1

K = .139527HR TP = .133330HR K/TP RATIO = 1.046479 SHAPE CONSTANT, N = 3.373630
UNIT PEAK = 13.155 CFS UNIT VOLUME = .9989 B = 310.99 P60 = 1.9700
AREA = .005640 SQ MI IA = .53000 INCHES INF = 1.33400 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=18 CODE=1

PARTIAL HYDROGRAPH 118.00

RUNOFF VOLUME = .68597 INCHES = .2063 ACRE-FEET
PEAK DISCHARGE RATE = 7.31 CFS AT 1.532 HOURS BASIN AREA = .0056 SQ. MI.

ADD HYD ID=18 SUM NO=118.1 IDS=6 & 18
PRINT HYD ID=18 CODE=1

PARTIAL HYDROGRAPH 118.10

RUNOFF VOLUME = 1.07860 INCHES = 1.0142 ACRE-FEET
PEAK DISCHARGE RATE = 32.86 CFS AT 1.499 HOURS BASIN AREA = .0176 SQ. MI.

COMPUTE NM HYD ID=19 HYD NO=119.0 AREA=0.00800 SQ MI
(A,B,C,D) 95 0 0 5
TP=0.13333 HR MASS RAINFALL=-1

K = .072665HR TP = .133330HR K/TP RATIO = .545000 SHAPE CONSTANT, N = 7.106420
UNIT PEAK = 1.5789 CFS UNIT VOLUME = .9922 B = 526.28 P60 = 1.9700
AREA = .000400 SQ MI IA = .10000 INCHES INF = .04000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

K = .161199HR TP = .133330HR K/TP RATIO = 1.209023 SHAPE CONSTANT, N = 2.940974
UNIT PEAK = 15.788 CFS UNIT VOLUME = .9988 B = 276.97 P60 = 1.9700
AREA = .007600 SQ MI IA = .65000 INCHES INF = 1.67000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=19 CODE=1

PARTIAL HYDROGRAPH 119.00

RUNOFF VOLUME = .57675 INCHES = .2461 ACRE-FEET
PEAK DISCHARGE RATE = 8.28 CFS AT 1.532 HOURS BASIN AREA = .0080 SQ. MI.

ADD HYD ID=19 SUM NO=119.1 IDS=17 & 19
PRINT HYD ID=19 CODE=1

PARTIAL HYDROGRAPH 119.10

RUNOFF VOLUME = .62857 INCHES = .5106 ACRE-FEET
PEAK DISCHARGE RATE = 17.65 CFS AT 1.532 HOURS BASIN AREA = .0152 SQ. MI.

COMPUTE NM HYD ID=20 HYD NO=120.0 AREA=0.01484 SQ MI
(A,B,C,D) 37 3 3 57
TP=0.13333 HR MASS RAINFALL=-1

K = .072665HR TP = .133330HR K/TP RATIO = .545000 SHAPE CONSTANT, N = 7.106420
UNIT PEAK = 33.388 CFS UNIT VOLUME = .9990 B = 526.28 P60 = 1.9700
AREA = .008459 SQ MI IA = .10000 INCHES INF = .04000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

K = .155356HR TP = .133330HR K/TP RATIO = 1.165202 SHAPE CONSTANT, N = 3.042894
UNIT PEAK = 13.655 CFS UNIT VOLUME = .9988 B = 285.30 P60 = 1.9700
AREA = .006381 SQ MI IA = .61860 INCHES INF = 1.58209 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=20 CODE=1

PARTIAL HYDROGRAPH 120.00

RUNOFF VOLUME = 1.40584 INCHES = 1.1127 ACRE-FEET
PEAK DISCHARGE RATE = 31.36 CFS AT 1.499 HOURS BASIN AREA = .0148 SQ. MI.

ADD HYD ID=20 SUM NO=120.1 IDS=19 & 20
PRINT HYD ID=20 CODE=1

PARTIAL HYDROGRAPH 120.10

RUNOFF VOLUME = 1.01215 INCHES = 1.6232 ACRE-FEET
PEAK DISCHARGE RATE = 48.76 CFS AT 1.499 HOURS BASIN AREA = .0301 SQ. MI.

COMPUTE NM HYD ID=21 HYD NO=121.0 AREA=0.04313 SQ MI
(A,B,C,D) 0 30 10 60
TP=0.187 HR MASS RAINFALL=-1

K = .101915HR TP = .187000HR K/TP RATIO = .545000 SHAPE CONSTANT, N = 7.106420
UNIT PEAK = 72.829 CFS UNIT VOLUME = .9996 B = 526.28 P60 = 1.9700
AREA = .025878 SQ MI IA = .10000 INCHES INF = .04000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

K = .175991HR TP = .187000HR K/TP RATIO = .941129 SHAPE CONSTANT, N = 3.757020
UNIT PEAK = 31.241 CFS UNIT VOLUME = .9997 B = 338.63 P60 = 1.9700
AREA = .017252 SQ MI IA = .46250 INCHES INF = 1.14500 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=21 CODE=1

PARTIAL HYDROGRAPH 121.00

RUNOFF VOLUME = 1.55983 INCHES = 3.5880 ACRE-Feet
PEAK DISCHARGE RATE = 86.08 CFS AT 1.565 HOURS BASIN AREA = .0431 SQ. MI.

ADD HYD ID=21 SUM NO=121.1 IDS=18 & 21
PRINT HYD ID=21 CODE=1

PARTIAL HYDROGRAPH 121.10

RUNOFF VOLUME = 1.42019 INCHES = 4.6021 ACRE-Feet
PEAK DISCHARGE RATE = 116.09 CFS AT 1.532 HOURS BASIN AREA = .0608 SQ. MI.

COMPUTE NM HYD ID=22 HYD NO=122.0 AREA=0.00292 SQ MI
(A,B,C,D) 0 30 10 60
TP=0.13333 HR MASS RAINFALL=-1

K = .072665HR TP = .133330HR K/TP RATIO = .545000 SHAPE CONSTANT, N = 7.106420
UNIT PEAK = 6.9154 CFS UNIT VOLUME = .9978 B = 526.28 P60 = 1.9700
AREA = .001752 SQ MI IA = .10000 INCHES INF = .04000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

K = .125481HR TP = .133330HR K/TP RATIO = .941129 SHAPE CONSTANT, N = 3.757020
UNIT PEAK = 2.9665 CFS UNIT VOLUME = .9956 B = 338.63 P60 = 1.9700
AREA = .001168 SQ MI IA = .46250 INCHES INF = 1.14500 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=22 CODE=1

PARTIAL HYDROGRAPH 122.00

RUNOFF VOLUME = 1.55983 INCHES = .2429 ACRE-Feet
PEAK DISCHARGE RATE = 6.97 CFS AT 1.499 HOURS BASIN AREA = .0029 SQ. MI.

ADD HYD ID=22 SUM NO=122.1 IDS=16 & 22
PRINT HYD ID=22 CODE=1

PARTIAL HYDROGRAPH 122.10

RUNOFF VOLUME = .83641 INCHES = 3.2560 ACRE-Feet
PEAK DISCHARGE RATE = 105.25 CFS AT 1.499 HOURS BASIN AREA = .0730 SQ. MI.

COMPUTE NM HYD ID=1 HYD NO=152.0 AREA=0.13048 SQ MI
(A,B,C,D) 0 45 20 35
TP=0.1476 HR MASS RAINFALL=-1

K = .081436HR TP = .147600HR K/TP RATIO = .551735 SHAPE CONSTANT, N = 6.995647
UNIT PEAK = 161.21 CFS UNIT VOLUME = .9999 B = 521.05 P60 = 1.9700
AREA = .045668 SQ MI IA = .10000 INCHES INF = .04000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

K = .133830HR TP = .147600HR K/TP RATIO = .906708 SHAPE CONSTANT, N = 3.906945
UNIT PEAK = 200.49 CFS UNIT VOLUME = 1.000 B = 348.92 P60 = 1.9700
AREA = .084812 SQ MI IA = .45385 INCHES INF = 1.12077 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=1 CODE=1

PARTIAL HYDROGRAPH 152.00

RUNOFF VOLUME = 1.26174 INCHES = 8.7803 ACRE-Feet
PEAK DISCHARGE RATE = 253.89 CFS AT 1.532 HOURS BASIN AREA = .1305 SQ. MI.

COMPUTE NM HYD ID=2 HYD NO=153.0 AREA=0.05022 SQ MI
(A,B,C,D) 0 45 15 40
TP=0.1412 HR MASS RAINFALL=-1

K = .076954HR TP = .141200HR K/TP RATIO = .545000 SHAPE CONSTANT, N = 7.106420
UNIT PEAK = 74.871 CFS UNIT VOLUME = 1.000 B = 526.28 P60 = 1.9700
AREA = .020088 SQ MI IA = .10000 INCHES INF = .04000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

K = .132887HR TP = .141200HR K/TP RATIO = .941129 SHAPE CONSTANT, N = 3.757027
UNIT PEAK = 72.264 CFS UNIT VOLUME = 1.000 B = 338.63 P60 = 1.9700
AREA = .030132 SQ MI IA = .46250 INCHES INF = 1.14500 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=2 CODE=1

PARTIAL HYDROGRAPH 153.00

RUNOFF VOLUME = 1.31174 INCHES = 3.5133 ACRE-FEET
PEAK DISCHARGE RATE = 101.21 CFS AT 1.532 HOURS BASIN AREA = .0502 SQ. MI.

COMPUTE NM HYD ID=3 HYD NO=162.0 AREA=0.01659 SQ MI
(A,B,C,D) 0 40 35 25
TP=0.13333 HR MASS RAINFALL=-1

K = .072665HR TP = .133330HR K/TP RATIO = .545000 SHAPE CONSTANT, N = 7.106420
UNIT PEAK = 16.371 CFS UNIT VOLUME = .9986 B = 526.28 P60 = 1.9700
AREA = .004148 SQ MI IA = .10000 INCHES INF = .04000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

K = .120147HR TP = .133330HR K/TP RATIO = .901127 SHAPE CONSTANT, N = 3.932611
UNIT PEAK = 32.723 CFS UNIT VOLUME = 1.000 B = 350.65 P60 = 1.9700
AREA = .012443 SQ MI IA = .43000 INCHES INF = 1.05400 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=3 CODE=1

PARTIAL HYDROGRAPH 162.00

RUNOFF VOLUME = 1.17826 INCHES = 1.0425 ACRE-FEET
PEAK DISCHARGE RATE = 32.76 CFS AT 1.499 HOURS BASIN AREA = .0166 SQ. MI.

COMPUTE RATING CURVE CID=1 VS NO=1 CODE=-1 SLP=.027 DIA=2.5 FT N=.013

RATING CURVE PIPE SECTION 1.0

WATER SURFACE ELEV	FLOW AREA SQ FT	FLOW RATE CFS	MAX WIDTH FT
.00	.00	.00	.00
.13	.10	.35	1.11
.26	.27	1.53	1.53
.39	.49	3.57	1.82
.52	.74	6.42	2.03
.65	1.02	10.02	2.19
.78	1.31	14.30	2.32
.91	1.62	19.15	2.41
1.04	1.94	24.49	2.47
1.17	2.26	30.19	2.50
1.30	2.59	36.13	2.50
1.43	2.91	42.18	2.50
1.56	3.23	48.19	2.50
1.69	3.54	54.01	2.50
1.82	3.84	59.46	2.50
1.95	4.12	64.34	2.50
2.08	4.37	68.40	2.50
2.21	4.60	71.31	2.50
2.35	4.78	72.50	2.50
2.50	4.91	72.50	2.50

COMPUTE TRAVEL TIME ID=6 REACH NO=1 NO VS=1 L=1600 FT SLP=.027

TRAVEL TIME TABLE

REACH= 1.0

WATER DEPTH FEET	AVERAGE AREA SQ. FT.	FLOW RATE CFS	TRAVEL TIME HRS
.130	.098	.35	.1227
.261	.271	1.53	.0786
.391	.490	3.57	.0611
.521	.741	6.42	.0514
.651	1.017	10.02	.0451
.782	1.312	14.30	.0408
.912	1.620	19.15	.0376
1.042	1.937	24.49	.0352
1.173	2.261	30.19	.0333
1.303	2.586	36.13	.0318
1.433	2.910	42.18	.0307
1.563	3.229	48.19	.0298
1.694	3.540	54.01	.0291
1.824	3.837	59.46	.0287
1.954	4.117	64.34	.0284
2.084	4.373	68.40	.0284
2.215	4.599	71.31	.0287
2.345	4.783	72.50	.0293
2.500	4.909	72.50	.0301

ROUTE ID=6 HYD NO=162.9 INFLOW ID=3 DT=0 HR
PRINT HYD ID=6 CODE=1

PARTIAL HYDROGRAPH 162.90

RUNOFF VOLUME = 1.17827 INCHES = 1.0425 ACRE-FEET
PEAK DISCHARGE RATE = 32.00 CFS AT 1.532 HOURS BASIN AREA = .0166 SQ. MI.

COMPUTE NM HYD ID=4 HYD NO=163.0 AREA=0.05291 SQ MI
(A,B,C,D) 0 40 30 30
TP=0.13333 HR MASS RAINFALL=-1

K = .072665HR TP = .133330HR K/TP RATIO = .545000 SHAPE CONSTANT, N = 7.106420
UNIT PEAK = 62.653 CFS UNIT VOLUME = .9992 B = 526.28 P60 = 1.9700
AREA = .015873 SQ MI IA = .10000 INCHES INF = .04000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

K = .121085HR TP = .133330HR K/TP RATIO = .908161 SHAPE CONSTANT, N = 3.900325
UNIT PEAK = 96.799 CFS UNIT VOLUME = 1.000 B = 348.47 P60 = 1.9700
AREA = .037037 SQ MI IA = .43571 INCHES INF = 1.07000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=4 CODE=1

PARTIAL HYDROGRAPH 163.00

RUNOFF VOLUME = 1.22797 INCHES = 3.4652 ACRE-FeET
PEAK DISCHARGE RATE = 107.13 CFS AT 1.499 HOURS BASIN AREA = .0529 SQ. MI.

COMPUTE NM HYD ID=5 HYD NO=200.0 AREA=0.03004 SQ MI
(A,B,C,D) 0 45 15 40
TP=0.1453 HR MASS RAINFALL=-1

K = .079189HR TP = .145300HR K/TP RATIO = .545000 SHAPE CONSTANT, N = 7.106420
UNIT PEAK = 43.522 CFS UNIT VOLUME = .9998 B = 526.28 P60 = 1.9700
AREA = .012016 SQ MI IA = .10000 INCHES INF = .04000 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

K = .136746HR TP = .145300HR K/TP RATIO = .941129 SHAPE CONSTANT, N = 3.757027
UNIT PEAK = 42.006 CFS UNIT VOLUME = .9999 B = 338.63 P60 = 1.9700
AREA = .018024 SQ MI IA = .46250 INCHES INF = 1.14500 INCHES PER HOUR
RUNOFF COMPUTED BY INITIAL ABSTRACTION/INFILTRATION NUMBER METHOD - DT = .033300

PRINT HYD ID=5 CODE=1

PARTIAL HYDROGRAPH 200.00

RUNOFF VOLUME = 1.31174 INCHES = 2.1016 ACRE-FeET
PEAK DISCHARGE RATE = 59.95 CFS AT 1.532 HOURS BASIN AREA = .0300 SQ. MI.

ADD HYD ID=1 SUM NO=152.1 IDS=1 & 6
PRINT HYD ID=1 CODE=1

PARTIAL HYDROGRAPH 152.10

RUNOFF VOLUME = 1.25232 INCHES = 9.8228 ACRE-FeET
PEAK DISCHARGE RATE = 285.89 CFS AT 1.532 HOURS BASIN AREA = .1471 SQ. MI.

***** ROUTE FLOWS FROM KATHRYN TO THAXTON IN 72" RCP
 ***** NOTE THAT CAPACITY EXCEEDED (real slope=0.21%)
 COMPUTE RATING CURVE CID=1 VS NO=1 CODE=-1 SLP=.0045 DIA=6.0 FT N=.013

RATING CURVE PIPE SECTION 1.0			
WATER SURFACE ELEV	FLOW AREA SQ FT	FLOW RATE CFS	MAX WIDTH FT
.00	.00	.00	.00
.31	.56	1.49	2.67
.63	1.56	6.47	3.67
.94	2.82	15.04	4.36
1.25	4.27	27.05	4.87
1.56	5.86	42.23	5.27
1.88	7.55	60.26	5.56
2.19	9.33	80.73	5.78
2.50	11.16	103.22	5.92
2.81	13.02	127.24	5.99
3.13	14.90	152.28	6.00
3.44	16.76	177.78	6.00
3.75	18.60	203.13	6.00
4.06	20.39	227.67	6.00
4.38	22.10	250.65	6.00
4.69	23.71	271.22	6.00
5.00	25.19	288.33	6.00
5.32	26.49	300.57	6.00
5.63	27.55	305.61	6.00
6.00	28.27	305.61	6.00

COMPUTE TRAVEL TIME ID=3 REACH NO=1 NO VS=1 L=1350 FT SLP=.0045

TRAVEL TIME TABLE
 REACH= 1.0

WATER DEPTH FEET	AVERAGE AREA SQ. FT.	FLOW RATE CFS	TRAVEL TIME HRS
.313	.562	1.49	.1414
.625	1.564	6.47	.0906
.938	2.824	15.04	.0704
1.251	4.271	27.05	.0592
1.563	5.859	42.23	.0520
1.876	7.554	60.26	.0470
2.189	9.329	80.73	.0433
2.501	11.159	103.22	.0405
2.814	13.022	127.24	.0384
3.127	14.897	152.28	.0367
3.439	16.764	177.78	.0354
3.752	18.601	203.13	.0343
4.065	20.388	227.67	.0336
4.377	22.101	250.65	.0331
4.690	23.712	271.22	.0328
5.003	25.189	288.33	.0328

	5.315	26.489	300.57	.0330
	5.628	27.547	305.61	.0338
	6.000	28.274	305.61	.0347

ROUTE ID=3 HYD NO=152.9 INFLOW ID=1 DT=0 HR
 PRINT HYD ID=3 CODE=1

PARTIAL HYDROGRAPH 152.90

RUNOFF VOLUME = 1.25233 INCHES = 9.8228 ACRE-FEET
 PEAK DISCHARGE RATE = 270.91 CFS AT 1.565 HOURS BASIN AREA = .1471 SQ. MI.

ADD HYD ID=2 SUM NO=153.2 IDS=2 & 4
 PRINT HYD ID=2 CODE=1

PARTIAL HYDROGRAPH 153.20

RUNOFF VOLUME = 1.26876 INCHES = 6.9785 ACRE-FEET
 PEAK DISCHARGE RATE = 208.01 CFS AT 1.499 HOURS BASIN AREA = .1031 SQ. MI.

ADD HYD ID=1 SUM NO=153.1 IDS=3 & 2
 PRINT HYD ID=1 CODE=1

PARTIAL HYDROGRAPH 153.10

RUNOFF VOLUME = 1.25910 INCHES = 16.8013 ACRE-FEET
 PEAK DISCHARGE RATE = 476.00 CFS AT 1.532 HOURS BASIN AREA = .2502 SQ. MI.

***** ROUTE FLOWS FROM KATHRYN TO THAXTON IN 72" RCP
 ***** NOTE THAT CAPACITY EXCEEDED (real slope=0.21%)
 COMPUTE RATING CURVE CID=1 VS NO=1 CODE=-1 SLP=.012 DIA=6.0 FT N=.013

RATING CURVE PIPE SECTION 1.0			
WATER SURFACE ELEV	FLOW AREA SQ FT	FLOW RATE CFS	MAX WIDTH FT
.00	.00	.00	.00
.31	.56	2.43	2.67
.63	1.56	10.56	3.67
.94	2.82	24.56	4.36
1.25	4.27	44.17	4.87
1.56	5.86	68.97	5.27
1.88	7.55	98.40	5.56
2.19	9.33	131.83	5.78

2.50	11.16	168.55	5.92
2.81	13.02	207.78	5.99
3.13	14.90	248.67	6.00
3.44	16.76	290.32	6.00
3.75	18.60	331.72	6.00
4.06	20.39	371.79	6.00
4.38	22.10	409.32	6.00
4.69	23.71	442.90	6.00
5.00	25.19	470.84	6.00
5.32	26.49	490.84	6.00
5.63	27.55	499.05	6.00
6.00	28.27	499.05	6.00

COMPUTE TRAVEL TIME ID=3 REACH NO=1 NO VS=1 L=2250 FT SLP=.012

TRAVEL TIME TABLE

REACH= 1.0

WATER DEPTH FEET	AVERAGE AREA SQ. FT.	FLOW RATE CFS	TRAVEL TIME HRS
.313	.562	2.43	.1443
.625	1.564	10.56	.0925
.938	2.824	24.56	.0719
1.251	4.271	44.17	.0604
1.563	5.859	68.97	.0531
1.876	7.554	98.40	.0480
2.189	9.329	131.83	.0442
2.501	11.159	168.55	.0414
2.814	13.022	207.78	.0392
3.127	14.897	248.67	.0374
3.439	16.764	290.32	.0361
3.752	18.601	331.72	.0350
4.065	20.388	371.79	.0343
4.377	22.101	409.32	.0337
4.690	23.712	442.90	.0335
5.003	25.189	470.84	.0334
5.315	26.489	490.84	.0337
5.628	27.547	499.05	.0345
6.000	28.274	499.05	.0354

ROUTE ID=3 HYD NO=153.9 INFLOW ID=1 DT=0 HR
PRINT HYD ID=3 CODE=1

PARTIAL HYDROGRAPH 153.90

RUNOFF VOLUME = 1.25910 INCHES = 16.8013 ACRE-FEET
PEAK DISCHARGE RATE = 457.70 CFS AT 1.565 HOURS BASIN AREA = .2502 SQ. MI.

ADD HYD ID=1 SUM NO=200.1 IDS=3 & 5
PRINT HYD ID=1 CODE=1

PARTIAL HYDROGRAPH 200.10

RUNOFF VOLUME = 1.26474 INCHES = 18.9028 ACRE-Feet
PEAK DISCHARGE RATE = 513.06 CFS AT 1.565 HOURS BASIN AREA = .2802 SQ. MI.

ADD HYD ID=2 SUM NO=202.0 IDS=20 & 21
PRINT HYD ID=2 CODE=1

PARTIAL HYDROGRAPH 202.00

RUNOFF VOLUME = 1.28511 INCHES = 6.2254 ACRE-Feet
PEAK DISCHARGE RATE = 164.14 CFS AT 1.532 HOURS BASIN AREA = .0908 SQ. MI.

ADD HYD ID=1 SUM NO=202.1 IDS=1 & 2
PRINT HYD ID=1 CODE=1

PARTIAL HYDROGRAPH 202.10

RUNOFF VOLUME = 1.26972 INCHES = 25.1282 ACRE-Feet
PEAK DISCHARGE RATE = 671.39 CFS AT 1.565 HOURS BASIN AREA = .3711 SQ. MI.

ADD HYD ID=1 SUM NO=700.1 IDS=1 & 22
PRINT HYD ID=1 CODE=1

HYDROGRAPH FROM AREA 700.10

RUNOFF VOLUME = 1.19850 INCHES = 28.3841 ACRE-Feet
PEAK DISCHARGE RATE = 769.60 CFS AT 1.532 HOURS BASIN AREA = .4441 SQ. MI.

FINISH


NORMAL PROGRAM FINISH END TIME (HR:MIN:SEC) = 08:07:46

1. The first part of the document is a title page. It contains the title "THE HISTORY OF THE UNITED STATES OF AMERICA" and the author "BY JAMES M. SMITH".






GRATING CAPACITIES FOR TYPE DOUBLE

"C," AND "D"



GRATING & GUTTER PLAN

TYPICAL HALF STREET SECTION
(ABOVE BASIN)



SOUTH BROADWAY SECTOR DRAINAGE MANAGEMENT PLAN

Developed Conditions Report

SEPTEMBER 1990



BOHANNAN-HUSTON, INC.
7500 JEFFERSON NE
ALBUQUERQUE, NM 87109

1.0 INTRODUCTION

This report presents the results of the Existing and Developed Conditions study for the South Broadway Sector Drainage Management Plan, and is prepared for the City of Albuquerque under the authorization of the Architect/Engineer's Agreement #0259-01.

The South Broadway study area lies between Interstate 25 on the east, the Atchison, Topeka and Santa Fe Railroad on the West, Lomas on the north and the City Limits on the south. The City Limits on the south run east and west parallel to, and approximately 1700 feet south of, Woodward Road. This area was included in the Albuquerque Master Drainage Study, Volume I, prepared by Bohannon-Huston, Inc. in January of 1991. This current drainage study analyzes the area in more detail, paying particular attention to time varying pipe hydraulics and the Bell/Commercial storm water pumping station.

2.0 DESCRIPTION OF THE STUDY AREA

The study area (2.1 square miles) encompasses much more than the South Broadway neighborhood. The northern portion between Lomas and Central includes the southern tip of Martinez Town, although in the last ten years, its once residential character has been impacted by the growth of the St. Joseph's Hospital complex and construction of Senior Citizens housing.

Between Central and Coal lies the Huning/Highland addition, the first suburb to be built on the East Mesa. This area is currently being "gentrified" by rehabilitation of the Victorian houses in the area. The South Broadway neighborhood lies south of Coal, east and west of Broadway, and is almost entirely residential in nature; except for existing commercial uses located on Broadway.

The area south of Gibson and west of Broadway is known as the San Jose Barrio, historically an Hispanic farming community. The area is now primarily residential with scattered commerce and industry. The General Electric Plant in the area is one of Albuquerque's larger employers.

Topographically, the study area slopes from I-25 on the east down to the AT&SF Railroad on the west. The railroad forms a drainage barrier on the west resulting in flooding in the low lying areas just east of the tracks. The north to south slope is slight, with an overall slope of .2%.

3.0 HISTORY OF FLOODING

Construction of Interstate 25 and the South Diversion Channel has effectively diverted most off-site flows from entering the study area from the east. Thus, historic flooding from east-west arroyos passing through the study area is no longer a problem. Present flooding is caused by on-site runoff which collects against the railroad tracks in low lying areas. Approximately half of the study area lies east of Broadway. This portion is characterized by 2% to 3% slopes from east to west, and drains quickly and efficiently.

4.0 AGENCIES/JURISDICTION/PERMITS/AGREEMENTS

Two entities play the major roles in providing drainage for the area--the City of Albuquerque and the Middle Rio Grande Conservancy District (MRGCD). The only outfall for the area is the San Jose Drain, a conveyance facility owned and maintained by the MRGCD. In contrast, all storm sewers in the area were constructed and are maintained by the City, and all empty into the San Jose Drain.

While the drain was constructed to lower the water table in the adjoining agricultural land, an agreement was finalized in September,

1958 between the MRGCD, the Bureau of Reclamation and the City of Albuquerque to allow the City to discharge storm drainage into the San Jose Drain. Subsequently, additional agreements for City discharge into the drain have been consummated, though none as sweeping as the 1958 accord. A record of all agreements and permits concerning the San Jose Drain in the study area can be found in Appendix II, including the historic 1958 document.

It should be noted that the 1958 agreement does not specify an allowable discharge rate. Rather, the permit was attached to an engineering plan set, and authorized discharges as shown on the plan set. These discharges are shown as ditches or pipes emptying into the San Jose Drain. This was the procedure used for several other discharge agreements between the City and MRGCD. The referenced plan sets are archived in the MRGCD library.

Note that the record of permits found in Appendix II contains agreements between the MRGCD and HOH-City entities, as well as permits for domestic water lines crossing the San Jose Drain. While these permits do not directly pertain to this drainage study, each one impacts the Drain, and should be considered if improvements to the drain are considered in the future.

The Albuquerque Metropolitan Arroyo Flood Control Authority (AMAFCA) South Diversion Channel crosses the southeast corner of the study area, as shown on Plate M-14 in Appendix I. The portion of the study area east of the South Diversion Channel drains into the Diversion Channel and leaves the study area. This area and the South Diversion Channel are not addressed in this report.

Bernalillo County has no drainage responsibilities in the study area.

5.0 SOURCES OF INFORMATION

Surface drainage patterns were determined from contours on City of Albuquerque topographic orthophoto mapping at a nominal scale of 1"=500'. Information on existing storm drainage facilities was obtained from various sources including:

- o South Broadway Neighborhoods Sector Development Plan, July, 1986.
- o City of Albuquerque Drainage Facilities maps.
- o As-Built drawings of drainage facilities.
- o Albuquerque Master Drainage Study, Volume I, January, 1981.
- o Volume II, Albuquerque Storm Water Pumping Stations.
- o Southeast Valley Drainage Management Plan, San Jose Drain and Vicinity, AMAFCA.
- o Bell Commercial Pump Station #37--Drainage Study, City of Albuquerque, July 15, 1987.
- o Bell Commercial Pump Station logs.
- o Field Reconnaissance by Buchanan-Huston, Inc. personnel.
- o Field Surveys by Albuquerque Surveying Company.
- o Fairbanks - Horse Pump Curves.

6.0 HYDROLOGY

The City of Albuquerque is currently rethinking its hydrologic approach, principally through a collaboration between the University of New Mexico Civil Engineering Department, AMAFCA and City of Albuquerque hydrology staff. While this new hydrology is being used for many drainage studies within the City area, consensus has not been reached and the new hydrologic approach has not been approved by the City. It is anticipated that use of the new hydrology would produce runoff results much different than those obtained in the AIDS report of 1981, the current guiding document for drainage planning in the South Broadway area.

Because of these considerations, the hydrologic approach used for the AMDS Volumes I, II and III has been chosen for this study. It is felt that this approach maintains continuity in drainage philosophy throughout the City and conforms to a hydrologic approach approved by the City of Albuquerque. Details of the hydrologic approach are presented in the following sections.

6.1 Precipitation. The AMDS reports use the following equation to generate a mass rainfall table:

$$R(T) = Q \times A \times T^B \text{ where:}$$

- R(T) = Accumulate rainfall at time T (in inches)
- Q = Total Rainfall from the storm (in inches)
- T = Time elapsed (in hours)
- A = Empirical coefficient - determined by linear regression or other means
- B = Empirical exponent - determined by linear regression or other means

The following variables were used for the AMDS hydrology and for this study:

	A	B	Q	T
100-year	.85	.090521	2.4	6.0
10-year	.85	.090521	1.6	6.0

The resulting rainfall hyetograph reflects an event with high intensity in the early stages of the storm. It should be kept in mind that runoff is the result of many variables including total precipitation, hyetograph shape, runoff model, curve numbers, etc. It is the combined effect of all these variables that should be compared with field data and previous studies, rather than any single variable.

The modeled storm is the 6-hour event, the storm commonly used in the Albuquerque area for sizing storm sewers and channel capacities. Note that for design of reservoirs with detention times greater than 6 hours, the 24-hour storm should be used for analysis.

6.2 Rainfall-Runoff Model. The previous City study of the area, AMDS Volume I, used a combination of HYMO and RADS, modeling the runoff of basins east of Broadway with HYMO. RADS, developed by Bohannon-Huston, Inc., was written specifically to predict flooding in flat topography. It was used in the AMDS Volume I to generate runoff volumes for the South Broadway basins west of Broadway and to route both the RADS generated flows and HYMO generated flows. It is our opinion that the use of RADS for the basins between Broadway and the Railroad was inappropriate, as these basins have steep (2%) slopes from east to west and cannot be adequately modeled by RADS.

HYMO (Hydrologic Modeling), a computer program developed by the Agricultural Research Service of the U.S. Department of Agriculture, has been used by the Albuquerque engineering community for many years and has been approved by the City of Albuquerque for City hydrologic analysis. Because of the inappropriateness of RADS for the study area and because of City and BHI satisfaction with HYMO in the past, the HYMO model was chosen to model the entire study area.

In order to maintain continuity with the AMDS Volume I study and to allow comparison between the old and new studies, the new study used AMDS Volume I basin boundaries and basin identifications wherever possible. Basin characteristics from AMDS I for basins east of Broadway were also used where appropriate (area, land use, curve numbers, times to peak). However, as opposed to the rest of the AMDS volumes, Volume I combined the impervious and pervious portions of each basin using a composite curve number. In order to bring all the AMDS studies into conformity, this study modeled all basins using separate pervious and impervious modeling.

The hydrologic course of action for the project can be summarized as follows:

1. Runoff for basins previously modeled with RADS were remodeled using HYMO as in AMDS Volumes II-III studies.
2. Runoff for basins previously modeled with HYMO were preserved except that the impervious areas of each basin were modeled separately from the pervious areas.
3. Hydrographs for runoff entering the study area from the east were taken from the AMDS Volume II Restudy without making any adjustments. These hydrographs were generated with HYMO during the Restudy, and used the "Heggen" rainfall distribution. The times-to-peak of the Restudy runoff hydrographs will be later than for the hydrographs generated inside the study area because the Heggen rainfall distribution places the most intense rainfall later in the storm (see Appendix V). However, this mismatch in peaks was considered acceptable because (1) Restudy flows contribute little to the system discharge, (2) reanalysis of the AMDS Volume II using a more compatible rainfall would be a large effort and is outside the scope of the contract.

6.2.1 Runoff Hydrographs. A unit hydrograph approach is used by HYMO for generating runoff hydrographs for each subbasin. Three equations (found in the HYMO Users' Manual) define the rising limb and the recession of the hydrograph. The shape of the unit hydrograph is defined by two variables, the time to peak, T_p , and the recession constant, K . The HYMO program will compute the values of T_p and K or allow the user to specify them. The following equations were used to define these variables:

$$T_c = \frac{.0078 \times L^{.77}}{S^{.385}} \quad (\text{Kirpich Equation})$$

$$\begin{aligned} T_c &= \text{Time of concentration in minutes} \\ L &= \text{Length of longest water pathway in feet} \\ S &= \text{Slope of longest water pathway} \\ \text{Time to Peak } T_p &= 2/3 T_c \quad \text{in minutes} \\ \text{Recession Constant } K &= 1/2 T_p \quad \text{in minutes} \end{aligned}$$

Next, the depth of runoff in inches is found by applying the Soil Conservation Service (SCS) rainfall-runoff relationship:

$$Q = (P - (200/CN) + 2)^2 / (P + (800/CN) - 8)$$

Where: Q = runoff in inches depth over the drainage area
 P = accumulated rainfall in inches
 CN = curve number

Storm outflow hydrographs are then computed by merging the accumulated depth of runoff with the unit hydrograph.

In the pervious/impervious approach, a runoff hydrograph is generated for the pervious and impervious portions of each basin separately, then added together to produce the outflow hydrograph for the basin.

Basin boundaries are shown on the Modeling Map in the back pocket of this report. Basin characteristics are tabulated in Table 1 on the following page along with the 10-year and 100-year peak discharges from each basin.

6.2.2 Routing. The South Broadway storm sewer system contains a pumping station and several cross-connections, features not normally modeled in storm sewers. Additionally, analysis of the system trunk lines using pressure flow is desired to see if significant additional capacity is present in the system. While HYMO can model routing of surface flow, street flow, channel flow and pipe flow, it cannot model pumps, pipe networks (interconnections) or pressure flow. Therefore,

we have chosen the Storm Water Management Model (SWMM) developed by the EPA for routing of the hydrographs generated by HYMO or taken from the Volume II Restudy. SWMM can handle not only the surface flow, street flow, channel flow and pipe flow, but also the pumps, pipe cross-connections and pressure flow.

The EXTRAN portion of SWMM is intended for application in systems where the assumption of steady flow, for purposes of computing back-water profiles, cannot be made. The program solves the full dynamic equations for gradually varied flow (St. Venant equations) using an explicit solution technique to step forward in time.

6.2.3 Existing Conditions Curve Numbers. HYMO uses the SCS Curve Number method to determine runoff volumes. The runoff curve numbers account for the combined effect of soil types, vegetative cover, land use and antecedent moisture content. For this project, Antecedent Moisture Conditions II, recommended by SCS, was used. In addition, it was assumed that all commercial and residential areas were free discharging (no on-site ponding).

In this analysis, pervious and impervious areas within a basin were considered separately. The impervious areas were assigned a curve number of 95 and their runoff calculated separately from the pervious areas. The SCS method allows for use of a curve number of 95 in "warmer climates." Additionally, the City of Albuquerque effort to revise its Hydrology procedure is now moving toward abstraction and infiltration values that will reduce the runoff from impervious areas and result in a volume equivalent to the runoff from a CN of 95 at the 6-hour storm.

For the pervious areas, the soil type was determined from the SCS Soil Survey of Bernalillo County. Land use and percentages of impervious areas were determined through windshield surveys and aerial photographs. Table 1 presents these basin characteristics. Note that

characteristics for those basins previously modeled with HYMO in the AMDS Volume I study were not available.

6.2.4 Developed Conditions Curve Numbers. While most of the study area was fully developed at the time of the Existing Conditions analysis, further development is expected in 7 of the 28 basins. In keeping with the hydrologic assumptions detailed above, the percents of impervious areas were increased in these basins to reflect increased development. Table 2 presents the changes in basin hydrology for the 7 subbasins where development is expected. Free discharge is assumed from all developing areas.

6.2.5 Modeling Map. The modeling map for the study area can be found in the pocket at the end of this report. Subbasin boundaries, existing drainage facilities and analysis points are shown. Since only the trunk lines are modeled, these lines are accentuated on the map. Surface flow routing is also indicated.

6.2.6 Off-Site Flows. The area to the east of Interstate 25 was analyzed in the AMDS Restudy, Volume II. Possible flow paths into the South Broadway area were investigated during the Restudy with the following results

Analysis Point	Peak 100-Year Discharge (cfs)	Peak 10-Year Discharge (cfs)
APV1	52	20
APW1-SS3	23	9
APW1	0	0
APX1	0	0
APY1	0	0
APZ1SS-2	0	0
APAA1-1	6	0
APAA1-2	11	0
APAA1-3	40	14
APBB1	0	0
APDD1	13	0
APFF1	5	0
APCC1	SOUTH DIVERSION CHANNEL	
APGG1	TO SOUTH DIVERSION CHANNEL	
APHH1	TO SOUTH DIVERSION CHANNEL	

BASIN (SQ. MI.)	AREA	LENGTH OF FLOWPATH @ TOP @ BOTTOM	ELEV. ELEV.	SLOPE TYPE-A	SOIL TYPE-B	LAND USE	CN	IMPERV AREA	PERV AREA	TC	TP	10-YR 100-YR					
												Qpk CFS	Qpk CFS				
SJ-1	0.0795	3500	4968.0	4950	0.0051	65	35	RANGE-FAIR	60	30	0.02385	0.05564	31.8	0.3532	0.177	26	48
SJ-2	0.0989	2500	4959.0	4948	0.0044	30	70	RANGE-FAIR	65	35	0.0346	0.06426	26.0	0.2894	0.145	45	88
SJ-3	0.0237	1500	4965.0	4946.5	0.0123	35	65	RANGE-FAIR	64	35	0.0083	0.01541	11.8	0.1313	0.066	22	41
SJ-4	0.1881	2375	4964.0	4946.4	0.0074	28	72	RANGE-FAIR	66	35	0.033	0.0612	20.5	0.2276	0.114	54	105
SJ-5	0.0414	2500	4963.5	4944	0.0078	50	50	RANGE-FAIR	62	40	0.01654	0.02482	20.9	0.2322	0.116	26	48
SJN-6	0.0526	3500	4945.0	4939.8	0.0015	0	100	RANGE-FAIR	70	30	0.01578	0.03682	51.3	0.5697	0.285	12	26
SJN-701	0.0788	2250	4968.0	4944	0.0107	91	9	RANGE-FAIR	69	30	0.02364	0.05516	17.1	0.1898	0.095	46	96
SJ-7	0.0684	2550	4966.0	4943.9	0.0087	30	70	RANGE-FAIR	65	32	0.02188	0.0465	20.4	0.2264	0.113	36	70
SJ-8	0.0460	1125	4960.0	4939	0.0187	10	90	RANGE-POOR	78	20	0.00921	0.03682	10.0	0.1111	0.056	41	99
SJ-9SS	0.0419	1600	4942.0	4938.2	0.0024	0	100	RANGE-POOR	79	35	0.01467	0.02724	23.4	0.2603	0.130	27	58
SJ-90L	0.0504	2300	4942.0	4936.8	0.0023	0	100	RANGE-POOR	79	35	0.01764	0.03276	31.6	0.3508	0.175	26	54
SJN-10	0.0167	1900	4942.5	4941	0.0008	0	100	RANGE-POOR	79	20	0.00333	0.01332	40.9	0.4540	0.227	5	12
SJN-710	0.0321	1700	5002.5	4938	0.0379	87	13	RANGE-POOR	69	4	0.00128	0.03083	10.0	0.1111	0.056	5	21
SJN-720	0.0409	2225	4996.0	4936.5	0.0267	90	10	RANGE-POOR	69	2	0.00082	0.04008	11.9	0.1321	0.066	3	20
SJN-730	0.0423	1750	4994.0	4945	0.028	70	30	RANGE-FAIR	62	40	0.01693	0.0254	10.0	0.1111	0.056	52	96
SJN-740	0.1302	2100	4941.0	4936	0.0024	0	100	RANGE-FAIR	70	40	0.0521	0.07814	28.9	0.3206	0.160	65	130
SJN-109	0.1042	3200	5017.0	4938.5	0.0245	85	15	RANGE-POOR	70	8	0.00834	0.09587	16.3	0.1806	0.090	20	65
SJN-100*	0.0970						54	60	0.0582	0.0388				0.1755	0.088	118	210
SJN-102*	0.1750						54	40	0.07	0.105				0.2112	0.106	121	215
SJN-105*	0.0710						54	35	0.02485	0.04615				0.1494	0.075	53	103
SJN-106*	0.0950						54	35	0.03325	0.06175				0.1799	0.090	66	117
SJN-150*	0.0750						54	35	0.02625	0.04875				0.1259	0.063	71	125
SJN-152*	0.1320						54	35	0.0462	0.0858				0.1476	0.074	109	194
SJN-153*	0.0620						54	40	0.0248	0.0372				0.1412	0.071	60	108
SJN-200*	0.0550						54	40	0.022	0.033				0.1453	0.073	53	94
SJN-202*	0.0820						54	10	0.0082	0.0738				0.1872	0.094	16	28
SJN-700*	0.0565						69	0	0	0.0565				0.1186	0.059	5	33
BJ-134	0.0660	3700	5073.0	4868	0.0554		54	65	0.0429	0.0231	13.3	0.1476	0.074	101	180		



* All basin data except percent impervious taken from original NADS report.

* All basin data except percent impervious taken from original NIDS report.

TABLE 2
HYDROLOGIC COMPARISON
EXISTING VS. FULL DEVELOPMENT

BASIN (SQ. MI.)	AREA	EXISTING DEVELOPMENT				FULL DEVELOPMENT				100-YR	
		CN	IMPERV	PERV	Qpk	CN	IMPERV	PERV	Qpk	CFS	CFS
SJ-8	0.0460	78	20	0.00921	0.03682	99	78	30	0.01381	0.03222	118
SJN-10	0.0167	79	20	0.00333	0.01332	12	79	30	0.005	0.01166	13
SJN-710	0.0321	69	4	0.00128	0.03083	21	69	40	0.01284	0.01927	73
SJN-720	0.0409	69	2	0.00082	0.04008	20	69	40	0.01636	0.02454	86
SJN-109	0.1042	70	8	0.00834	0.09587	65	70	40	0.04168	0.06253	169
SJN-202*	0.0820	54	10	0.0082	0.0738	28	54	30	0.0246	0.0574	84
SJN-700*	0.0565	69	0	0	0.0565	33	69	40	0.0226	0.0339	134

* All basin data except percent impervious taken from original NIDS report.



MAP KEY

LEGEND

- STUDY AREA BOUNDARY
- L14552 SWMM ANALYSIS POINT
- 10 YEAR FLOOD HAZARD AREA
- 100 YEAR FLOOD HAZARD AREA
- PROPOSED STORM SEWER

EXISTING UTILITIES

- SAS --- SANITARY SEWER, SIZE 12" or LARGER
- G --- GAS LINE, SIZE 6" or LARGER
- W --- WATER LINE, SIZE 10" or LARGER
- 12" SD --- 18" SD --- STORM DRAIN LINE, SIZE 10" or LARGER
(DENOTES CHANGE IN PIPE SIZE)


NOTE: EXISTING UTILITIES ARE SHOWN ON ARTERIAL AND COLLECTOR STREETS AND WHERE DRAINAGE FACILITIES ARE PROPOSED.

0 500 1000 1500 2000



SCALE IN FEET
1" = 500'



Orthophotography and topography
by Bohannon-Houston, Inc. from
aerial photograph dated 10-8-80



PG 498 3 - BOWEN, PAUL ROBERT
(under) 11 Bowden, Robert
BOWEN, PAUL ROBERT



LEGEND

- - - - - PROPOSED STORM DRAIN
- - - - - EXISTING GRADE
- STORM DRAIN LINE & MANHOLE IN PROFILE
- STORM DRAIN LINE & MANHOLE IN PLAN
- 100 YEAR STORM HYDRAULIC GRADE LINE
- 10 YEAR STORM HYDRAULIC GRADE LINE
- 100 YEAR STORM HYDRAULIC GRADE LINE W/IMPROVEMENT

1	2	3	4	5	6	7	8	9	10	11	12
SOUTH BROADWAY DRAINAGE MANAGEMENT STUDY ALAMO AVE., MECHAM ST. OLD SAN JOSE DRAIN & THE SAN JOSE DRAIN Sheet No. _____ Scale _____											
MI4N 8 S Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____ Station _____ Point _____ Scale _____ Notes _____											
Station _____ Point _____											

[illegible]

1949 2 (Total) 1,000
 (Total) 1,000
 1949 2 1,000

SJN-6

SJH-200

SJH-701

SJH-202

SJ-7

SJH-700

SJN-10

SJ-955

SJ-8

SJH-109

SJ-90L

SJN-710

SJN-740

SJN-720

AP-DDI

AP-EEI

AP-FFI

AP-CCI

Master plan Area
Indicated by Shading

N

Scale:
1" = 500'

SECTOR PLAN
BASIN MAP

PHASE 2



List of Scanned Files: See Hydrology Staff

H-16/D095
H-17/D027
H-17/D030
H-17/D035
H-17/D037
H-17/D049
H-17/D054A
H-17/D055
H-17/D057
H-17/D061
H-17/D063
H-17/D064
H-17/D064A
H-17/D065
H-17/D066
H-17/D067
H-17/D068
H-17/D069
H-17/D071
H-17/D082
H-17/D085
H-17/D086A
H-17/D087
H-17/D089
H-17/D091
H-17/D092
H-17/D093
H-17/D095
H-17/D097
H-17/D098
H-17D070
H-18/D042
H-18/D055
H-18/D056
H-18/D057
H-19/D003
H-19/D011
H-19/D015
H-19/D040
H-19/D041
H-19/D047
H-19/D047B
H-19/D059
H-19/D060
H-19/D061
H-19/D063
H-20/D003A
H-20/D027
H-20/D031
H-22/D035
H-22/D063
H-22/D065

●
●
●
●
●



Bingham, Brad L.

From: Sanchez, Teresa S.
Sent: Monday, July 16, 2007 10:19 AM
To: Bingham, Brad L.
Subject: RE: Senior Kitchen Site Meeting - Cancelled

Brad,

We are located at 714 7th Street - in the down town area - just South of Coal. Between 8th and Iron. It is a small residential street which is a dead-end. The Barelvas Community Center is the dead-end - we are the single story building just north of the center. The building is marked Barelvas in mosaic tiles.
Look forward to seeing you.

Teresa Sanchez
Executive Assistant
Department of Senior Affairs
City of Albuquerque
505.764.6469
505.764.6480 (FAX)
<http://www.cabq.gov>

From: Bingham, Brad L.
Sent: Monday, July 16, 2007 8:35 AM
To: Sanchez, Teresa S.
Subject: RE: Senior Kitchen Site Meeting - Cancelled

Can you tell me where your office is, I have never been there,
Thanks

From: Sanchez, Teresa S.
Sent: Friday, July 13, 2007 7:13 AM
To: Bingham, Brad L.
Subject: RE: Senior Kitchen Site Meeting - Cancelled

Brad,

Thank you. Again, we apologize for the inconvenience.

Thank you,
Teresa Sanchez
Executive Assistant
Department of Senior Affairs
City of Albuquerque
505.764.6469
505.764.6480 (FAX)
<http://www.cabq.gov>

7/19/2007

From: Bingham, Brad L.
Sent: Thursday, July 12, 2007 5:45 PM
To: Sanchez, Teresa S.; Adamsko, Linda M.; 'bill glasgow'; Hise, Blanca B.; Baca, John R.; Wardlaw, Rebecca E.; Baca, Barbara C.
Subject: RE: Senior Kitchen Site Meeting - Cancelled

I can make this next meeting

From: Sanchez, Teresa S.
Sent: Thursday, July 12, 2007 4:49 PM
To: Adamsko, Linda M.; 'bill glasgow'; Hise, Blanca B.; Baca, John R.; Wardlaw, Rebecca E.; Bingham, Brad L.; Baca, Barbara C.
Subject: RE: Senior Kitchen Site Meeting - Cancelled
Importance: High

Good Afternoon,
Due to unexpected conflict in scheduling, the meeting scheduled for tomorrow will need to be canceled. We apologize for the short notice and inconvenience it may have caused everyone.

Thursday, July 19th at 11:00am would be the next available date for the following individuals. Hopefully it will work for each of you as well. Please let me know.

Bill Glasgow
Blanca Hise
Barbara Baca

Thank you,
Teresa Sanchez
Executive Assistant
Department of Senior Affairs
City of Albuquerque
505.764.6469
505.764.6480 (FAX)
<http://www.cabq.gov>

From: Adamsko, Linda M.
Sent: Tuesday, July 10, 2007 2:00 PM
To: 'bill glasgow'; Hise, Blanca B.; Sanchez, Teresa S.; Baca, John R.; Wardlaw, Rebecca E.; Bingham, Brad L.
Subject: RE: Senior Kitchen Site

Greetings. Because of scheduling conflicts, I need to move the meeting on Friday, July 13 up to 10:30 at the Office of Senior Affairs. Does this work for all (most)? thanx for your patience.

Linda Adamsko
City of Albuquerque
Property Manager, Legal Department

7/19/2007

(505)768-3318

From: bill glasgow [mailto:bglasgow@rmkmarch.com]
Sent: Tuesday, July 10, 2007 11:25 AM
To: Adamsko, Linda M.
Subject: RE: Senior Kitchen Site

Hi Linda,

3:00 sounds good for me and Mark.

Thanks

Bill

From: Adamsko, Linda M. [mailto:LAdamsko@cabq.gov]
Sent: Friday, July 06, 2007 10:02 AM
To: bill glasgow
Subject: FW: Senior Kitchen Site

From: Adamsko, Linda M.
Sent: Friday, July 06, 2007 9:52 AM
To: Hise, Blanca B.; Bingham, Brad L.; 'bglasgow@rkkmarch.com'
Cc: Wardlaw, Rebecca E.; Sanchez, Teresa S.; Baca, John R.
Subject: Senior Kitchen Site

Greetings all. I would like to have a meeting on Friday, July 13 to discuss the drainage pond south of the senior kitchen parcel. PM is best for me, but I can arrange my schedule. Let me pull 3:00 out and see how this works for everyone. Thanx.

Linda Adamsko
City of Albuquerque
Property Manager, Legal Department
(505)768-3318

7/19/2007

Centralized Facility Property Meeting 19 July 2007

Agenda

- I. Is it advisable to acquire Lot 7 for expansion for the DSA facility?

- II. What are the costs to remediate any problems?

Hise, Blanca B.

From: Wardlaw, Rebecca E.
Sent: Friday, July 13, 2007 8:04 AM
To: Sanchez, Teresa S.; Adamsko, Linda M.; 'bill glasgow'; Hise, Blanca B.; Baca, John R.; Bingham, Brad L.; Baca, Barbara C.
Subject: RE: Senior Kitchen Site Meeting - Cancelled

I am available **Thursday, July 19th at 11:00 am**

From: Sanchez, Teresa S.
Sent: Thursday, July 12, 2007 4:49 PM
To: Adamsko, Linda M.; 'bill glasgow'; Hise, Blanca B.; Baca, John R.; Wardlaw, Rebecca E.; Bingham, Brad L.; Baca, Barbara C.
Subject: RE: Senior Kitchen Site Meeting - Cancelled
Importance: High

Good Afternoon,
Due to unexpected conflict in scheduling, the meeting scheduled for tomorrow will need to be canceled. We apologize for the short notice and inconvenience it may have caused everyone.

Thursday, July 19th at 11:00am would be the next available date for the following individuals. Hopefully it will work for each of you as well. Please let me know.

Bill Glasgow
Blanca Hise
Barbara Baca

Thank you,
Teresa Sanchez
Executive Assistant
Department of Senior Affairs
City of Albuquerque
505.764.6469
505.764.6480 (FAX)
<http://www.cabq.gov>

From: Adamsko, Linda M.
Sent: Tuesday, July 10, 2007 2:00 PM
To: 'bill glasgow'; Hise, Blanca B.; Sanchez, Teresa S.; Baca, John R.; Wardlaw, Rebecca E.; Bingham, Brad L.
Subject: RE: Senior Kitchen Site

Greetings. Because of scheduling conflicts, I need to move the meeting on Friday, July 13 up to 10:30 at the Office of Senior Affairs. Does this work for all (most)? thanx for your patience.

Linda Adamsko
City of Albuquerque

7/13/2007

Property Manager, Legal Department
(505)768-3318

From: bill glasgow [mailto:bglasgow@rmkmarch.com]
Sent: Tuesday, July 10, 2007 11:25 AM
To: Adamsko, Linda M.
Subject: RE: Senior Kitchen Site

Hi Linda,

3:00 sounds good for me and Mark.

Thanks

Bill

From: Adamsko, Linda M. [mailto:LAdamsko@cabq.gov]
Sent: Friday, July 06, 2007 10:02 AM
To: bill glasgow
Subject: FW: Senior Kitchen Site

From: Adamsko, Linda M.
Sent: Friday, July 06, 2007 9:52 AM
To: Hise, Blanca B.; Bingham, Brad L.; 'bglasgow@rkkmarch.com'
Cc: Wardlaw, Rebecca E.; Sanchez, Teresa S.; Baca, John R.
Subject: Senior Kitchen Site

Greetings all. I would like to have a meeting on Friday, July 13 to discuss the drainage pond south of the senior kitchen parcel. PM is best for me, but I can arrange my schedule. Let me pull 3:00 out and see how this works for everyone. Thanx.

Linda Adamsko
City of Albuquerque
Property Manager, Legal Department
(505)768-3318

7/13/2007

Cherne, Curtis

From: Bingham, Brad L.
Sent: Tuesday, July 10, 2007 2:58 PM
To: Cherne, Curtis
Subject: FW: Senior Kitchen Site

From: Adamsko, Linda M.
Sent: Tuesday, July 10, 2007 2:00 PM
To: 'bill glasgow'; Hise, Blanca B.; Sanchez, Teresa S.; Baca, John R.; Wardlaw, Rebecca E.; Bingham, Brad L.
Subject: RE: Senior Kitchen Site

Greetings. Because of scheduling conflicts, I need to move the meeting on Friday, July 13 up to 10:30 at the Office of Senior Affairs. Does this work for all (most)? thanx for your patience.

Linda Adamsko
City of Albuquerque
Property Manager, Legal Department
(505)768-3318

From: bill glasgow [mailto:bglasgow@rmkmarch.com]
Sent: Tuesday, July 10, 2007 11:25 AM
To: Adamsko, Linda M.
Subject: RE: Senior Kitchen Site

Hi Linda,

3:00 sounds good for me and Mark.

Thanks

Bill

From: Adamsko, Linda M. [mailto:LAdamsko@cabq.gov]
Sent: Friday, July 06, 2007 10:02 AM
To: bill glasgow
Subject: FW: Senior Kitchen Site

From: Adamsko, Linda M.
Sent: Friday, July 06, 2007 9:52 AM
To: Hise, Blanca B.; Bingham, Brad L.; 'bglasgow@rmkmarch.com'
Cc: Wardlaw, Rebecca E.; Sanchez, Teresa S.; Baca, John R.

7/13/2007

Subject: Senior Kitchen Site

Greetings all. I would like to have a meeting on Friday, July 13 to discuss the drainage pond south of the senior kitchen parcel. PM is best for me, but I can arrange my schedule. Let me pull 3:00 out and see how this works for everyone. Thanx.

Linda Adamsko
City of Albuquerque
Property Manager, Legal Department
(505)768-3318

7/13/2007

Cherne, Curtis

From: Baca, Barbara C.
Sent: Tuesday, September 12, 2006 8:04 AM
To: Cherne, Curtis
Subject: Re: Fw: Request for Information-lot 7

Curtis,

Sorry about the late response, I was out of the office the last few days. Can you put the copies in interoffice mail or do we need to pick it up? Just let me know where and we can send someone over if that works better. Thanks. Barbara

Curtis Cherne/PLN/CABQ

09/07/2006 03:54 PM

To

Barbara C. Baca/SENIOR AFFAIRS/C/

cc

Subject

Re: Fw: Request for Information-lot 7 [↑](#)

Barbara,

I left a voice mail yesterday. The original plan is a nonstandard size. I made a copy that got most of the lots in the area, but cut off some notes. Let me know when someone can pick it up.

Curtis

Barbara C. Baca/SENIOR AFFAIRS/CABQ

09/06/2006 08:51 AM

To

Curtis Cherne/PLN/CABQ@COA

cc

Subject

Re: Fw: Request for Information-lot 7 [↑](#)

Hi Curtis,

Thanks for the information. Can we get a copy of the Grading and Drainage Master Plan? Let me know, and we can have someone pick it up. Thank you.

Barbara

Curtis Cherne/PLN/CABQ

09/05/2006 10:21 AM

To

Barbara C. Baca/SENIOR AFFAIRS/C.

cc

Brad L. Bingham/PWD/CABQ@COA, I

Subject

Fw: Request for Information-lot 7

Barbara,

Per the Broadway Industrial Center Grading and Drainage Master Plan, Lot 7 was designated for ponding run-off from Lots 7, 8,9 and 10 which also includes run-off from I-25. The pond is required to be 3.06 acre-ft with an allowable run-off of 14.32 cfs. 3.06 acre-ft is a pond approximately 250 ft x 150 ft x 3.6 ft deep, which is about 1/2 the lot. The pond could be made deeper which would require less area. Another alternative is to pond the water below ground and a parking lot (not a building) could be put on top. Underground storage systems are relatively expensive.

In addition to earthwork, some piping would also be required.

Curtis Cherne
Engineering Associate
DBS-Hydrology
Planning Dept.

----- Forwarded by Curtis Cherne/PLN/CABQ on 09/05/2006 10:01 AM -----

Brad L. Bingham/PWD/CABQ

09/05/2006 09:38 AM

To

Curtis Cherne/PLN/CABQ@COA

cc

Subject

Fw: Request for Information

Curtis, could you please look this up for me, thx

----- Forwarded by Brad L. Bingham/PWD/CABQ on 09/05/2006 09:37 AM -----

Barbara C. Baca/SENIOR AFFAIRS/CABQ

09/05/2006 08:56 AM

To

Brad L. Bingham/PWD/CABQ@COA,

cc

Clara Maldonado@Exchange@COA

Subject

Fw: Request for Information

Good Morning Brad and Kristal,

Please see my email below requesting information on a piece of property the Department of Senior Affairs is interested in purchasing. The details of the property are in the email below. Please let me know how I need to proceed. Can I set up an appointment with you to discuss drainage issues? We are in a hurry to have Real Property pursue acquisition, so your initial review would be very helpful. I can be reached at 764-6406. Thank you.

Barbara Baca

----- Forwarded by Barbara C. Baca/SENIOR AFFAIRS/CABQ on 09/05/2006 08:51 AM -----

Dan W. Hogan@Exchange

09/05/2006 08:47 AM

To Barbara C. Baca/SENIOR AFFAIRS/C
cc Brad L. Bingham/PWD/CABQ@COA,
Subject RE: Request for Information

Barbara,

I hate to send you away but for consistency you should probably be working with the group that will ultimately be reviewing this. They are the Planning/Hydrology folks and are located at One Stop. You probably know Brad Bingham (924-3986), Kristal Metro (924-3981) is a key person under Brad and is usually a little easier to contact.

Thanks,
Dan Hogan
COA, DMD, Storm Drainage
768-2778

From: Baca, Barbara C.
Sent: Friday, September 01, 2006 9:03 AM
To: Hogan, Dan W.
Subject: Request for Information
Importance: High

Hi Dan!

I would like to ask for your expertise on some property that the Department of Senior Affairs is interested in purchasing. The property is located at 2520 Karsten Court SE, Lot 7 Plat for Broadway Industrial Center Subdivision Unit 3 containing 3.0844 acres. (Zone Atlas page M-14-Z)

We already own the adjacent property (Lot 6) immediately to the west. Your staff did review this property before it was purchased and it was determined that the pond on that piece was not required because of the drainage improvements that had been done in the area. My questions is what are the drainage requirements on the new piece? There is currently a large ponding area and we are wanting to know how much "buildable" property is available on the site. I would be happy to meet with you on site if needed. Please give me a call at 764-6406.

Thank you very much.

Barbara

List of Scanned Files: See Hydrology Staff

G-18/D034
G-18/D036
G-19/D004
G-19/D022
G-19/D022A
G-19/D023
G-20/D001
G-20/D004A
G-20/D014A
G-20/D023
G-20/D025
G-20/D029
G-20/D030
G-20/D031
G-20/D035
G-20/D039
G-21/D007A
G-21/D012C
G-21/D012C1
G-21/D012E
G-21/D012G
G-21/D025
G-21/D031
G-21/D039
G-22/D008A
G-22/D017
G-22/D018
G-22/D019
G-22/D020
H-09/D001A
H-09/D001A1
H-09/D001B
H-09/D001C
H-09/D001D
H-09/D001D1
H-09/D001D2
H-09/D001F
H-10/D004
H-10/D007
H-10/D007A
H-10/D009
H-11/D009
H-11/D009A
H-11/D010
H-14/D071
H-15/D004
H-15/D037
H-15/D040A
H-15/D045
H-16/D030
H-16/D091
H-16/D093



New Address Search

Copyright ©1994- City of Albuquerque. All rights reserved.
Official website for the City of Albuquerque www.cabq.gov

Albuquerque - Official City Website

Address Query

Search Results

The following address was the closest match:

City Council District: 3 - BENTON

New Mexico State Legislature Districts
NM House of Representatives: 14 ⓘ
NM Senate: 14 ⓘ

School Districts

Elementary: DOLORES GONZALES
Middle: WASHINGTON
High School: ALBUQUERQUE

Neighborhood Association: BARELAS

Zoning: SU-2
Zoning Description: R-1

City Platting Information

Lot: A
Block: 0000
Subdivision: SENIOR CITIZENS MULTI-SERVICE CENTER

Flood Zone:

For floodplain information, please contact the City of Albuquerque's Floodplain Manager at 924-3986 or email bbingham@cabq.gov

Police Beat/Area Command: 221 / VALLEY
Jurisdiction: ALBUQUERQUE
Zone Atlas Page: K14 (opens in new window)

Ownership Data from Bernalillo County Assessor ⓘ

(County Assessor data updated to November 2006)

Name: CITY OF ALBUQUERQUE
Address: PO BOX 1293
Address: ALBUQUERQUE NM 87103 1293
UPC: 101405704122932315
Tax Year: 2007
Tax District: A1AM
Legal Description: TRACT 'A' SUMMARY PLAT SENIOR CITIZENS MULTI-SERVICE CONT 1.5932 AC
Property Class: C
Document Number: 77447 072577
Lot Size (Acres): 1.62035736

[Open Advanced Map Viewer in a new window](#)